# County of Santa Clara

## Department of Planning and Development

County Government Center, East Wing, 7th Floor 70 West Hedding Street San Jose, CA 95110 Phone: (408) 299-5700 www.sccplandev.org



For information on Permit Applications and the County's InSite Public Portal please use this link

https://www.sccgov.org/sites/dp d/Iwantto/Permits/Pages/Devel opmentPermitApplications.aspx

The Permit Card must be onsite at all times.

For information on scheduling inspections visit our website at <u>https://plandev.sccgov.org/ab</u> <u>out-us/building-</u> <u>inspection/inspection</u>



Follow the link do download a PDF copy of the The Smoke detector/CO alarm affidavit <u>https://stgenpln.blob.core.wi</u> ndows.net/document/Affidav it\_Smoke\_CO\_Alarm.pdf

# **Bulletin #BL006- Residential Pool Demolition Projects**

#### PERMIT APPLICATION REQUIREMENTS

- Location of the pool area to be demolished and setbacks to property lines.
- Distance to nearby remaining structures, such as detached garage, septic tank, or other accessory structure. Label all the structures.
- Non-buildable area If the post-demolition area is to become a non-buildable area, delineate the non-buildable area on the Plot Plan.
- Buildable area If the post-demolition area is to become buildable, you must provide the following two items: -
  - A Demolition, Drainage, and Compaction Plan prepared and wet stamped by a state- licensed engineer –
  - A completed Special Inspection Form that designates the supervising engineer or Special Inspection Agency that will both conduct the backfill compaction observation and provide a compaction report to the Building Division, declaring the abated area as buildable.

### **INSPECTION REQUIREMENTS**

For most pool demolition projects there are typically two inspections required

- 1. SP04 Pool Demolition
  - a. Provide holes (approx. 2'x2') in the gunite to allow drainage at the deep and shallow ends of the pool
  - b. The natural gas line and electrical wiring serving the pool and pool equipment must be capped off as part of the demolition process. This step will be verified during inspection.
- 2. FI01 Project Complete
  - a. The pool must be completely backfilled.
  - b. For engineered backfill a compaction report from a licensed geology engineering or special inspection agency must be provided.
  - c. A smoke detector/CO alarm affidavit signed by the property owner must be uploaded to the permit record through the Insite Public Portal.