# MODIFICATION TO USE PERMIT AND SITE APPROVAL 0671-17P-17A **PROJECT NAME :**

# ANTIOCHIAN ORTHODOX CHURCH OF THE REDEEMER

PROJECT SITE

ADDRESS: 380 MAGDALENA AVE, LOS ALTOS, CA

# CONTACT

<u>OWNER</u>


ANTIOCHIAN ORTHODOX CHURCH OF THE REDEEMER 380 MAGDALENA DRIVE LOS ALTOS, CA

### ARCHITECT

LPMD ARCHITECTS 1288 KIFER ROAD, SUITE 206 SUNNYVALE, CA. 94086 PHONE (408) 992-0280 FAX (408) 992-0281

CIVIL ENGINEER OSUNA ENGINEERING INC. 117 BERNAL RD. SUITE 70-336 SAN JOSE, CA 95119 PHONE (408) 772-4381 info@osunaengineering.com

# LOCATION MAP



## SCOPE OF WORK IN MODIFICATION :

ADJUST FIRST FLOOR OF FELLOWSHIP HALL TO MOVE OUT OF "DISCOVERED FAULT AREA" ADJUST SECOND FLOOR TO FOLLOW MODIFICATION TO FIRST FLOOR AREA ADJUST EXTERIOR ELEVATIONS DUE TO FAULT MODIFCAITIONS REVISE FRONT EXTERIOR ELEVATIONS TO PROVIDE COVERED WALKWAY ALONG FELLOWSHIP HALL REVISE FRONT AND SIDE EXTERIOR ELEVATIONS TO FOLLOW NEW FOOTPRINT OF FELLOWHIP HALL

### **PROJECT INFORMATION:**

: 380 MAGDALENA AVE, LOS ALTOS HILLS, CA 94024 ADDRESS APN : 331-03-073 LOT SIZE : 92,120 S.F. EXISTING CHURCH STRUCTURE : 6.614 S.F.

PROPOSED FELLOWSHIP STRUCTURE 

1ST FLOOR	FELLOWSHIP HALL ADMINISTRATION OFFICE	12,225 S.F.
2ND FLOOR	DAY CARE /CLASSROOMS	5,409 S.F.
		17,634 S.F.

EXISTING PARKING PROVIDED FUR CHURCH USE:

	4 ACCESSIBLE 22 COMPACT 65 STANDARD
 TOTAL:	91

PARKING REQUIRED FOR FELLOWSHIP HALL:

FELLOWSHIP HALL (A3 OCCUPANCY) : 361 OCCUPANTS/4 = REQUIRED 90.25 < 91 PROVIDED

CLASSROOM/DAYCARE (E OCCUPANCY) CHILDREN (81 CHILDREN/15 = 5.4

STAFF (81 CHILDREN/4) = 20.25

25.65 REQUIRED < 91 REQUIRED

(CHURCH SITE WILL BE UTILIZING SHARED PARKING AS ALL USES ARE NOT OCCUPIED AT SAME TIME)

NEW BUILDING FOOTPRINT: 12,225 S.F. RATIO: 13.32 % OF SITE AREA

LANDSCAPED AREA: EXISTING

**DEVELOPMENT SCHEDULE:** TIME OF COMMENCEMENT OF CONSTRUCTION COMPLETION OF CONSTRUCTION

DEFERRED SUBMITTAL FOR FIRE SPRINKLERS DESIGNED PER NFPA 13 WILL BE REQUIRED AND SUBMITTED TO SANTA CLARA COUNTY FIRE DEPARTMENT FOR APPROVAL DURING BUILDING PERMIT PROCESS

A0 TITLE SHEET A1 SITE PLAN

CIVIL C0 TITLE SHEET C1 CONCEPTUAL GRADING & DRAINAGE PLAN C2.1 CONCEPTUAL GRADING & DRAINAGE PLAN C3 CONSTRUCTION DETAILS C4.1 SANTA CLARA COUNTY BMP SHEET C4.2 SANTA CLARA COUNTY BMP SHEET

DECE	EMBER 2020	PLANNING COMMENTS
-	IURCH O 380 M	IIAN ORTHODOX OF THE REDEEMER MAGDALENA AVE .TOS, CALIFORNIA
Projec Sheet	ct No: : Title:	<b>Date:</b> 10-20-202
	•••••	HIP BUILDIN SHEET
	-	
Sheet		40


# DRAWING INDEX:

ARCHITECTURAL


A2 1ST FLOOR PLAN A3 2ND FLOOR PLAN A4 ELEVATIONS AND SECTIONS

MAY 2020 CHURCH BOARD REVISIONS











ANTIOCHIAN ORTHODOX CHURCH OF THE REDEEMER 380 MAGDALENA AVE LOS ALTOS, CALIFORNIA

MAY 2020 CHURCH BOARD REVISIONS DECEMBER 2020 PLANNING COMMENTS

Project No: Date: 10-20-2020 Sheet Title:




Scale: Sheet No:

**A1** 

**of** 20

Sheets





MAY 2020 CHURCH BOARD REVISIONS

ANTIOCHIAN ORTHODOX CHURCH OF THE REDEEMER 380 MAGDALENA AVE LOS ALTOS, CALIFORNIA

Project No: Sheet Title:

Date: 10-20-2020


# FIRST FLOOR

Scale: Sheet No:

A2

**of** 20

Sheets





MAY 2020 CHURCH BOARD REVISIONS

## ANTIOCHIAN ORTHODOX CHURCH OF THE REDEEMER 380 MAGDALENA AVE LOS ALTOS, CALIFORNIA

Project No: Sheet Title:

Date: 10-20-2020


# SECOND FLOOR

Scale: Sheet No:



Sheets

**of** 20





MAY 2020 CHURCH BOARD REVISIONS

## ANTIOCHIAN ORTHODOX CHURCH OF THE REDEEMER 380 MAGDALENA AVE LOS ALTOS, CALIFORNIA

Project No: Sheet Title:

Date: 10-20-2020

## ELEVATIONS

Scale: Sheet No:

**A4** 

**of** 20

**Sheets** 

#### COUNTY OF SANTA CLARA General Construction Specifications

#### GENERAL CONDITIONS

- ALL CONSTRUCTION WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE SOILS AND/OR GEOTECHNICAL REPORT PREPARED BY: CORNERSTONE EARTH GROUP, 1259 OAKMEAD PARKWAY, SUNNYVALE CA 94085, TEL 408-245-4600, PROJECT NO. 253-4-1 AND DATED FEBRUARY 25, 2019, THIS REPORT IS SUPPLEMENTED BY: 1) THESE PLANS AND SPECIFICATIONS, 2) THE COUNTY OF SANTA CLARA STANDARD DETAILS. 3) THE COUNTY OF SANTA CLARA STANDARD SPECS, 4) STATE OF CALIFORNIA STANDARD DETAILS, 5) STATE OF CALIFORNIA STANDARD SPECIFICATIONS. IN THE EVENT OF CONFLICT THE FORMER SHALL TAKE PRECEDENCE OVER THE LATTER. THE
- PERFORMANCE AND COMPLETION OF ALL WORK MUST BE TO THE SATISFACTION OF THE COUNTY. DEVELOPER IS RESPONSIBLE FOR INSTALLATION OF THE IMPROVEMENTS SHOWN
- ON THESE PLANS AND HE OR HIS SUCCESSOR PROPERTY OWNERS ARE RESPONSIBLE FOR THEIR CONTINUED MAINTENANCE. DEVELOPER SHALL BE RESPONSIBLE FOR CORRECTION OF ANY ERRORS OR OMISSIONS IN THESE PLANS. THE COUNTY SHALL BE AUTHORIZED TO REQUIRE DISCONTINUANCE OF ANY WORK AND SUCH CORRECTION AND MODIFICATION OF PLANS AS MAY BE NECESSARY TO COMPLY WITH COUNTY STANDARDS OR
- CONDITIONS OF DEVELOPMENT APPROVAL. DEVELOPER SHALL OBTAIN ENCROACHMENT PERMITS FROM THE SANTA CLARA VALLEY WATER DISTRICT AND CALIFORNIA DEPARTMENT OF TRANSPORTATION WHERE NEEDED. COPIES OF THESE PERMITS SHALL BE KEPT AT THE JOB SITE 4. FOR REVIEW BY THE COUNTY'S INSPECTOR.
- DEVELOPER SHALL REMOVE OR TRIM ALL TREES TO PROVIDE AN UNOBSTRUCTED FIFTEEN (15) FOOT VERTICAL CLEARANCE FOR ROADWAY AREA.
- THIS PLAN AUTHORIZES THE REMOVAL OF ONLY THOSE TREES WITH TRUNK DIAMETERS GREATER THAN 12 INCHES MEASURED 4.5 FEET ABOVE THE GROUND THAT ARE SHOWN TO BE REMOVED UNLESS AN AMENDED PLAN IS APPROVED OR A SEPARATE TREE REMOVAL PERMIT IS OBTAINED FROM THE PLANNING OFFICE. IT IS THE CONTRACTOR'S RESPONSIBILITY TO ENSURE THAT REMOVAL OF ADDITIONAL TREES HAS BEEN PERMITTED.
- DEVELOPER SHALL PROVIDE ADEQUATE DUST CONTROL AS REQUIRED BY THE COUNTY INSPECTOR
- ALL PERSONS MUST COMPLY WITH SECTION 4442 OF THE PUBLIC RESOURCES CODE AND SECTION 13005 OF THE HEALTH AND SAFETY CODE RELATING TO THE USE OF SPARK ARRESTERS. UPON DISCOVERING OR UNEARTHING ANY BURIAL SITE AS EVIDENCED BY
- HUMAN SKELETAL REMAINS OR ARTIFACTS, THE PERSON MAKING SUCH DISCOVERY SHALL IMMEDIATELY NOTIFY THE COUNTY CORONER AT (4008) 454-2520 AND LAND DEVELOPMENT ENGINEERING OFFICE AT (408) 299-5730. NO FURTHER DISTURBANCE OF THE SITE MAY BE MADE EXCEPT AS AUTHORIZED BY THE LAND DEVELOPMENT OFFICE IN ACCORD WITH PROVISIONS OF THIS ORDINANCE (COUNTY ORDINANCE CODE SECTION B6-18).
- THESE PLANS ARE FOR THE WORK DESCRIBED IN THE SCOPE OF WORK ONLY. A SEPARATE PERMIT WILL BE REQUIRED FOR THE SEPTIC LINE CONSTRUCTION. ANY DEVIATION FROM THESE APPROVED PLANS SHALL BE RE-APPROVED IN WRITING BY THE COUNTY ENGINEER PRIOR TO CONSTRUCTION.

#### CONSTRUCTION STAKING

- THE DEVELOPER'S ENGINEER IS RESPONSIBLE FOR THE INITIAL PLACEMENT AND REPLACEMENT OF CONSTRUCTION GRADE STAKES. THE STAKES ARE TO BE ADEQUATELY IDENTIFIED, LOCATED, STABILIZED, ETC. FOR THE CONVENIENCE OF CONTRACTORS. LATERAL OFFSET OF STAKES SET FOR CURBS AND GUTTERS SHALL NOT EXCEED 2 1/2 FEET FROM BACK OF CURB.
- ANY PROPERTY LINE STAKES OR ROAD MONUMENTS DISTURBED DURING CONSTRUCTION SHALL BE REPLACED BY DEVELOPER'S ENGINEER AND LICENSED LAND SURVEYOR.
- PROPERTY LINE STAKING MUST BE PERFORMED BY THE PROJECT ENGINEER OR LAND SURVEYOR TO ESTABLISH OR RE-ESTABLISH THE PROJECT BOUNDARY AND SHALL BE INSPECTED BY THE COUNTY INSPECTOR PRIOR TO THE BEGINNING OF THE WORK.
- ENGINEER OR LAND SURVEYOR AND VERIFIED BY THE COUNTY INSPECTOR PRIOR TO THE COMMENCEMENT OF GRADING.

#### ONSTRUCTION INSPECTION

- CONTRACTOR SHALL NOTIFY PERMIT INSPECTION UNIT, SANTA CLARA COUNTY PRIOR TO COMMENCING WORK AND FOR FINAL INSPECTION OF WORK AND SITE.
- COUNTY REQUIRES A MINIMUM OF 24 HOURS ADVANCE NOTICE FOR
- GENERAL INSPECTION, 48 HOURS FOR ASPHALT CONCRETE INSPECTION. INSPECTION BY SANTA CLARA COUNTY SHALL BE LIMITED TO INSPECTION OF MATERIALS AND PROCESSES OF CONSTRUCTION TO OBSERVE THEIR COMPLIANCE WITH PLANS & SPECIFICATIONS BUT DOES NOT INCLUDE RESPONSIBILITY FOR THE SUPERINTENDENT OF CONSTRUCTION, SITE CONDITIONS, EQUIPMENT OR PERSONNEL. CONTRACTOR SHALL NOTIFY THE COUNTY LAND DEVELOPMENT INSPECTOR AT PHONE (408) 299-6868 AT LEAST 24 HOURS PRIOR TO COMMENCING WORK AND FOR FINAL INSPECTION
- OF WORK AND SITE. DEVELOPER AND/OR HIS AUTHORIZED REPRESENTATIVE MUST SUBMIT WRITTEN REQUEST FOR FINAL INSPECTION AND ACCEPTANCE. SAID REQUEST SHALL BE
- DIRECTED TO THE INSPECTION OFFICE NOTED ON THE PERMIT FORM. THE CONTRACTOR SHALL PROVIDE TO THE COUNTY CONSTRUCTION INSPECTOR WITH PAD ELEVATION AND LOCATION CERTIFICATES, PREPARED BY THE
- PROJECT ENGINEER OR LAND SURVEYOR, PRIOR TO COMMENCEMENT OF THE BUILDING FOUNDATION.

#### ITE PREPARATION (CLEARING AND GRUBBING)

- AREAS TO BE IMPROVED WILL BE REMOVED TO AN AUTHORIZED DISPOSAL SITE ACCESS ROADS AND DRIVEWAYS EXISTING TREES AUTHORIZED FOR REMOVAL, ROOTS, AND FOREIGN MATERIAL IN AS FOLLOWS:
  - PROPOSED ROADWAYS (EITHER PRIVATE OR TO BE DEDICATED TO PUBLIC USE)
  - B) FROM AREAS AFFECTED BY THE PROPOSED GRADING EXCEPT WHERE
- NOTED ON THE PLANS. IT SHALL BE THE RESPONSIBILITY OF THE DEVELOPER TO MOVE OR RELOCATE UTILITY POLES AND OTHER OBSTRUCTIONS IN THE WAY OF CONSTRUCTION.
- TILITY LOCATION, TRENCHING & BACKFILL
- CONTRACTOR SHALL NOTIFY USA (UNDERGROUND SERVICE ALERT) AT 1-800-277-2600 A MINIMUM OF 24 HOURS BEFORE BEGINNING
- UNDERGROUND WORK FOR VERIFICATION OF THE LOCATION OF UNDERGROUND UTILITIES. ACCURATE VERIFICATION AS TO SIZE, LOCATION, AND DEPTH OF EXISTING
- UNDERGROUND CONDUITS OR FACILITIES SHALL BE THE INDIVIDUAL CONTRACTORS RESPONSIBILITY. PLAN LOCATIONS ARE APPROXIMATE AND FOR GENERAL INFORMATION ONLY.
- ALL UNDERGROUND INSTALLATIONS SHALL BE IN PLACE AND THE TRENCH BACKFILLED AND COMPACTED BEFORE PLACING AGGREGATE BASE MATERIAL OR SURFACE STRUCTURES. SURFACING MAY BE DONE IF THE UTILITY COMPANY CONCERNED INDICATES BY LETTER THAT IT WILL BORE. UNLESS SPECIFICALLY AUTHORIZED BY THE COUNTY, GAS AND WATER MAINS SHALL BE INSTALLED OUTSIDE THE PAVED AREAS.
- TRENCH BACKFILL IN EXISTING PAVEMENT AREAS SHALL BE SAND MATERIAL IN ACCORDANCE WITH THE APPLICABLE PROVISIONS OF THE STATE SPECIFICATIONS. THE STRUCTURAL SECTION FOR TRENCH REPLACEMENT SHALL CONSIST OF NOT LESS THAN 12 INCHES OF APPROVED AGGREGATE BASE MATERIAL COMPACTED TO A RELATIVE COMPACTION OF AT LEAST 95% AND 4 INCHES OF HOT ASPHALT CONCRETE PLACED IN TWO LIFTS. TRENCH RESTORATION FOR HIGHER TYPE PAVEMENTS SHALL BE MADE IN KIND OR AS
- DIRECTED BY THE COUNTY TRENCH BACKFILL IN NEW CONSTRUCTION AREAS SHALL BE SAND MATERIAL COMPACTED TO A RELATIVE COMPACTION OF AT LEAST 90%. THE REQUIREMENT FOR SELECT MATERIAL MAY BE WAIVED BY COUNTY IF THE NATIVE SOIL IS SUITABLE FOR USE AS TRENCH BACKFILL BUT THE COMPACTION REQUIREMENTS WILL NOT BE THEREBY WAIVED.
- BACKFILL AND TRENCH RESTORATION REQUIREMENTS SHALL APPLY AS MINIMUM STANDARDS TO ALL UNDERGROUND FACILITIES INSTALLED BY OTHER FIRMS OR PUBLIC AGENCIES.

#### ETAINING WALLS

- REINFORCED CONCRETE AND CONCRETE MASONRY UNIT RETAINING WALLS SHALL HAVE FOUNDATION AND REINFORCEMENT INSPECTED BY THE COUNTY ENGINEERING CONTINUAL CONTROL OF THE COUNTY INSPECTOR. INSPECTOR AND ENGINEER OF RECORD PRIOR TO POURING THE FOUNDATION AND FORMING THE WALL
- SEGMENTAL BLOCK RETAINING WALLS SHALL HAVE FOUNDATION AND REINFORCEMENT INSPECTED BY THE COUNTY ENGINEERING INSPECTOR.

#### GRADING

- 1. EXCAVATED MATERIAL SHALL BE PLACED IN THE FILL AREAS DESIGNATED OR WATER ALL ACTIVE CONSTRUCTION AREAS AT LEAST TWICE DAILY. COVER ALL TRUCKS HAULING SOIL, SAND, AND OTHER LOOSE MATERIALS OR SHALL BE HAULED AWAY FROM THE SITE TO A COUNTY APPROVED DISPOSAL SITE. WHERE FILL MATERIAL IS TO BE PLACED ON NATURAL GROUND, IS SHALL REQUIRE ALL TRUCKS TO MAINTAIN AT LEAST TWO FEET OF FREEBOARD. BE STRIPPED OF ALL VEGETATION. TO ACHIEVE A PROPER BOND WITH THE 3. PAVE, APPLY WATER THREE TIMES DAILY, OR APPLY (NON-TOXIC) SOIL FILL MATERIAL, THE SURFACE OF THE GROUND SHALL BE SCARIFIED TO DEPTH STABILIZERS ON ALL UNPAVED ACCESS ROADS, PARKING AREAS AND STAGING OF 6" BEFORE FILL IS PLACED. WHERE NATURAL GROUND IS STEEPER THAN AREAS AT CONSTRUCTION SITES. 5:1, IT SHALL BE BENCHED AND THE FILL KEYED IN TO ACHIEVE STABILITY. 4. SWEEP DAILY (WITH WATER SWEEPERS) ALL PAVED ACCESS ROADS, PARKING WHERE NEW FILL IS TO BE PLACED ON EXISTING FILL THE EXISTING FILL SHALL AREAS AND STAGING AREAS AT CONSTRUCTION SITES. THE USE OF DRY BE REMOVED UNTIL MATERIAL COMPACTED TO 90% RELATIVE COMPACTION IS POWDER SWEEPING IS PROHIBITED. EXPOSED. THEN THE NEW FILL MATERIAL SHALL BE PLACED AS PER THESE SWEEP STREETS DAILY (WITH WATER SWEEPERS) IF VISIBLE SOIL MATERIAL IS CONSTRUCTION NOTES. FILL MATERIAL SHALL BE PLACED IN UNIFORM LIFTS CARRIED ONTO ADJACENT PUBLIC STREETS. THE USE OF DRY POWDER NOT EXCEEDING 6" IN UNCOMPACTED THICKNESS. BEFORE COMPACTION BEGINS, SWEEPING IS PROHIBITED THE FILL SHALL BE BROUGHT TO A WATER CONTENT THAT WILL PERMIT 6. ALL CONSTRUCTION VEHICLES, EQUIPMENT AND DELIVERY TRUCKS SHALL PROPER COMPACTION BY EITHER 1) AERATING THE FILL IF IT IS TOO WET OR HAVE A MAXIMUM IDLING TIME OF 5 MINUTES (AS REQUIRED BY THE 2) MOISTENING THE FILL WITH WATER IF IT IS TOO DRY. EACH LIFT SHALL BE CALIFORNIA AIRBORNE TOXIC CONTROL MEASURE TITLE 13, SECTION 2485 OF THOROUGHLY MIXED BEFORE COMPACTION TO ENSURE A UNIFORM DISTRIBUTION CALIFORNIA CODE OF REGULATIONS (CCR)). ENGINES SHALL BE SHUT OFF IF OF MOISTURE. CONSTRUCTION REQUIRES LONGER IDLING TIME UNLESS NECESSARY FOR
- EXCESS CUT MATERIAL SHALL NOT BE SPREAD OR STOCKPILED ON THE SITE. SURPLUS EARTH FILL MATERIAL SHALL BE PLACED IN A SINGLE (8" MAX) THICK LAYER COMPACTED TO WITHSTAND WEATHERING IN THE AREA(S) DELINEATED ON THE PLAN.
- NO ORGANIC MATERIAL SHALL BE PLACED IN ANY FILL. NO TREES SHALL BE REMOVED OUTSIDE OF CUT, FILL OR ROADWAY AREAS. THE UPPER 6" OF SUBGRADE BELOW DRIVEWAY ACCESS ROAD OR PARKING AREA SHALL BE COMPACTED TO 95% OF MAXIMUM DENSITY.
- MAXIMUM CUT SLOPE SHALL BE 2 HORIZONTAL TO 1 VERTICAL. MAXIMUM FILL SLOPE SHALL BE 2 HORIZONTAL TO 1 VERTICAL EARTHWORK QUANTITIES

		EARI	HWORK !	QUANTITIES						
	DESCRIPTION	EARTH	IWORK QUA	ANTITIES ALL	EARTH QUAN EXCLUDIN	TITIES	MAXIMUM DEPTHS			
		CUT (-)	FILL (+)	EXEMPT?	CUT (-)	FILL (+)	CUT (-)	FILL (+)		
		CY	CY	YES/NO	CY	CY	FT	FT		
BUILDING EXEMPT	MAIN BUILDING PAD	1,882	223	YES			13.4	1.1		
SITE	PARKING AND DRIVEWAY	739	0	NO	739	0	0.0	2.7		
	BIORETENTION POND	59	0	NO	59	0	-1.5	0.0		
WORK	WALKWAYS & LANDSCAPE	484	217	NO	484	217	-1.5	4.0		
	TOTALS:		TOTALS:		440		1,282 217		<- EXEMPT TOTALS	
TOTAL NET IMPORT: IMPORT (+) / EXPORT (-)		-2,	724	CUBIC YARDS (IN-PLACE)	-1,065		CUBIC YARDS (IN-PLACE)			

EXCESS MATERIAL SHALL BE OFF HAULED TO A COUNTY APPROVED DUMP

- NOTIFY SOILS ENGINEER TWO (2) DAYS PRIOR TO COMMENCEMENT OF ANY GRADING WORK TO COORDINATE THE WORK IN THE FIELD.
- 8. ALL MATERIALS FOR FILL SHOULD BE APPROVED BY THE SOILS ENGINEER BEFORE IT IS BROUGHT TO THE SITE. 9. THE UPPER 6" OF THE SUBGRADE SOIL SHALL BE SCARIFIED, MOISTURE
- CONDITIONED AND COMPACTED TO A MINIMUM RELATIVE COMPACTION OF 95% 10. ALL AGGREGATE BASE MATERIAL SHALL BE COMPACTED TO A MINIMUM 95%
- RELATIVE COMPACTION. 11. THE GEOTECHNICAL PLAN REVIEW LETTER MUST BE REVIEWED AND APPROVED BY THE COUNTY GEOLOGIST PRIOR TO FINAL APPROVAL BY THE COUNTY ENGINEER FOR BUILDING OCCUPANCY.
- 12. THE PROJECT GEOTECHNICAL ENGINEER SHALL PERFORM COMPACTION TESTING AND PRESENT THE RESULTS TO THE COUNTY ENGINEERING INSPECTOR PRIOR TO THE CONSTRUCTION OF ANY PAVED AREA.
- 13. GRADING WORK BETWEEN OCTOBER 15TH AND APRIL 15TH IS AT THE DISCRETION OF THE SANTA CLARA COUNTY GRADING OFFICIAL.
- 14. TOTAL DISTURBED AREA FOR THE PROJECT
- 15. WDID NO. N/A PROPER CONSTRUCTION STAKES SHALL BE SET IN THE FIELD BY THE PROJECT 16. THE INSPECTOR MAY VERIFY THAT A VALID NOTICE OF INTENT (NOI) HAS BEEN ISSUED BY THE STATE AND THAT A CURRENT AND UP TO DATE STORM WATER POLLUTION PREVENTION PLAN (SWPPP) IS AVAILABLE ON SITE.

#### TREE PROTECTION

- 1. FOR ALL TREES TO BE RETAINED WITH A CANOPY IN THE DEVELOPMENT AREA OR INTERFACES WITH THE LIMITS OF GRADING FOR ALL PROPOSED DEVELOPMENT ON SITE THE TREES SHALL BE PROTECTED BY THE PLACEMEN OF RIGID TREE PROTECTIVE FENCING, CONSISTENT WITH THE COUNTY INTEGRATED LANDSCAPE GUIDELINES, AND INCLUDE THE FOLLOWING:
- FENCING SHOULD BE PLACED ALONG THE OUTSIDE EDGE OF THE DRIPLINE OF THE TREE OR GROVE OF TREES. THE FENCING SHALL BE MAINTAINED THROUGHOUT THE SITE
- CONSTRUCTION PERIOD AND SHALL BE INSPECTED PERIODICALLY FOR DAMAGE AND PROPER FUNCTION. FENCING SHALL BE REPAIRED, AS NECESSARY, TO PROVIDE A PHYSICAL
- BARRIER FROM CONSTRUCTION ACTIVITIES. SIGNAGE STATING, "WARNING- THIS FENCING SHALL NOT BE REMOVED WITHOUT PERMISSION FROM THE SANTA CLARA COUNTY PLANNING
- OFFICE (408) 299-5770. COUNTY OF SANTA CLARA TREE PROTECTION MEASURES MAY BE FOUND AT
- http://www.sccplanning.gov." SHALL BE PLACED ON THE TREE PROTECTIVE FENCING UNTIL FINAL OCCUPANCY. PRIOR TO COMMENCEMENT OF ANY CONSTRUCTION ACTIVITY, TREE PROTECTIVE
- FENCING SHALL BE SECURELY IN PLACED AND INSPECTED BY THE LAND DEVELOPMENT ENGINEERING INSPECTOR.
- SEE EXISTING TREE PROTECTION DETAILS FOR MORE INFORMATION.

- A) TO A MINIMUM DEPTH OF TWO FEET BELOW THE FINISHED GRADE OF 1. DRIVEWAY LOCATIONS SHALL BE AS SHOWN ON THE IMPROVEMENT PLANS WITH CENTERLINE STATIONING. THE MINIMUM CONCRETE THICKNESS SHALL BE 6 INCHES THROUGHOUT (WITH A MAXIMUM APPROACH SLOPE OF 1 1/4 INCHES PER FOOT
  - ALL DRIVEWAY OR COMMON ACCESS ROAD SECTIONS IN EXCESS OF 15 PERMIT CAS000004/ ORDER NO. 2013-0001-DWQ. LONGITUDINAL SLOPE MUST BE PAVED WITH A MINIMUM 2-INCH ASPHALT LIFT DROP INLETS SHALL BE COUNTY STANDARD TYPE 5 UNLESS OTHERWISE NOTED OR FULL DEPTH CONCRETE LIFT PRIOR TO ANY COMBUSTIBLE FRAMING. ON THE PLANS. THE DEVELOPER'S ENGINEER SHALL BE RESPONSIBLE FOR THE 3. THE OWNER AND PRIME CONTRACTOR ARE RESPONSIBLE FOR MAINTAINING PROPER LOCATION OF DROP INLETS. WHERE STREET PROFILE GRADE EXCEEDS 6% DROP INLETS SHALL BE SET AT 500 ANGLE CURB LINE TO ACCEPT WATER
  - PROJECT SITE ACCESS AND NEIGHBORHOOD ACCESS FOR EMERGENCY VEHICLES AND LOCAL RESIDENTS.
  - 4. ROADWAYS DESIGNATED AS NOT COUNTY MAINTAINED ROADS AS SHOWN ON THE PLAN WILL NOT BE ELIGIBLE FOR COUNTY MAINTENANCE UNTIL THE ROADWAYS ARE IMPROVED (AT NO COST TO THE COUNTY) TO THE PUBLIC MAINTENANCE ROAD STANDARDS APPROVED BY THE BOARD OF SUPERVISORS AND IN EFFECT AT SUCH TIME THAT THE ROADWAYS ARE CONSIDERED FOR ACCEPTANCE INTO THE COUNTY'S ROAD SYSTEM. ALL WORK IN THE COUNTY ROAD RIGHT-OF-WAY REQUIRES AN
  - ENCROACHMENT PERMIT FROM THE ROADS AND AIRPORTS DEPARTMENT. EACH INDIVIDUAL ACTIVITY REQUIRES A SEPARATE PERMIT - I.E. CABLE, ELECTRICAL, GAS. SEWER, WATER, RETAINING WALLS, DRIVEWAY APPROACHES, FENCES, LANDSCAPING, TREE REMOVAL, STORM DRAINAGE IMPROVEMENTS. ETC ..

TREET LIGHTING

1. PACIFIC GAS & ELECTRIC ELECTROLIER SERVICE FEE SHALL BE PAID BY THE DEVELOPER AND/OR HIS AUTHORIZED REPRESENTATIVE.

SANITARY SEWER

- THE SANITARY SEWER AND WATER UTILITIES SHOWN ON THESE PLANS ARE NOT PART OF THIS GRADING PERMIT AND ARE SHOWN FOR REFERENCE ONLY.
- ALL MATERIALS AND METHODS OF CONSTRUCTION OF SANITARY SEWERS SHALL THE AS-BUILT PLANS MUST BE FURNISHED TO THE COUNTY ENGINEER CONFORM TO THE SPECIFICATIONS OF THE JURISDICTION INVOLVED. INSPECTION AFTERCONSTRUCTION. OF SANITARY SEWER WORK SHALL BE DONE BY SAID JURISDICTION.

#### PORTLAND CEMENT CONCRETE

1. CONCRETE USED FOR STRUCTURAL PURPOSES SHALL BE CLASS "A" (6 SACK PER CUBIC YARD) AS SPECIFIED IN THE STATE STANDARD SPECIFICATIONS. CONCRETE PLACED MUST DEVELOP A MINIMUM STRENGTH FACTOR OF 2800 PSI IN A SEVEN-DAY PERIOD. THE CONCRETE MIX DESIGN SHALL BE UNDER THE

#### AIR QUALITY, LANDSCAPING AND EROSION CONTROL

- PROPER OPERATION OF THE VEHICLE. 7. ALL VEHICLE SPEEDS ON UNPAVED ROADS SHALL BE LIMITED TO 15 MILES PER HOUR. 8. ALL CONSTRUCTION EQUIPMENT SHALL BE MAINTAINED AND PROPERLY TUNED IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS. ALL EQUIPMENT
- SHALL BE CHECKED BY A CERTIFIED MECHANIC AND DETERMINED TO BE RUNNING IN PROPER CONDITION PRIOR TO OPERATION. 9. POST A SIGN THAT IS AT LEAST 32 SQUARE FEET MINIMUM 2 INCHES LETTER HEIGHT VISIBLE NEAR THE ENTRANCE OF CONSTRUCTION SITE THAT IDENTIFIES THE FOLLOWING REQUIREMENTS. OBTAIN ENCROACHMENT PERMIT FOR SIGN FROM ROADS DEPARTMENT OR OTHER APPLICABLE AGENCY IF REQUIRED.
  - A. 15 MILES PER HOUR (MPH) SPEED LIMIT B. 5 MINUTES MAXIMUM IDLING TIME OF VEHICLES
- TELEPHONE NUMBER TO CONTACT THE BAY AREA AIR QUALITY MANAGEMENT DISTRICT REGARDING DUST COMPLAINTS. NOTE PHONE NUMBER OF THE BAY AREA AIR QUALITY MANAGEMENT DISTRICT AIR POLLUTION COMPLAIN HOTLINE OF 1-800-334-6367
- 10. ALL FILL SLOPES SHALL BE COMPACTED AND LEFT IN A SMOOTH AND FIRM CONDITION CAPABLE OF WITHSTANDING WEATHERING. 11. ALL EXPOSED DISTURBED AREAS SHALL BE SEEDED WITH BROME SEED SPREAD AT THE RATE OF 5 LB. PER 1000 SQUARE FEET (OR APPROVED EQUAL). SEEDING AND WATERING SHALL BE MAINTAINED AS REQUIRED TO ENSURE GROWTH.
- 12. ALL DITCHES SHALL BE LINED PER COUNTY STANDARD SD8. 13. ALL STORM DRAINAGE STRUCTURES SHALL BE INSTALLED WITH EFFECTIVE ENTRANCE & OUTFALL EROSION CONTROLS E.G. SACKED CONCRETE RIP-RAP. ENERGY DISSIPATERS SHALL BE INSTALLED AT ALL DITCH OUTFALLS. WHERE OUTFALLS ARE NOT INTO AN EXISTING CREEK OR WATER COURSE, RUNOFF SHALL BE RELEASED TO SHEET FLOW.
- 14. PRIOR TO GRADING COMPLETION AND RELEASE OF THE BOND. ALL GRADED AREAS SHALL BE RESEEDED IN CONFORMANCE WITH THE COUNTY GRADING ORDINANCE TO MINIMIZE THE VISUAL IMPACTS OF THE GRADE SLOPES AND REDUCE THE POTENTIAL FOR EROSION OF THE SUBJECT SITE. 15. PERMANENT LANDSCAPING SHOWN ON THE ATTACHED LANDSCAPE PLAN MUST BE INSTALLED AND FIELD APPROVED BY THE COUNTY PLANNING OFFICE PRIOR
- TO FINAL APPROVAL BY THE COUNTY ENGINEER, AND FINAL OCCUPANCY RELEASE BY THE BUILDING INSPECTION OFFICE. 16. THE OWNER SHALL PREPARE AND PRESENT A WINTERIZATION REPORT TO THE COUNTY INSPECTOR FOR REVIEW PRIOR TO OCTOBER 15TH OF EVERY YEAR. 17. THE OWNER, CONTRACTOR, AND ANY PERSON PERFORMING CONSTRUCTION ACTIVITIES SHALL INSTALL AND MAINTAIN CONSTRUCTION BEST MANAGEMENT PRACTICES (BMPS) ON THE PROJECT SITE AND WITHIN THE SANTA CLARA COUNTY ROAD RIGHT-OF-WAY THROUGHOUT THE DURATION OF THE CONSTRUCTION AND UNTIL THE ESTABLISHMENT OF PERMANENT STABILIZATION AND SEDIMENT CONTROL TO PREVENT THE DISCHARGE OF POLLUTANTS INCLUDING SEDIMENT, CONSTRUCTION MATERIALS, EXCAVATED MATERIALS, AND
- WASTE INTO THE SANTA CLARA COUNTY RIGHT-OF-WAY. STORM SEWER WATERWAYS, ROADWAY INFRASTRUCTURE. BMPS SHALL INCLUDE, BUT NOT BE LIMITED TO THE FOLLOWING: A. PREVENTION OF POLLUTANTS IN STORM WATER DISCHARGES FROM THE CONSTRUCTION SITE AND THE CONTRACTOR'S MATERIAL AND
- EQUIPMENT LAYDOWN / STAGING AREAS. B. PREVENTION OF TRACKING OF MUD, DIRT, AND CONSTRUCTION
- MATERIALS ONTO THE PUBLIC ROAD RIGHT-OF-WAY. C. PREVENTION OF DISCHARGE OF WATER RUN-OFF DURING DRY AND WET WEATHER CONDITIONS ONTO THE PUBLIC ROAD RIGHT-OF-WAY 18. THE OWNER, CONTRACTOR, AND ANY PERSON PERFORMING CONSTRUCTION ACTIVITIES SHALL ENSURE THAT ALL TEMPORARY CONSTRUCTION FACILITIES, INCLUDING BUT NOT LIMITED TO CONSTRUCTION MATERIALS, DELIVERIES, HAZARDOUS AND NON-HAZARDOUS MATERIAL STORAGE, EQUIPMENT, TOOLS, PORTABLE TOILETS, CONCRETE WASHOUT, GARBAGE CONTAINERS, LAYDOWN YARDS. SECONDARY CONTAINMENT AREAS, ETC. ARE LOCATED OUTSIDE THE SANTA CLARA COUNTY ROAD RIGHT-OF-WAY. 19. EROSION CONTROL PLAN IS A GUIDE AND SHALL BE AMENDED AS NECESSARY TO PREVENT EROSION AND ILLICIT DISCHARGES ON A YEAR AROUND BASIS.
- DEPENDING ON THE SEASON, WEATHER, AND FIELD CONDITIONS. EROSION CONTROL MEASURES IN ADDITION TO THOSE NOTED IN THE PERMITTED PLANS MAY BE NECESSARY. FAILURE TO INSTALL SITE SITE AND SITUATIONALY APPROPRIATE EROSION CONTROL MEASURES MAY RESULT IN VIOLATIONS, FINES, AND A STOPPAGE OF WORK.

#### STORM DRAINAGE AND STORMWATER MANAGEMENT

- DEVELOPER IS RESPONSIBLE FOR ALL NECESSARY DRAINAGE FACILITIES WHETHER SHOWN ON THE PLANS OR NOT AND HE OR HIS SUCCESSOR PROPERTY OWNERS ARE RESPONSIBLE FOR THE ADEQUACY AND CONTINUED MAINTENANCE OF THESE FACILITIES IN A MANNER WHICH WILL PRECLUDE ANY HAZARD TO LIFE, HEALTH, OR DAMAGE TO ADJOINING PROPERTY, CONSISTENT WITH NPDES PERMIT CAS612008 / ORDER NO. R2-2009-0047 AND NPDES
- OR AS SHOWN ON THE PLANS. WHERE CULVERTS ARE INSTALLED THE DEVELOPER SHALL BE RESPONSIBLE FOR GRADING THE OUTLET DITCH TO DRAIN TO AN EXISTING SWALE OR TO AN
- OPEN AREA FOR SHEET FLOW. 4. UPON INSTALLATION OF DRIVEWAY CONNECTIONS, PROPERTY OWNERS SHALL PROVIDE FOR THE UNINTERRUPTED FLOW OF WATER IN ROADSIDE DITCHES. THE COUNTY SHALL INSPECT UNDERGROUND DRAINAGE IMPROVEMENTS AND STORMWATER MANAGEMENT FEATURES PRIOR TO BACKFILL.

#### AS-BUILT PLANS STATEMEN

THIS IS A TRUE COPY OF THE AS-BUILT PLANS. THERE (\_\_\_\_ WERE) (\_\_\_ WERE NOT) MINOR FIELD CHANGES - MARKED WITH THE SYMBOL (^). THERE (\_\_\_WERE) WERE NOT) PLAN REVISIONS INDICATING SIGNIFICANT CHANGES REVIEWED BY THE COUNTY ENGINEER AND MARKED WITH THE SYMBOL  $\triangle$ .


NOTE: THIS STATEMENT IS TO BE SIGNED BY THE PERSON AUTHORIZED BY THE COUNTY ENGINEER TO PERFORM THE INSPECTION WORK. A REPRODUCIBLE COPYOF

SIGNATURE

#### GEOTECHNICAL ENGINEER OBSERVATION

1. A CONSTRUCTION OBSERVATION LETTER FROM THE RESPONSIBLE GEOTECHNICAL ENGINEER AND ENGINEERING GEOLOGIST DETAILING CONSTRUCTION OBSERVATIONS AND CERTIFYING THAT THE WORK WAS DONE IN ACCORDANCE WITH THE RECOMMENDATIONS IN THE GEOTECHNICAL AND GEOLOGIC REPORTS SHALL BE SUBMITTED PRIOR TO THE GRADING COMPLETION AND RELEASE OF THE BOND.

ROAD:



#### SURVEY MONUMENT PRESERVATION

- 1. THE LANDOWNER / CONTRACTOR MUST PROTECT AND ENSURE THE PERPETUATION OF SURVEY MONUMENTS AFFECTED BY CONSTRUCTION
- ACTIVITIES. 2. PRIOR TO THE START OF CONSTRUCTION, THE CONTRACTOR SHALL LOCATE, STAKE, AND FLAG OR OTHERWISE IDENTIFY WITH PAINT OR OTHER MARKINGS ALL PERMANENT SURVEY MONUMENTS OF RECORD AND ANY UNRECORDED MONUMENTS THAT ARE DISCOVERED THAT ARE WITHIN 50 FEET OF THE CONSTRUCTION ACTIVITY
- 3. THE LANDOWNER, CONTRACTOR AND/OR ANY PERSON PERFORMING CONSTRUCTION ACTIVITIES THAT WILL OR MAY DISTURB AN EXISTING MONUMENT, CORNER STAKE, OR ANY OTHER PERMANENT SURVEYED MONUMENT SHALL CAUSE TO HAVE A LICENSED LAND SURVEYOR OR CIVIL ENGINEER, AUTHORIZED TO PRACTICE SURVEYING, ENSURE THAT A CORNER RECORD AND/OR RECORD OF SURVEY ARE FILED WITH THE COUNTY SURVEYOR'S OFFICE PRIOR TO DISTURBING SAID MONUMENTS AND RESET PERMANENT MONUMENT(S) IN THE SURFACE OF THE NEW CONSTRUCTION OR SET A WITNESS MONUMENT(S) TO PERPETUATE THE LOCATION IF ANY PERMANENT MONUMENT COULD BE DESTROYED, DAMAGED, COVERED, DISTURBED, OR OTHERWISE OBLITERATED. THE LICENSED LAND SURVEYOR OR CIVIL ENGINEER SHALL FILE A CORNER RECORD OR RECORD OF SURVEY WITH COUNTY SURVEYOR PRIOR TO FINAL ACCEPTANCE OF THE PROJECT BY THE LAND DEVELOPMENT ENGINEERING INSPECTOR.

#### ABBREVATIONS

- AC = ASPHALT CONCRETEAD = AREA DRAIN
- BC = BEGIN CURVEBS = BOTTOM OF STAIR
- BU = BUBBLE UP
- BVC = BEGIN VERTICAL CURVE BRW = BOTTOM OF RETAINING WALL
- CB = CATCH BASINCL = CENTERLINE
- CO = CLEANOUT
- DS = DOWNSPOUT WITH SPLASH BOX EC = END CURVE
- ELEV. = ELEVATION EVC = END VERTICAL CURVE
- EX. = EXISTING
- $F/C = FACE \ OF \ CURB$ FF = FINISHED FLOOR ELEVATION
- FH = FIRE HYDRANT
- FL = FLOW LINEGB = GRADE BREAK
- GFF = GARAGE FINISH FLOOR
- HP = HIGH POINTHC = HANDICAP UNIT
- INV = INVFRT

LP = LOW POINTPAD = PAD ELEVATIONPCC = PORTLAND CEMENT CONCRETE PL = PROPERTY LINE PV = PAVEMENT GRADEPVC = POLYVINYL CHLORIDE PIPEPVI = POINT OF VERTICAL INTERSECTION RCP = REINFORCED CONCRETE PIPE ROW = RIGHT OF WAY*S*=.004> *SLOPE* SD = STORM DRAIN SDMH = STORM DRAIN MANHOLE SG = SUBGRADE ELEVATIONSS = SANITARY SEWER SSMH = SANITARY SEWER MANHOLE STA = STATION  $TC = TOP \ OF \ CURB$ TF = TOP OF FENCETRW = TOP OF RETAINING WALL TS = TOP OF STAIRTW = TOP OF WALL VCP = VITRIFIED CLAY PIPE WM = WATER METER WV = WATER VALVE


INSPECTION.

COUNTY OF SANTA CLARA DEPT	. OF ROADS AND AIRPORTS								
ISSUED BY:	DATE:								
ENCROACHMENT PERMIT NO.									

NO WORK SHALL BE DONE IN THE COUNTY'S RIGHT-OF-WAY WITHUOT AN ENCROACHEMENT PERMIT, INCLUDING THE STAGING OF CONSTRUCTION MATERIAL AND THE PLACEMENT OF PORTABLE TOILETS.

#### ENGINEER'S STATEMENT

I HEREBY STATE THAT THESE PLANS ARE IN COMPLIANCE WITH ADOPTED COUN APPROVED TENTATIVE MAP (OR PLAN) AND CONDITIONS OF APPROVAL PERTAIN FILE(S) NO. CONDITIONS OF APPROVAL FILE NO. 671-17P-17A, DATED 8/16 DATE 12/18/20




#### COUNTY ENGINEER'S NOTE

ISSUANCE OF A PERMIT AUTHORIZING CONSTRUCTION DOES NOT RELEASE THE ENGINEER FROM RESPONSIBILITY FOR THE CORRECTION OF ERRORS OR OMISSIO PLANS. IF, DURING THE COURSE OF CONSTRUCTION, THE PUBLIC INTEREST RE (OR DEPARTURE FROM) THE SPECIFICATIONS OF THE PLANS, THE COUNTY SHA TO REQUIRE THE SUSPENSION OF WORK, AND THE NECESSARY MODIFICATION C SPECIFY THE MANNER IN WHICH THE SAME IS TO BE MADE.

CHRISTOPHER L. FREITAS 42107 R.C.E. NO.



\_\_\_\_\_



# PLANNING SUBMITTAL FOR FELLOWSHIP BUII DING


PROJECT NAME: ANTIOCHIAN ORTHODOX CHURCH OF THE REDEEMER

SYMBOL

 $\square$ 

×

 $\boxtimes$ 



#### EXISTING TREE PROTECTION DETAILS


. PRIOR TO THE COMMENCEMENT OF ANY GRADING, TREE PROTECTIVE FENCING SHALL BE IN PLACE IN ACCORDANCE WITH THE TREE PRESERVATION PLAN AND INSPECTED BY A CERTIFIED ARBORIST. THE ARBORIST SHALL MONITOR CONSTRUCTION ACTIVITY TO ENSURE THAT THE TREE PROTECTION MEASURES ARE IMPLEMENTED AND ADHERED TO DURING CONSTRUCTION. THIS CONDITION SHALL BE INCORPORATED INTO THE GRADING PLANS. 2. FENCE SHALL BE MINIMUM 5 FEET TALL CONSTRUCTED OF STURDY MATERIAL (CHAIN-LINK OR EQUIVALENT STRENGTH/ DURABILITY). 3. FENCE SHALL BE SUPPORTED BY VERTICAL POSTS DRIVEN 2 FEET (MIN) INTO THE GROUND AND SPACED NOT MORE THAN 10 FEET APART. 4. TREE FENCING SHALL BE MAINTAINED THROUGHOUT THE SITE DURING THE CONSTRUCTION PERIOD, INSPECTED PERIODICALLY FOR DAMAGE AND PROPER FUNCTION, REPAIRED AS NECESSARY TO PROVIDE A PHYSICAL BARRIER FROM

CONSTRUCTION ACTIVITIES, AND REMAIN IN PLACE UNTIL THE FINAL 5. A SIGN THAT INCLUDES THE WORDS, "WARNING: THIS FENCE SHALL NOT BE

REMOVED WITHOUT THE EXPRESSED PERMISSION OF THE SANTA CLARA COUNTY PLANNING OFFICE," SHALL BE SECURELY ATTACHED TO THE FENCE IN A VISUALLY PROMINENT LOCATION.


COUNTY OF SANTA CLARA


LAND DEVELOPMENT ENGINEERING & SURVEYING





		· · · · · ·	
GRADING / DRAINAGE PERMIT NO.		СО	TITLE SHEET
ISSUED BY: DATE:		C1	CONCEPTUAL GRADING & DRAINAGE PLAN
	CTI	C2.1-C2.2	CONCEPTUAL STORMWATER MANAGEMENT PLAN
	IRU	C3	SECTIONS & DETAILS
TED COUNTY STANDARDS, THE L PERTAINING THERETO DATED	CONSTRUCTION	C4.1-C4.2	COUNTY BMP SHEET 1
<u>ED 8/16/17</u> 70829 R.C.E. NO.	OR C		
6-30-21	L		
EXPIRATION DATE	NOT	ENGINEER	R'S NAME: PORFIRIO OSCAR OSUNA
ASE THE DEVELOPER, PERMITTEE OF & OMISSIONS CONTAINED IN THE EREST REQUIRES A MODIFICATION OF INTY SHALL HAVE THE AUTHORITY CATION OR DEPARTURE AND TO	NNING SUBMITTAL -	ADDRESS PHONE N EMAIL:	: <u>117 BERNAL RD, #70-336</u> <u>SAN JOSE, CA 95119</u> 0. <u>408-772-4381</u> <u>info@osunaengineering.com</u>
EITAS	Γ	Revision 1	APN Sheet
3/31/20 EXPIRATION DATE	<b>L</b>	Revision 2 Revision 3	331-03-073         CO           Co.         File         of           7
NO.:			





NO.	MAINTENANCE ACTIVITIES FOR BIORE MAINTENANCE TASK		FREQUENCY OF TASK
1	REMOVE OBSTRUCTIONS, WEEDS, DEBRIS AND TRASH FROM BIORETEN INLETS AND OUTLETS; AND DISPOSE OF PROPERLY.	NTION AREA AND ITS	QUARTERLY, OR AS NEEDED AFT STORM EVENTS
2	INSPECT BIORETENTION AREA FOR STANDING WATER. IF STANDING WA DRAIN WITHIN 2-3 DAYS, TILL AND REPLACE THE SURFACE BIOTREATME APPROVED SOIL MIX AND REPLANT.		QUARTERLY, OR AS NEEDED AFT STORM EVENTS
3	CHECK UNDERDRAINS FOR CLOGGING. USE THE CLEANOUT RISER TO CUNDERDRAINS.	CLEAN ANY CLOGGED	QUARTERLY, OR AS NEEDED AFT STORM EVENTS
4	MAINTAIN THE IRRIGATION SYSTEM AND ENSURE THAT PLANTS ARE RE CORRECT AMOUNT OF WATER (IF APPLICABLE).	QUARTERLY	
5	ENSURE THAT THE VEGETATION IS HEALTHY AND DENSE ENOUGH TO F AND PROTECT SOILS FROM EROSION. PRUNE AND WEED THE BIORETE AND/OR REPLACE ANY DEAD PLANTS.		ANNUALLY, BEFORE THE WET SEASON BEGINS
6	USE COMPOST AND OTHER NATURAL SOIL AMENDMENTS AND FERTILIZ SYNTHETIC FERTILIZERS, ESPECIALLY IF THE SYSTEM USES AN UNDER		ANNUALLY, BEFORE THE WET SEASON BEGINS
7	CHECK THAT MULCH IS AT APPROPRIATE DEPTH (2 - 3 INCHES PER SOII SPECIFICATIONS) AND REPLENISH AS NECESSARY BEFORE WET SEASO RECOMMENDED THAT 2" – 3" OF ARBOR MULCH BE REAPPLIED EVERY Y	ON BEGINS. IT IS	ANNUALLY, BEFORE THE WET SEASON BEGINS
8	INSPECT THE ENERGY DISSIPATION AT THE INLET TO ENSURE IT IS FUN ADEQUATELY, AND THAT THERE IS NO SCOUR OF THE SURFACE MULCH ACCUMULATED SEDIMENT.		ANNUALLY, BEFORE THE WET SEASON BEGINS
9	INSPECT OVERFLOW PIPE TO ENSURE THAT IT CAN SAFELY CONVEY EX STORM DRAIN. REPAIR OR REPLACE DAMAGED PIPING.	XCESS FLOWS TO A	ANNUALLY, BEFORE THE WET
10	REPLACE BIOTREATMENT SOIL AND MULCH, IF NEEDED. CHECK FOR ST STRUCTURAL FAILURE AND CLOGGED OVERFLOWS. REMOVE TRASH AI DEAD PLANTS.	,	SEASON BEGINS
11	INSPECT BIORETENTION AREA USING THE ATTACHED INSPECTION CHE	CKLIST.	ANNUALLY, BEFORE THE WET SEASON
<ul> <li>PROVI THE R THIS II RATE</li> <li>ONLY INTER TECHI ONE F TIMES</li> <li>PROTE EXCES</li> </ul>	PERVIOUS PAVER REQUIREMENTS TOR OR PERMITEE SHALL: IDE CERTIFICATION FROM THE PAVER MANUFACTURER THAT THE PAVERS MEET REQUIREMENTS OF THE C3 STORMWATER HANDBOOK FOR PERVIOUS PAVERS. NCLUDES, BUT IS NOT LIMITED TO, HAVING A MINIMUM SURFACE INFILTRATION OF 100"/HR WHEN TESTED IN ACCORDANCE WITH ASTM C1701. CONTRACTORS HOLDING CERTIFICATION OF COMPLETION IN THE PLOCKING CONCRETE PAVEMENT INSTITUTES PICP INSTALLER NICIAN COURSE SHALL BE USED TO INSTALL THE PAVERS AND AT LEAST FOREMAN WITH THIS CERTIFICATION MUST BE ON THE JOBSITE AT ALL S DURING CONCRETE PAVER INSTALLATION. ECT THE EXCAVATED AREA FOR PERVIOUS PAVERS FROM SSIVE COMPACTION DUE TO CONSTRUCTION TRAFFIC AND PROTECT THE HED PAVEMENT FROM CONSTRUCTION TRAFFIC.		
	CONCRETI CURB/EDG FOR OVER	AGGREGATE IN OPENING E PAVERS MIN. 3 1/8 IN. (8 E RESTRAINT WITH CUT- FLOW DRAINAGE (CURB 3 COURSE 1 1/2 TO 2 IN. (40 8 AGGREGATE) MM) THICK NO. 57 STONE ADED BASE	0 MM) THICK DUTS SHOWN)
	\`\`\`	LE ON SIDE AND TOP OF \$ 150 MM) THICK NE SUBBASE	SUBBASE

PERMEABLE PAVEMENT WITH FULL

EXFILTRATION TO SOIL SUBGRADE

jËÇ

\_\_\_\_\_

ICPI-68


NO SCALE


SCALE

						TR	REATMENT CO	NTROL MEA	SURE SUMM	IARY TABL	.E							
Drainage Management Area (DMA)	Treatment Control Measure (TCM)	Treatment Type	Drainage Area (s.f.)	Impervious Area (s.f.)	Pervious Area (s.f.)	Bioretention Area Requied (s.f.)	Bioretention Area Provided (s.f.)	Bioretention Lined or Unlined	Disarlaight	Storage Depth Required (ft)	Storage Depth Provided (ft)	# of Cratridges Required	# of Cartridges Provided	Media Type	Cartridge Height (inches)	# of Credit Trees	Treatment Credit (s.f.)	Location
1	1	Bioretention	23,571	16,278	7,293	651	800	Unlined	6	6	6	-	( <b>-</b> )	-	-	-	-	See Plan
2	2	Permeable Pavers	11,941	7,635	4,306	N/A	0	N/A	-	-	-	-	-	-	-	-	-	See Plan
3	N/A	N/A	11,055	508	10,547	N/A	0	N/A	-	-	-	-	-	-	-	-	-	See Plan
4	4	Permeable Pavers	3,545	774	2,771	N/A	0	N/A	-	-	-							See Plan
					0	0		_	_		_	_		_	-			
						-												
		Totals:	50,112	25,195	24,917													
*Sizing for Bio	retention Are	ea Required calcula	ated using the	e Combo Flow a	and Volume N	Nethod												
		SIZING FOR		BASED TRE	EATMENT						SIZING	FOR VOL	UME BAS	ED TRE				
D	A=	<b>1</b> 23571 s.f.								DM	<b>A # 2</b> A= 10359	sf						
Impervious A		16278 s.f.		% Imperviou	sness= 69	0.06%			Impervious Area = 5402 s.f. % Imperviousness (i)= 52.15% Pervious Pavement Area = 4957 s.f.									
MAF MAPg	'site = age =	24 13.9	Corre	ction Factor= 1	1.7266					MAPsit MAPgag	e = 24		Cor	rrection Fa	ctor= 1.726	6		
Clay (D):	-	Sandy Clay (	D):	Clay Lo	am (D):	X			P6(gage):	0.512	in							
Silt Loam/Loa	m (B):		Not Applica	ble (100% Impe	ervious):					P6(site)= P P6(site):	6(gage) x Corro 0.88403							

	SIZING FOR VOLU	ME BASED TREATME	NT		SIZING FO
DMA #	1				DMA # 2
A=	23571 s.f.				A= <u>10359</u> s.f.
Impervious Area =	16278 s.f.	% Imperviousness=	69.06%		Impervious Area = 5402 s.f.
	-				Pervious Pavement Area = 4957 s.f.
MAPsite =	24	Correction Factor= 1.7266			MAPsite = 24
MAPgage =	13.9				MAPgage = 13.9
Clay (D):	Sandy Clay (D):	Clay Loam (D):	X		P6(gage): 0.512 in
Silt Loam/Loam (B):	Not Ap	plicable (100% Impervious):			P6(site)= P6(gage) x Correction
	·				P6(site): 0.88403 in
Are the soils outside the buildin	g footprint graded/compacted	?	YES Yes/No		
		L			Cw= 0.858i^3 – 0.78i^2 + 0.774i + 0.
If yes, and the soil will be compared	acted during site preparation	and grading, the soil infiltration	า		Cw: 0.3531852
rate will be decreased. Modify	your answer to a soil with a low	ver infiltration rate (eg. Silt Lo	am to Clay)		Regression Factor (a)
Modified Soil Type: D					
					Po = a x Cw x P6(site)
S= 2.90%					Po: 0.6129 in.
	Volume for 1% Slope (UBS1		-		
UBS Vo	olume for 15% Slope (UBS15	%) = <u>0.44529719</u> inches (U	se Figure B-5)		Design Volume = $Po x A x 1ft/12$
					Design Volume = 529.085 ft^3
	olume for X% Slope (UBSX		orrected Slope for	r the site)	
Adjusted UBS = Correc	ction Factor (Step 2) x UBSx%	(Step 5)			SELF RE
Adjusted UBS =	0.7390126 inches				
-	ted UBS (Step 6) x Drainage	Area (Step 1) x 1ft/12 inch			
					Poi
Design Volume =	1,451.61 ft^3				
	BO FLOW & VOLUME	<b>BIORETENTION CAI</b>	CULATION		
Total Draina					Minimum Sterage Double - Design V
	ous Area = <u>16,278</u> sq. <sup>·</sup> ous Area = 7,293 sq. <sup>·</sup>				Minimum Storage Depth = Design V
Equivalent Impervi				<b>17,007</b> sq. ft	* Porosity of Class II Permeable
Rainfall Intensity =	0.2 in/hr			17,007 Sq. it	** If value = "No" increase size of
	djusted UBS (Step 6) / Rainfal	Intensity			
	3.6950631 hrs	i interiority			
Estimate the Surfa	ace Area = 720 sq. 1	t (Typically start with Tota	Impervious x 0 03	3)	
Volume of Treate					SOURCE CONTROL MEASURES:
Volume in Pond					
	Ponding = 0.4765092 ft		Ponding = 5.7	inches	1. CONNECT THE FOLLOWING FEATURES TO SANITA
			0	(Round up)	a.POOLS, SPAS, FOUNTAINS. 2. BENEFICIAL LANDSCAPING.
If Depth of Ponding is less than	6" the design can be optimize	ed with a smaller surface area	. (repeat)	, , , , , , , , , , , , , , , , , , , ,	3. USE OF WATER EFFICIENT IRRIGATION SYSTEMS.
					J. UJE VI WATEN EFFICIENT INNIGATION STOLEMO

If Depth of Ponding is greater than 12" a larger surface area will be required. (repeat) If Depth of Ponding is between 6" to 12" this is the range allowable for Bioretention or Flow-Through Planters.





COUNTY FILE NO .:

i^3 – 0.78i^2 + 0.774i + 0.04 .3531852 a = 1.963 (48 hour draw down) egression Factor (a)

Volume = Po x A x 1ft/12in

SELF RETAINING (PERVIOUS PAVEMENT)

orosity of Rock*	Min. Storage Depth Required (in)	Pervious ≥ 1/2 Impervious**
0.40	3.20	Yes

orage Depth = Design Volume (c.f.) / Pervious Pavement Area (s.f.) / rock porosity x 12 in/1 ft

osity of Class II Permeable = 0.4 based on SCVURPPP training. ue = "No" increase size of pervious pavement.

#### <u>SURES:</u>

4. STORM DRAIN LABELING.

LOWING FEATURES TO SANITARY SEWER:

SITE DESIGN MEASURES:


- 1. PROTECT EXISTING TREES, VEGETATION, AND SOIL.
- 2. PRESERVE OPEN SPACE AND NATURAL DRAINAGE PATTERNS. 6. DIRECT RUNOFF FROM ROOFS, SIDEWALKS, PATIOS TO LANDSCAPED AREAS.

PORFIRIO OSCAR OSUNA RCE 70829 EXP. 6–30–21


NC.

Ń


 $\mathbf{O}$ 



3+	-00	290 285 280 275 270 265 260 255 250 245 3+	25				AS RECISION		SIQUAL CHANNEL CAP OSUMA 30-21	BY CITY DATE REVISIONS
					290 285 280 275 260 255 250 245 3+	PLANNING SUBMITTAL – NOT FOR CONSTRUCTION	CONCEPTUAL GRADING & DRAINAGE PLAN	CONSTRUCTION DETAILS	A 380 MAGDALENA AVE. CONSULTING CIVIL ENGINEERS & LAND SURVEYORS	<i>LUS ALIUS, CALIE Designed: J.O Checked: 0.0 Date: 12/18/20</i> SAN JOSE, CA 95119 Info@osunaengineering.com



\_\_\_\_\_



#### STANDARD BEST MANAGEMENT PRACTICE NOTES

- 1. Solid and Demolition Waste Management: Provide designated waste collection areas and containers on site away from streets, gutters, storm drains, and waterways, and arrange for regular disposal. Waste containers must be watertight and covered at all times except when waste is deposited. Refer to Erosion & Sediment Control Field Manual, 4th Edition (page C3) or latest.
- 2. Hazardous Waste Management: Provide proper handling and disposal of hazardous wastes by a licensed hazardous waste material hauler. Hazardous wastes shall be stored and properly labeled in sealed containers constructed of suitable materials. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-5 to C-6) or latest.
- 3. <u>Spill Prevention and Control</u>: Provide proper storage areas for liquid and solid materials, including chemicals and hazardous substances, away from streets, gutters, storm drains, and waterways. Spill control materials must be kept on site where readily accessible. Spills must be cleaned up immediately and contaminated soil disposed properly. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-7 to C-8, C-13 to C-14) or latest.
- 4. <u>Vehicle and Construction Equipment Service and Storage</u>: An area shall be designated for the maintenance, where onsite maintenance is required, and storage of equipment that is protected from stormwater run-on and runoff. Measures shall be provided to capture any waste oils, lubricants, or other potential pollutants and these wastes shall be properly disposed of off site. Fueling and major maintenance/repair, and washing shall be conducted off-site whenever feasible. Refer to Erosion & Sediment Control Field Manual, 4th Edition (page C9) or latest.
- 5. Material Delivery, Handling and Storage: In general, materials should not be stockpiled on site. Where temporary stockpiles are necessary and approved by the County, they shall be covered with secured plastic sheeting or tarp and located in designated areas near construction entrances and away from drainage paths and waterways. Barriers shall be provided around storage areas where materials are potentially in contact with runoff. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-11 to C-12) or latest.
- 6. <u>Handling and Disposal of Concrete and Cement</u>: When concrete trucks and equipment are washed on-site, concrete wastewater shall be contained in designated containers or in a temporary lined and watertight pit where wasted concrete can harden for later removal. If possible have concrete contractor remove concrete wash water from site. In no case shall fresh concrete be washed into the road right-of-way. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-15 to C-16) or latest.
- 7. <u>Pavement Construction Management</u>: Prevent or reduce the discharge of pollutants from paving operations, using measures to prevent run-on and runoff pollution and properly disposing of wastes. Avoid paving in the wet season and reschedule paving when rain is in the forecast. Residue from saw-cutting shall be vacuumed for proper disposal. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-17 to C-18) or latest.
- 8. Contaminated Soil and Water Management: Inspections to identify contaminated soils should occur prior to construction and at regular intervals during construction. Remediating contaminated soil should occur promptly after identification and be specific to the contaminant identified, which may include hazardous waste removal. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-19 to C-20) or latest.
- . <u>Sanitary/Septic Water Management</u>: Temporary sanitary facilities should be located away from drainage paths, waterways, and traffic areas. Only licensed sanitary and septic waste haulers should be used. Secondary containment should be provided for all sanitary facilities. Refer to Erosion & Sediment Control Field Manual, 4th Edition (page C-21) or latest.
- 10. Inspection & Maintenance: Areas of material and equipment storage sites and temporary sanitary facilities must be inspected weekly. Problem areas shall be identified and appropriate additional and/or alternative control measures implemented immediately, within 24 hours of the problem being identified.

Best Management Practices and Erosion Control Details Sheet 1 County of Santa Clara

#### STANDARD EROSION CONTROL NOTES

1. Sediment Control Management:

Tracking Prevention & Clean Up: Activities shall be organized and measures taken as needed to prevent or minimize tracking of soil onto the public street system. A gravel or proprietary device construction entrance/exit is required for all sites. Clean up of tracked material shall be provided by means of a street sweeper prior to an approaching rain event, or at least once at the end of each workday that material is tracked, or, more frequently as determined by the County Inspector. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages B-31 to B-33) or latest.

Storm Drain Inlet and Catch Basin Inlet Protection: All inlets within the vicinity of the project and within the project limits shall be protected with gravel bags placed around inlets or other inlet protection. At locations where exposed soils are present, staked fiber roles or staked silt fences can be used. Inlet filters are not allowed due to clogging and subsequent flooding. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages B-49 to B-51) or latest.

Storm Water Runoff: No storm water runoff shall be allowed to drain in to the existing and/or proposed underground storm drain system or other above ground watercourses until appropriate erosion control measures are fully installed.

<u>Dust Control</u>: The contractor shall provide dust control in graded areas as required by providing wet suppression or chemical stabilization of exposed soils, providing for rapid clean up of sediments deposited on paved roads, furnishing construction road entrances and vehicle wash down areas, and limiting the amount of areas disturbed by clearing and earth moving operations by scheduling these activities in phases.

Stockpiling: Excavated soils shall not be placed in streets or on paved areas. Borrow and temporary stockpiles shall be protected with appropriate erosion control measures(tarps, straw bales, silt fences, ect.) to ensure silt does not leave the site or enter the storm drain system or neighboring watercourse.

- 2. Erosion Control: During the rainy season, all disturbed areas must include an effective combination of erosion and sediment control. It is required that temporary erosion control measures are applied to all disturbed soil areas prior to a rain event. During the non-rainy season, erosion control measures must be applied sufficient to control wind erosion at the site.
- 3. Inspection & Maintenance: Disturbed areas of the Project's site, locations where vehicles enter or exit the site, and all erosion and sediment controls that are identified as part of the Erosion Control Plans must be inspected by the Contractor before, during, and after storm events, and at least weekly during seasonal wet periods. Problem areas shall be identified and appropriate additional and/ or alternative control measures implemented immediately, within 24 hours of the problem being identified.
- 4. <u>Project Completion</u>: Prior to project completion and signoff by the County Inspector, all disturbed areas shall be reseeded, planted, or landscaped to minimize the potential for erosion on the subject site.

lation

nform


ct


Õ

roj

Â

- 5. It shall be the Owner's/Contractor's responsibility to maintain control of the entire construction operation and to keep the entire site in compliance with the erosion control plan.
- 6. Erosion and sediment control best management practices shall be operable year round or until vegetation is fully established on landscaped surfaces.





—

—

\_\_\_\_