


ALTERATIONS AND ADDITIONS TO: DHAMI RESIDENCE

GENERAL NOTES		ABBREVIATIONS		LOCATION MAP		PROJECT DATA		SHEET INDEX	
<div>1. SITE USE: Construction access shall be through areas of Site designated as a construction unloading and storage area.</div> <div>2. SITE CLEAN-UP: The Site shall be maintained in a clean, orderly condition free of debris and litter, and shall not be unreasonably encumbered with any materials or equipment. Verify location of trash containers and parking areas to be used with Owner and regulatory agency.</div> <div>3. SECURITY: Contractor shall maintain and is solely responsible for any temporary security measures necessary to the Work. Contractor shall provide and maintain fencing, barricades, warning sign/signals and all other protective measures appropriate to the necessary standard of safety.</div> <div>4. UTILITIES: Contractor shall verify location and protect utilities in and around work area whether or not delineated in the Drawings. Contractor shall notify utility company and responsible professional of any conflict or potential conflict with utilities.</div> <div>5. VERIFICATION: Contractor shall take field measurements and verify field conditions and shall carefully compare such field measurements and conditions and other information known to the Contractor with the Drawings prior to commencing activities. Errors, omissions, or inconsistencies between these and all documents or against field conditions shall be at once reported to Owner and Architect.</div> <div>6. NOTIFICATION: Architect shall be promptly notified of any changes from Work indicated herein, whether discretionary, necessitated by unanticipated field conditions, by code requirements, or for any other reason. Prompt written notice shall be given by the Owner to the Architect if the Owner becomes aware of any fault or defect in the Project or nonconformance with the prepared Drawings or documents.</div> <div>7. DOCUMENTS: The intent of the Contract Documents is to include all items necessary for the proper execution and completion of the Work by the Contractor. The Contract Documents are complementary, in that what is required by one shall be as binding as if required by all.</div> <div>8. CODE CONFORMANCE: All Work shall conform to requirements of currently adopted California Building Code (CBC), C.A.C. Title-24 requirements, Federal Americans with Disabilities Act, and all other applicable federal, state, and local codes and requirements adopted by local jurisdiction or otherwise applicable to this Project.</div> <div>9. CONSTRUCTION STANDARDS: All construction and materials shall be as specified and as required by the current edition of the CBC, locally enforced codes, and authorities. All articles, materials, and equipment shall be installed, applied, and connected as directed by the manufacturer's specifications except where otherwise noted.</div> <div>10. STORAGE: All materials stored on Site shall be properly stacked and protected to prevent damage or deterioration until use. Failure to protect materials may be cause for rejection of work.</div> <div>11. WORKMANSHIP: Contractor shall do all cutting, fitting, or patching of Work that may be required to make its several parts fit together properly and shall not endanger any other Work by cutting, or otherwise altering the total Work or any part of it. Contractor shall exercise care to protect any construction so that integrity is not impaired. All patching, repairing and replacing of materials and surfaces, cut or damaged in execution of Work shall be done with applicable materials so that surfaces replaced will, upon completion, match surrounding similar surfaces.</div> <div>12. DIMENSIONS: All dimensions must be verified prior to starting Work. Do not scale Drawings without specific written authorization from Architect. Measured dimensions supersede dimensions obtained by scaling. All plan dimensions (interior and exterior) are to face of structure (FOS if wood-framed, FOM if masonry) unless noted otherwise. When so dimensioned, "CLR" means clear dimension from face of finish (FOF).</div> <div>13. SUPPORTS: Provide all necessary blocking, backing and framing for light fixtures, electric units, plumbing fixtures, toilet accessories, heating equipment and all other items requiring support.</div> <div>14. SHORING: It shall be the Contractor's sole responsibility to design and provide adequate shoring, bracing, etc., during construction and/or demolition.</div> <div>15. SAFETY: Contractor shall be solely responsible for initiating, maintaining and supervising all safety precautions and programs in connection with the Work, and take all reasonable precautions for safety of and protection to prevent damage, injury, or loss to employees on the Work and other persons who may be affected thereby, the Work and materials and equipment to be incorporated into the Work, and all property at the site or adjacent to it.</div> <div>16. HAZARDOUS MATERIALS: In the event Contractor encounters on the site materials reasonably believed to be asbestos, PCBs, or other listed hazardous materials, Contractor shall stop Work and report the condition in writing to Owner, Architect, and the regulating authority.</div> <div>17. SIMILAR CONDITIONS: Typical details and notes shall apply unless specifically shown or noted otherwise. Details not fully shown or noted shall be similar to details shown for similar conditions.</div> <div>18. OBSERVATION: Architect shall visit the site at intervals appropriate to the stage of construction, at Owner's authorization. At minimum, Contractor should arrange for Architect to observe the Work:<div>a. after demolition/ uncovering of structure but prior to subsequent work.</div><div>b. at green building preconstruction conference.</div><div>c. at each regulatory inspection.</div><div>d. at Substantial Completion.</div></div> <div>19. MISCELLANEOUS: Word "provide" used in Drawings means item is furnished, installed, and connected as required for complete installation, except as specifically noted otherwise. Word "verify" used in Drawings means item, dimension, condition, or provision shall be verified for accuracy and written clarification secured from Architect prior to initiation of associated Work.</div>		<div>A Area</div> <div>AB Anchor Bolt</div> <div>ABV Above</div> <div>AC Asphaltic Concrete, Air Conditioning</div> <div>ACST Acoustic, Acoustical</div> <div>ADH Adhesive, Adhesive</div> <div>AFF Above Finish Floor</div> <div>AGGR Aggregate</div> <div>ALUM Aluminum</div> <div>ALT Alternate</div> <div>APP Approve, Approved, Approval</div> <div>APPROX Approximate</div> <div>ARCH Architect, Architecture</div> <div>ASSY Assembly</div> <div>BD Board</div> <div>BETW Between</div> <div>BLDG Building</div> <div>BLKG Blocking</div> <div>BLT-IN Built-in</div> <div>BLW Below</div> <div>BM Beam</div> <div>B M Bench Mark</div> <div>B N Boundary Nail</div> <div>BOT Bottom</div> <div>BR Brass</div> <div>BZ Bronze</div> <div>BUR Built-up Roof</div> <div>CAB Cabinet</div> <div>C B Catch Basin</div> <div>C C J Concrete Control Joint</div> <div>CEM Cement</div> <div>CER Ceramic</div> <div>CHAM Chamfer</div> <div>C I Cast Iron</div> <div>C J Control Joint, Ceiling Joist</div> <div>C L Centerline</div> <div>C L G Ceiling</div> <div>CLOS Closet</div> <div>CLP Clear</div> <div>C M U Concrete Masonry Unit</div> <div>C O Clean Out</div> <div>COL Column</div> <div>CONC Concrete</div> <div>CONSTR Construction</div> <div>CONTR Contructus</div> <div>C/R Cash Register</div> <div>CS Channel Scribed</div> <div>CU Copper, Cubic</div> <div>d Penny (nail)</div> <div>DAT Datum</div> <div>DBL Double</div> <div>DEG Degree</div> <div>DEMO Demolition</div> <div>D F Douglas Fir, Drinking Fountain</div> <div>D I Diameter or Round</div> <div>DIM Dimension</div> <div>DN Down</div> <div>DP Deep</div> <div>DR Door</div> <div>DW Downspout</div> <div>DTL Detail</div> <div>DWG Drawing, Drawings</div> <div>EA Each</div> <div>EJ Expansion Joint</div> <div>EL Elevation</div> <div>ELEC Electric, Electrical</div> <div>EN Edge Nail</div> <div>ENGR Engineer</div> <div>EQU Equal</div> <div>EQUI Equipment</div> <div>EW Each Way</div> <div>EXIST Exists, Existing</div> <div>EXH Exhaust</div> <div>EXT Exterior</div> <div>F D Floor Drain</div> <div>F DN Foundation</div> <div>FIN Finish</div> <div>F J Floor Joist</div> <div>FLR Floor</div> <div>FLUOR Fluorescent</div> <div>F O F Face Of Finish</div> <div>F O M Face Of Masonry</div> <div>F O S Face of Stud</div> <div>F O STL Face of Steel</div> <div>F O W Face of Wall</div> <div>FPL Fireplace</div> <div>FR From</div> <div>F R P Fiber Reinforced Plastic</div> <div>FT Foot, Feet</div> <div>FTG Footing</div> <div>GA Gauge</div> <div>GALV Galvanized</div> <div>G I Galvanized Iron</div> <div>GL B Glass</div> <div>G S M Galvanized Sheet Metal</div> <div>GYP Gypsum</div> <div>H High</div> <div>H B Hose Bib</div> <div>HC Handcapped</div> <div>H C Hollow Core</div> <div>H D Hand Dryer</div> <div>HDWD Hardwood</div> <div>HDR Header</div> <div>H M Hollow Metal</div> <div>HOR Horizontal</div> <div>HORIZ Horizontal</div> <div>HR Hour, Hours</div> <div>HT Height</div> <div>I D Inside diameter</div> <div>INSUL Insulate, Insulated</div> <div>INT Interior</div> <div>JAN Janitor</div> <div>JT Joint</div> <div>JST oist</div> <div>KD Kiln Dried</div> <div>LAV Lavatory</div> <div>LBR Lumber</div> <div>LNGE Lounge</div> <div>LS Landscape, Land Surveyor</div> <div>LT Light</div> <div>MAX Maximum</div> <div>M B Machine Bolt</div> <div>MECH Mechanical</div> <div>MFR Manufacture, Manufacturer</div> <div>M H Manhole</div> <div>M I Malleable Iron</div> <div>MIN Minimum</div> <div>M O Masonry Opening</div> <div>MTL Metal</div> <div>N I C Not In Contract</div> <div>NOM Nominal</div> <div>N T S Not To Scale</div> <div>O On</div> <div>O C On Center</div> <div>O D Outside Diameter</div> <div>O H Overflow Drain</div> <div>OPNG Overhead</div> <div>OPP Opening</div> <div>P A F Opposite</div> <div>PL Power Activated Fastener</div> <div>PL Plate, Property Line</div> <div>PLAM Plastic Laminat</div> <div>PLAS Plaster, Plastic</div> <div>PLAS LAM Plastic Laminat</div> <div>PLYWD Plywood</div> <div>PNL Panel</div> <div>PR Pair</div> <div>PROV Provide</div> <div>P T Pressure Treated</div> <div>PTD Painted</div> <div>P V C Polyvinyl chloride</div> <div>QT Quarry Tile</div> <div>QTR Quarter</div> <div>R R Riser Radius</div> <div>R D Roof Drain</div> <div>RDL Relative Density</div> <div>RD Root Drain Line</div> <div>RDWD Redwood</div> <div>REF Reference</div> <div>REFR Refrigerator</div> <div>REINF Reinforce, Reinforcement</div> <div>REP Repair</div> <div>REPL Replace</div> <div>REQD Required</div> <div>RET Requirement</div> <div>RETN Retaining</div> <div>REV Revised, Revision</div> <div>RM Room</div> <div>RND Round</div> <div>RO Rough Opening</div> <div>RO Rafter</div> <div>RWL Rainwater Leader</div> <div>S B Solid Block</div> <div>S C Solid Core</div> <div>SCHED Schedule</div> <div>S D Site Drain</div> <div>SDG Siding</div> <div>S F Square Feet</div> <div>SH Sheet</div> <div>SHV Shelving</div> <div>SIM Similar</div> <div>SK Sink</div> <div>SOG Slab on Grade</div> <div>SPEC Specification</div> <div>SPECD Specified</div> <div>SPNK Sprinkler</div> <div>ST Stainless</div> <div>STL Standard</div> <div>STEEL Steel</div> <div>STRUC Structure, Structural</div> <div>SUSP Suspend, Suspended</div> <div>T Tread, Treads</div> <div>T C Top of Curb</div> <div>TEL Telephone</div> <div>TEMP Tempered</div> <div>T E N Typical Edge Nailing</div> <div>THK Tongue and Groove</div> <div>THK Thick</div> <div>THRU Through</div> <div>T O C Top of Concrete</div> <div>T O F Top of Curb</div> <div>T O F Top of Framing</div> <div>TOL Tolerance</div> <div>T O P Top of Plate</div> <div>T O S Top of Slope</div> <div>T O STL Top of Steel</div> <div>T O W Top of Wall</div> <div>T P Top of Pavement</div> <div>TR Toilet Room</div> <div>T V Top of Subfloor</div> <div>TV Television</div> <div>TYP Typical</div> <div>UNO Unless Noted Otherwise</div> <div>UR Urinal</div> <div>V Vent</div> <div>VENT Ventilate, Ventilation</div> <div>VER Verify</div> <div>VERT Vertical</div> <div>VEST Vestibule</div> <div>W Wide, Width</div> <div>W With</div> <div>W C Water Closet</div> <div>WD Wide, Wood</div> <div>WDW Window</div> <div>W GL Wire Glass</div> <div>W I Wrought Iron</div> <div>W/O Without</div> <div>WP Waterproof</div> <div>WR Water Resistant</div> <div>WSCT Wainscot</div> <div>WT Weight</div> <div>WWM Welded Wire Mesh</div> <div>YD Yard</div> <div>Z Zinc</div> <div>& And</div> <div>X By (e.g. 2X4)</div> <div>@ At</div> <div>(E) Existing</div> <div>(N) New</div> <div>(P) Proposed</div>				<div>DESCRIPTION: ADDITIONAL AND ALTERATIONS TO (E) SFR ENTAILING APPROX. 1,600SF OF ADDITIONAL SQUARE FOOTAGE TO (E) RESIDENCE. PROGRAM BRIEF ENTAILS AN ENTRY HALL EXTENSION, DEMOLITION AND CONSTRUCT NEW ENTRY PORCH, EASTERLY ADDITION TO MASTER BEDROOM, EASTERLY ADDITION TO FIRST FLOOR BEDROOM; EXTEND WESTERLY DECK; ADD AT-GRADE TERRACE; EXTEND BEDROOM #201 AT SECOND FLOOR. CONVERT EXISTING "RETREAT SPACE" INTO BEDROOM AND EXTEND WESTERLY; EXTEND BEDROOM #202 AT SECOND FLOOR; CONSTRUCT (N) SECOND FLOOR DECK.</div> <div>SITE ESTIMATED AREA: 15.93 AC</div> <div>ZONE DISTRICT: HS-d2</div> <div>MAX HT OF S.F.R.: 27 FT</div> <div>MAX GROSS AREA: 8,000 SF</div> <div>FYSB: 30 FT</div> <div>RYSB: 30 FT</div> <div>SYSB: 30 FT</div> <div>(E) BEDROOM COUNT: 4</div> <div>PROPOSED BEDRM COUNT: 5</div> <div>MIN. PARKING REQD: 2 (1-COVERED)</div> <div>PARKING FURNISHED: 6</div> <div>CBC/ CRC DESIGNATION: R-3 SINGLE FAMILY DWELLING</div> <div>CONST. TYPE: V-B SPRINKLERED</div> <div>FIRE JURISDICTION: W.U.I.</div> <div>BUILDING AREAS (AREAS APPROX):</div> <div>(E) SFR: 5,613 SF</div> <div>(E) GAR: 788 SF</div> <div>(E) PORCH: 35 SF</div> <div>1ST FLOOR ADDITIONS: 1,054 SF</div> <div>2ND FLOOR ADDITIONS: 545 SF</div> <div>TOTAL: 8,000 SF</div> <div>PROPOSED EXTERIOR IMPROVEMENTS (AREAS APPROX):</div> <div>ENTRY PORCH: 156 SF</div> <div>LOWER DECK EXTEND: 1,435 SF</div> <div>UPPER DECK EXTEND: 1,026 SF</div> <div>TERRACE AT GRADE: 4,139 SF</div> <div>CODES IN EFFECT:</div> <div>-2019 BUILDING STANDARDS ADMINISTRATIVE CODE</div> <div>-2019 CALIFORNIA RESIDENTIAL BUILDING CODE</div> <div>-2019 CALIFORNIA BUILDING CODE</div> <div>-2019 CALIFORNIA GREEN BUILDING STNDS CODE</div> <div>-2019 CALIFORNIA PLUMBING CODE</div> <div>-2019 CALIFORNIA MECHANICAL CODE</div> <div>-2019 CALIFORNIA ELECTRICAL CODE</div> <div>-2019 CALIFORNIA ENERGY EFFICIENCY STANDARDS</div> <div>-2019 CALIFORNIA FIRE CODE</div> <div>-2019 CALIFORNIA EXISTING BUILDING CODE</div> <div>-2019 CALIFORNIA REFERENCE STANDARDS CODE</div>		<div>SK-1.0 TITLE SHEET</div> <div>SK-1.1 BLDG AREA ANALYSIS</div> <div>SK-2.0 SITE PLAN</div> <div>SK-3.0 FIRST FLOOR PLAN</div> <div>SK-3.1 SECOND FLOOR PLAN</div> <div>SK-4.0 ELEVATIONS</div> <div>SK-4.1 ELEVATIONS</div> <div>SK-5.0 BUILDING SECTIONS</div> <div>SK-6.0 AXONOMETRICS</div> <div>EX-1 EXISTING CONDITIONS</div> <div>C0.1 COVER SHEET</div> <div>C1.1 (E) CONDITIONS & DEMO PLAN</div> <div>C2.1 SITE PLAN</div> <div>C3.1 GRADING & DRAINAGE PLAN</div> <div>C4.1 FIRE PREVENTION PLAN</div> <div>C4.2 FIRE PREVENTION PLAN</div> <div>C5.1 EROSION CONTROL PLAN</div> <div>C5.2 EROSION CONTROL DETAILS</div> <div>C5.3 EROSION CONTROL DETAILS</div> <div>OWTS1 SEPTIC SYSTEM PLAN</div>	
						PROJECT TEAM		REGULATORY REQUIREMENTS	
		<div>OWNER</div> <div>RAJ DHAMI 2100 OLD CALAVERAS RD. MILPITAS, CA 95035 (647) 928-7896</div>		<div>ARCHITECT</div> <div>DANIEL SILVERNAIL ARCHITECT, INC. 501 MISSION STREET, STE #2 SANTA CRUZ, CA, 95060 (831) 462-9138 www.silvernailarch.com</div>		<div>GEOTECHNICAL ENGNR</div> <div>BARRY MILSTONE 4444 SCOTTS VALLEY DRIVE SUITE #6 SCOTT VALLEY, CA 95033 (408) 353-5528</div>		<div>CIVIL ENGR</div> <div>C2G CIVIL CONSULTANTS GROUP, INC. 2100 OLD CALAVERAS RD SCOTT VALLEY, CA (831) 438-4420</div>	
		<div>WASTEWTR CONSULT.</div> <div>CHRISTOPHER DAY PO BOX 26 REDWOOD CITY, CA 94064 (650) 293-1045</div>							
						REGULATORY REQUIREMENTS			
						1. DEFERRED SUBMITTALS: CONTRACTOR SHALL PREPARE AND SUBMIT DEFERRED SUBMITTAL ITEMS TO ARCHITECT PROMPTLY UPON AWARD OF CONTRACT FOR CONSTRUCTION. DEFERRED SYSTEMS: <div>a. FIRE SPRINKLER SYSTEM.</div>			

DESCRIPTION:

ADDITIONS AND ALTERATIONS TO (E) SFR ENTAILING APPROX. 1,600SF OF ADDITIONAL SQUARE FOOTAGE TO (E) RESIDENCE. PROGRAM BRIEF ENTAILS AN ENTRY HALL EXTENSION, DEMOLITION AND CONSTRUCT NEW ENTRY PORCH, EASTERLY ADDITION TO MASTER BEDROOM, EASTERLY ADDITION TO FIRST FLOOR BEDROOM; EXTEND WESTERLY DECK; ADD AT-GRADE TERRACE; EXTEND BEDROOM #201 AT SECOND FLOOR. CONVERT EXISTING "RETREAT SPACE" INTO BEDROOM AND EXTEND WESTERLY; EXTEND BEDROOM #202 AT SECOND FLOOR; CONSTRUCT (N) SECOND FLOOR DECK.

SITE ESTIMATED AREA:

15.93 AC

ZONE DISTRICT:

HS-d2

MAX HT OF S.F.R.:

27 FT

MAX GROSS AREA:

8,000 SF

FYSB:

30 FT

FYSB:

30 FT

SYSB:

30 FT

(E) BEDROOM COUNT:

4

PROPOSED BEDRM COUNT:

5

MIN. PARKING REQD:

2 (1-COVERED)

PARKING FURNISHED:

6

CBC/ CRC DESIGNATION:

R-3 SINGLE FAMILY DWELLING

CONST. TYPE:

V-B SPRINKLERED

FIRE JURISDICTION:

W.U.I.

BUILDING AREAS (AREAS APPROX):

(E) SFR: 5,613 SF

(E) GAR: 788 SF

(E) PORCH: 35 SF

1ST FLOOR ADDITIONS: 1,054 SF

2ND FLOOR ADDITIONS: 545 SF

TOTAL: 8,000 SF

PROPOSED EXTERIOR IMPROVEMENTS (AREAS APPROX):

ENTRY PORCH: 156 SF

LOWER DECK EXTEND: 1,435 SF

UPPER DECK EXTEND: 1,026 SF

TERRACE AT GRADE: 4,139 SF

CODES IN EFFECT:

-2019 BUILDING STANDARDS ADMINISTRATIVE CODE

-2019 CALIFORNIA RESIDENTIAL BUILDING CODE

-2019 CALIFORNIA BUILDING CODE

-2019 CALIFORNIA GREEN BUILDING STNDS CODE

-2019 CALIFORNIA PLUMBING CODE

-2019 CALIFORNIA MECHANICAL CODE

-2019 CALIFORNIA ELECTRICAL CODE

-2019 CALIFORNIA ENERGY EFFICIENCY STANDARDS

-2019 CALIFORNIA FIRE CODE

-2019 CALIFORNIA EXISTING BUILDING CODE

-2019 CALIFORNIA REFERENCE STANDARDS CODE

SK-1.0 TITLE SHEET

SK-1.1 BLDG AREA ANALYSIS

SK-2.0 SITE PLAN

SK-3.0 FIRST FLOOR PLAN

SK-3.1 SECOND FLOOR PLAN

SK-4.0 ELEVATIONS

SK-4.1 ELEVATIONS

SK-5.0 BUILDING SECTIONS

SK-6.0 AXONOMETRICS

EX-1 EXISTING CONDITIONS

C0.1 COVER SHEET

C1.1 (E) CONDITIONS & DEMO PLAN

C2.1 SITE PLAN

C3.1 GRADING & DRAINAGE PLAN

C4.1 FIRE PREVENTION PLAN

C4.2 FIRE PREVENTION PLAN

C5.1 EROSION CONTROL PLAN

C5.2 EROSION CONTROL DETAILS

C5.3 EROSION CONTROL DETAILS

OWTS1 SEPTIC SYSTEM PLAN

REGULATORY REQUIREMENTS

1. DEFERRED SUBMITTALS: CONTRACTOR SHALL PREPARE AND SUBMIT DEFERRED SUBMITTAL ITEMS TO ARCHITECT PROMPTLY UPON AWARD OF CONTRACT FOR CONSTRUCTION. DEFERRED SYSTEMS:

a. FIRE SPRINKLER SYSTEM.

REVISIONS

DATE

#

△

△

△

△

△

9/28/20 10:26 AM

LICENSED ARCHITECT

DANIEL MATTHEW SILVERNAIL

C-24335

4-09-2021

RENEWAL DATE

STATE OF CALIFORNIA

PREPARED FOR:

RAJ DHAMI

2100 OLD CALAVERAS RD

MILPITAS, CA 95035

(647) 928-7896

Daniel Silvernail Architect, Inc.

501 Mission St Suite #2 Santa Cruz CA 95060

831.462.9138

APN 02931011

2100 OLD CALAVERAS RD MILPITAS CA 95035

TITLE SHEET

SCHEMATIC DESIGN DOCUMENTS

DHAMI RESIDENCE

DATE

xx/xx/xxxx

JOB#

20.008

MODEL-ING BY


DSAi

SHEET


SK-1.0

OF 10 SHEETS

DESIGN REVIEW DRAWINGS



B SECOND FLOOR AREA ANALYSIS
SCALE: 1/8" = 1'-0"



A FIRST FLOOR AREA ANALYSIS
SCALE: 1/8" = 1'-0"

AREA TABULATION		
STORY	BUILDING PORTION	GROSS AREA
1	EXISTING	4,733
1	SPICE KITCHEN ADDITION	203
1	NORTHERLY ADDITIONS	846
2	EXISTING	1,668
2	BEDROOM ADDITIONS	545
TOTAL		7,995

REVISIONS

DATE	#
	△
	△
	△
	△
	△

9/28/20 10:26 AM

LICENSED ARCHITECT

DANIEL MATTHEW SILVERNAIL

C-24335

6-30-2021

RENEWAL DATE

STATE OF CALIFORNIA

PREPARED FOR:

RAJ DHAMI

2100 OLD CALAVERAS RD

MILPITAS, CA 95035

(647) 928-7896

Daniel Silvernail Architect, Inc.

501 Mission St Suite #2 - Santa Cruz CA 95060 - 831.462.9138

BLDG AREA ANALYSIS

SCHEMATIC DESIGN DOCUMENTS

DHAMI RESIDENCE

2100 OLD CALAVERAS RD MILPITAS CA 95035

APN 029310111

DATE

xx/xx/xxxx

JOB#

20.008

MODEL-ING BY

DSAI


SHEET

SK-1.1

OF 10 SHEETS


SITE NOTES

1. CONDUCT THOROUGH AND COMPLETE INVESTIGATION OF UTILITIES AND OBSTRUCTIONS AFFECTING THE WORK PRIOR TO BEGINNING. CONSULT OWNER REGARDING LOCATIONS OF KNOWN UNDERGROUND UTILITIES. DO NOT PROCEED WITH WORK IN CONFLICT WITH EXISTING CONDITIONS OR OBSTRUCTIONS CONFLICTING WITH THE WORK SHOWN.
2. WORK SHALL CONFORM TO THE SOILS REPORT PREPARED FOR THIS PROJECT. SEE "GEOLOGIC AND GEOTECHNICAL REPORT, JAMES BAKER ASSOCIATES 1996.
3. FINISH GRADES SHALL SLOPE AT MINIMUM 5% AWAY FROM NEW CONSTRUCTION. AND PROVIDE POSITIVE DRAINAGE GRADIENT AWAY FROM NEW CONSTRUCTION. SURFACE WATER MUST NOT BE ALLOWED TO POND OR BE TRAPPED ADJACENT TO BUILDING FOUNDATIONS, BUILDING PADS, OR OTHER TRAFFIC SURFACING.
4. ON-SITE VEGETATION: PROTECT EXISTING LANDSCAPING. PROTECT ALL EXISTING TREES EXCEPT THOSE SPECIFICALLY INDICATED TO BE REMOVED.
5. CONTRACTOR SHALL VERIFY BY SURVEY OR OTHER MEANS ACCEPTABLE TO OWNER ACCURATE RELATIONSHIP OF EXISTING STRUCTURES TO THE PROPERTY LINES PRIOR TO BEGINNING.
6. SEPTIC SYSTEM: PROVIDE COMPLETE SYSTEM AS REQUIRED FOR NEW WORK. SANITARY WASTE PROVISIONS SHALL BE AS PER SEPARATE PERMIT: SEE DOCUMENTATION PREPARED BY PROJECT WASTEWATER CONSULTANT.
7. SURVEY INFORMATION SHOWN IS AS PER "SECONDARY DWELLING SITE PLAN" PREPARED BY MASON SULIC CIVIL & DESIGN CONSULTANTS DATED REV-0 8/13/99. ARCHITECT MAKES NO REPRESENTATION AS TO ACCURACY.



A PART. SITE PLAN
SCALE: 1" = 20'

PRELIMINARY
THIS IS NOT A SURVEY



REVISIONS	
DATE	#
	△
	△
	△
	△
	△
9/28/20	10:26 AM
<div><div>100%</div><div>LICENSED ARCHITECT</div><div>DANIEL MATTHEW SILVERNAIL</div><div>C-24335</div><div>6-30-2021</div><div>RENEWAL DATE</div><div>STATE OF CALIFORNIA</div></div>	


PREPARED FOR:
RAJ DHAMI
2100 OLD CALAVERAS RD
MILPITAS, CA 95035
(647) 928-7896

Daniel Silvernail Architect, Inc.
501 Mission St Suite #2 - Santa Cruz CA 95060 - 831.462.9138

SITE PLAN
SCHEMATIC DESIGN DOCUMENTS
DHAMI RESIDENCE
APN 02310111
2100 OLD CALAVERAS RD MILPITAS CA 95035


DATE	xx/xx/xxxx
JOB#	20.008
MODEL-ING BY	DSAI
SHEET	SK-2.0
OF	10 SHEETS

DESIGN REVIEW DRAWINGS



A SECOND FLOOR PLAN
SCALE: 1/8" = 1'-0"

- WALL LEGEND**
- (E) WALL OR PARTITION
 - (N) INT WALL OR PARTITION
 - WALL OR PARTITION REMOVED




REVISIONS	
DATE	#
	△
	△
	△
	△
	△

9/28/20 10:26 AM




PREPARED FOR:
RAJ DHAMI
2100 OLD CALAVERAS RD
MILPITAS, CA 95035
(647) 928-7896



SECOND FLOOR PLAN
SCHEMATIC DESIGN DOCUMENTS
DHAMI RESIDENCE
2100 OLD CALAVERAS RD MILPITAS CA 95035
APN 02931011

DATE	xx/xx/xxxx
JOB#	20.008
MODEL- ING BY	DSAI
SHEET	SK-3.1
OF	10 SHEETS

DESIGN REVIEW DRAWINGS




A NORTH ELEVATION

SCALE: 3/16" = 1'-0"

KEY TO COLORS:

- ① ROOFING: US TILE (BORAL) MISSION TILE, CARMEL BLEND.
- ② WINDOW FRAMES: MILGARD, INCORPORATED. WHITE VINYL, LRV-70.
- ③ RAILINGS: GLASS.
- ④ TRIM: SHERWIN WILLIAMS "ARUGULA" SW 6446 LRV-10.
- ⑤ EXTERIOR WALLS: SHERWIN WILLIAMS "FOLKSY GOLD" SW 6360 LRV-39.
- ⑥ COLUMN: THASSOS WHITE AAA MARBLE.
- ⑦ BALUSTRADES: ARCHITECTURAL CAST STONE, HADDINGSTONE INC, WHITE.



B WEST ELEVATION

SCALE: 3/16" = 1'-0"

REVISIONS	
DATE	#
	△
	△
	△
	△
	△
	△

9/28/20 10:26 AM




PREPARED FOR:
RAJ DHAMI
2100 OLD CALAVERAS RD
MILPITAS, CA 95035
(647) 928-7896

Daniel Silvernail Architect, Inc.
501 Mission St Suite #2 - Santa Cruz CA 95060 - 831.462.9138

ELEVATIONS
SCHEMATIC DESIGN DOCUMENTS
DHAMI RESIDENCE
2100 OLD CALAVERAS RD MILPITAS CA 95035
APN 02931011

DATE xx/xx/xxxx
JOB# 20.008
MODEL-ING BY DSAI
SHEET
SK-4.0
OF 10 SHEETS

DESIGN REVIEW DRAWINGS




A

SOUTH ELEVATION

SCALE: 3/16" = 1'-0"

KEY TO COLORS:

- 1 ROOFING: US TILE (BORAL) MISSION TILE, CARMEL BLEND.
- 2 WINDOW FRAMES: MILGARD, INCORPORATED. WHITE VINYL, LRV-70.
- 3 RAILINGS: GLASS.
- 4 TRIM: SHERWIN WILLIAMS "ARUGULA" SW 6446 LRV-10.
- 5 EXTERIOR WALLS: SHERWIN WILLIAMS "FOLKSY GOLD" SW 6360 LRV-39.
- 6 COLUMN: THASSOS WHITE AAA MARBLE.
- 7 BALUSTRADES: ARCHITECTURAL CAST STONE, HADDINGSTONE INC, WHITE.



B

EAST ELEVATION

SCALE: 3/16" = 1'-0"

REVISIONS	
DATE	#
	1
	2
	3
	4
	5

9/28/20 10:27 AM




PREPARED FOR:
RAJ DHAMI
2100 OLD CALAVERAS RD
MILPITAS, CA 95035
(647) 928-7896

Daniel Silvernail Architect, Inc.
501 Mission St Suite #2 Santa Cruz CA 95060 831.462.9138


ELEVATIONS
SCHEMATIC DESIGN DOCUMENTS
DHAMI RESIDENCE
2100 OLD CALAVERAS RD MILPITAS CA 95035
APN 02931011

DATE	xx/xx/xxxx
JOB#	20_008
MODEL- ING BY	DSAI
SHEET	SK-4.1
OF	10 SHEETS

DESIGN REVIEW DRAWINGS



A SECTION A-A'
SCALE: 3/16" = 1'-0"




B SECTION B-B'
SCALE: 3/16" = 1'-0"

REVISIONS	
DATE	#
	△
	△
	△
	△
	△

9/28/20 10:27 AM




PREPARED FOR:
RAJ DHAMI
2100 OLD CALAVERAS RD
MILPITAS, CA 95035
(647) 928-7896




BUILDING SECTIONS
SCHEMATIC DESIGN DOCUMENTS
DHAMI RESIDENCE
2100 OLD CALAVERAS RD MILPITAS CA 95035
APN 02931011


DATE	xx/xx/xxxx
JOB#	20.008
MODEL- ING BY	DSAI
SHEET	SK-5.0
OF	10 SHEETS




A NORTHWEST AXONOMETRIC
SCALE: 3/32" = 1'-0"



B NORTHEAST AXONOMETRIC
SCALE: 3/32" = 1'-0"



C SOUTHWEST AXONOMETRIC
SCALE: 3/32" = 1'-0"



D SOUTHEAST AXONOMETRIC
SCALE: 3/32" = 1'-0"

REVISIONS	
DATE	#
	△
	△
	△
	△
	△
	△

9/28/20 10:27 AM




PREPARED FOR:
RAJ DHAMI
2100 OLD CALAVERAS RD
MILPITAS, CA 95035
(647) 928-7896

Daniel Silvernail Architect, Inc.
501 Mission St Suite #2 Santa Cruz CA 95060 831.462.9138

AXONOMETRICS
SCHEMATIC DESIGN DOCUMENTS
DHAMI RESIDENCE
2100 OLD CALAVERAS RD MILPITAS CA 95035
APN 02931011


DATE xx/xx/xxxx
JOB# 20.008
MODEL-
ING BY DSAI
SHEET
SK-6.0
OF 10 SHEETS

DESIGN REVIEW DRAWINGS




B EXISTING SECOND FLOOR PLAN
SCALE: 1/8" = 1'-0"

THIS IS NOT A SURVEY



A EXISTING FIRST FLOOR PLAN
SCALE: 1/8" = 1'-0"

THIS IS NOT A SURVEY




REVISIONS	
DATE	#
	△
	△
	△
	△
	△

9/28/20 10:28 AM




PREPARED FOR:
RAJ DHAMI
2100 OLD CALAVERAS RD
MILPITAS, CA 95035
(647) 928-7896



EXISTING CONDITIONS
SCHEMATIC DESIGN DOCUMENTS
DHAMI RESIDENCE
2100 OLD CALAVERAS RD MILPITAS CA 95035
APN 02931011

DATE	xx/xx/xxxx
JOB#	20.008
MODEL- ING BY	DSAi
SHEET	EX-1
OF	10 SHEETS



REVISIONS	BY




COVER SHEET



C2G / CIVIL CONSULTANTS GROUP, INC.
Engineers/Planners
4444 Scotts Valley Blvd., Suite 6
Scotts Valley, CA 95060
T (831) 438-4420 F (831) 438-4420

DHAMI RESIDENCE
2100 OLD CALAVERAS RD
MILPITAS CA 95035

Date:	09/09/2020
Scale:	1" = 100'
Drawn:	JR
Job:	9010.01
Sheet:	C0.1
Of 9 Sheets	



ABBREVIATIONS

- AB AGGREGATE BASE
- AC ASPHALT CONCRETE
- BLDG BUILDING
- CONC CONCRETE
- EP EDGE OF PAVEMENT
- EL ELEVATION
- FL FLOWLINE
- GB GRADE BREAK
- G GROUND
- INV INVERT ELEVATION
- LP LOW POINT
- NAP NOT A PART
- NG NATURAL GROUND
- PSDE PRIVATE STORM DRAIN EASEMENT
- PUE PUBLIC UTILITY EASEMENT
- PL PROPERTY LINE
- SD STORM DRAIN
- SDDI STORM DRAIN DROP INLET
- SDMH STORM DRAIN MANHOLE
- SS SANITARY SEWER
- SSCO SANITARY SEWER CLEAN OUT
- TG TOP OF GRATE
- UG UNDERGROUND
- W WATER
- FM FORCE MAIN

IMPACTED AREA DEMO

- CONCRETE =684 SF
- BRICK, TILE, PAVERS =181 SF

REVISIONS	BY


EXISTING CONDITIONS
AND DEMOLITION PLAN



C2G / CIVIL CONSULTANTS GROUP, INC.
Engineers/Planners
4445 Stevens Canyon Road, Suite 6
Scotts Valley, CA 95065
T (831) 438-4420 F (831) 438-4420

DHAMI RESIDENCE
2100 OLD CALAVERAS RD
MILPITAS CA 95035

Date: 09/09/2020
Scale: 1" = 10'
Drawn: JR
Job: 9010.01
Sheet:
C1.1
Of 9 Sheets



REVISIONS	BY

OVERALL SITE PLAN




C2G / CIVIL CONSULTANTS GROUP, INC.
Engineers/Planners
14445 Canyon Blvd., Suite 6
San Jose, CA 95131
T (831) 438-4420 F (831) 438-4420

DHAMI RESIDENCE
2100 OLD CALAVERAS RD
MILPITAS CA 95035

Date:	09/09/2020
Scale:	1" = 60'
Drawn:	JR
Job:	9010.01
Sheet:	C2.1
Of	9 Sheets

Drawing: Z:\Drawings\CAD\9010.01 - Dhami Residence\Design\CAD\Sheets\9010.01 - C2.1 - CIVIL SITE PLAN.dwg Layout: C2.1 Last Saved: Thu, Sep 17, 2020 - 10:26am Last Plotted: Fri, Sep 18, 2020 - 12:22pm By: JRW



EARTHWORK QUANTITIES					
NOTE: THE EARTHWORK QUANTITIES SHOWN HEREON ARE EXCLUSIVE OF WALL FOOTINGS, EXISTING PAVEMENT REMOVAL AND OVER EXCAVATION AND RECOMPACTION, UTILITY TRENCH SPOILS & SOIL EXPANSION AND CONTRACTION FACTORS.					
DESCRIPTION	CUT (cu.yds)	FILL (cu.yds)	NET (cu.yds)	MAX CUT (cu.ft) HEIGHT	MAX FILL (cu.ft) HEIGHT
BUILDING PADS	0	0	0	0	0
DRIVEWAY IMP	0	0	0	0	0
SITE GRADING	0	0	0	0	0
PIERS	100	100	0	15	15
RETAINING WALLS	0	0	0	0	0
TOTAL					
NET VOLUME = 0 CU.YDS. OF FILL					
THE ABOVE QUANTITIES ARE FOR INFORMATION PURPOSES ONLY. THE CONTRACTOR IS RESPONSIBLE TO PROVIDE THE NECESSARY CUT AND FILL TO ACCOMPLISH FINISH GRADE SHOWN ON THESE PLANS.					

NEW/ REPLACED IMPERVIOUS AREAS	
	SQ FT
ROOF-BLDG	1049
DECK (N/A)	1436
CONCRETE-TER	4130
CONCRETE-SID	90
PERVIOUS PAV 10%	216
TOTAL	5485

LEGEND

- PEDESTRIAN CONCRETE
- DECKING (BY OTHERS)
- PROPERTY LINE
- PERVIOUS PAVERS

PERFORMANCE REQUIREMENT NO. 1 SITE DESIGN AND RUNOFF REDUCTION CERTIFICATION	
DESIGN STRATEGY	INCORPORATED?
1. Limit disturbance of creeks and natural drainage features.	✓
2. Minimize compaction of highly permeable soils.	✓
3. Limit clearing and grading of native vegetation at the site to the minimum area needed to build the project, allow access, and provide fire protection.	✓
4. Minimize impervious surfaces by concentrating improvements on the least sensitive areas of the site, while leaving the remaining land in a natural undisturbed state.	✓
5. Minimize stormwater runoff by implementing one or more of the following design measures:	
a) Direct roof runoff into cisterns or rain barrels for reuse.	
b) Direct roof runoff onto vegetated areas safely away from building foundations and footings.	✓
c) Direct runoff from sidewalks, walkways, and/or patios onto vegetated areas safely away from building foundations and footings.	✓
d) Direct runoff from driveways and/or uncovered parking lots onto vegetated areas safely away from building foundations and footings.	✓
e) Construct bike lanes, driveways, uncovered parking lots, sidewalks, walkways, and patios with permeable surfaces.	✓

I, TODD CREAMER, acting as the Project Engineer for DHAMI RESIDENCE project, located at 2100 OLD CALAVERAS ROAD, hereby state that the Site Design and Runoff Reduction design strategies indicated above have been incorporated into the design of the project.

Signature _____ Date _____

A-30

REVISIONS	BY


GRADING
AND
DRAINAGE
PLAN



C2G / CIVIL CONSULTANTS GROUP, INC.
Engineers/Planners
14455 Canyon Blvd., Suite 6
Scotts Valley, CA 95065
T (831) 438-4420 F (831) 438-4420


DHAMI RESIDENCE
2100 OLD CALAVERAS RD
MILPITAS CA 95035

Date:	09/09/2020
Scale:	1" = 10'
Drawn:	JR
Job:	9010.01
Sheet:	C3.1
Of	9 Sheets




1 EXISTING DRIVEWAY PLAN

Scale: 1"=80'




2 ENLARGED PLAN FOR DRIVEWAY ENTRY

Scale: 1"=80'



3 FIRE HYDRANT PATH OF TRAVEL

Scale: 1"=30'



4 EXISTING DRIVEWAY PROFILE

Scale: 1"=60'

REVISIONS	BY


FIRE PREVENTION
PLAN



C2G / CIVIL CONSULTANTS GROUP, INC.
Engineers/Planners
4445 Lakeside Drive, Suite 6
Sports Vics, CA 95066
T (831) 438-4420 F (831) 438-4420

DHAMI RESIDENCE
2100 OLD CALAVERAS RD
MILPITAS CA 95035

Date:	09/09/2020
Scale:	VARIES
Drawn:	JR
Job:	9010.01
Sheet:	C4.1
Of	9 Sheets



REVISIONS	BY


FIRE PREVENTION
PLAN



C2G / CIVIL CONSULTANTS GROUP, INC.
Engineers/Planners
14445 Canyon Blvd., Suite 6
San Jose, CA 95131
T (408) 438-4420 F (408) 438-4420
By: jgaw

DHAMI RESIDENCE
2100 OLD CALAVERAS RD
MILPITAS CA 95035

Date:	09/09/2020
Scale:	1"=20'
Drawn:	JR
Job:	9010.01
Sheet:	C4.2
Of	9 Sheets



GENERAL EROSION CONTROL NOTES

- IT IS THE CONTRACTOR'S RESPONSIBILITY TO PROVIDE AND MAINTAIN EROSION CONTROL MEASURES AS REQUIRED THROUGHOUT THE LIFE OF THE PROJECT IN CONFORMANCE WITH THE COUNTY OF MONTEREY.
- CONTRACTOR TO PROVIDE BACK-UP EROSION PREVENTION MEASURES (SOIL STABILIZATION) WITH SEDIMENT CONTROL MEASURES SUCH AS STRAW WATTLES, SILT FENCE, GRAVEL INLET FILTERS, AND/OR SEDIMENT TRAPS OR BASINS. ENSURE CONTROL MEASURES ARE ADEQUATE, IN PLACE, AND IN OPERABLE CONDITIONS. SEDIMENT CONTROLS, INCLUDING INLET PROTECTION, ARE NECESSARY BUT SHOULD BE A SECONDARY DEFENSE BEHIND GOOD EROSION CONTROL MEASURES.
- ALL EROSION PREVENTION AND SEDIMENT CONTROL MEASURES SHALL BE MAINTAINED AND REPAIRED THROUGHOUT THE SEASON. REPLACEMENT SUPPLIES SHOULD BE KEPT ON SITE.
- SITE INSPECTIONS SHALL BE CONDUCTED BEFORE AND AFTER EACH STORM EVENT, AND EVERY 24 HOURS FOR EXTENDED STORM EVENTS, TO IDENTIFY AREAS THAT CONTRIBUTE TO EROSION AND SEDIMENT PROBLEMS OR ANY OTHER POLLUTANT DISCHARGES. IF ADDITIONAL MEASURES ARE NEEDED, REVISE THE EROSION CONTROL PLAN AND IMPLEMENT THE MEASURES IMMEDIATELY. DOCUMENT ALL INSPECTION FINDINGS AND ACTIONS TAKEN.
- CONTRACTOR SHALL USE BEST MANAGEMENT PRACTICES DURING CONSTRUCTION FOR CONTROL OF STORM WATER RUNOFF.
- BETWEEN OCTOBER 15 AND APRIL 15, EXPOSED SOIL SHALL BE PROTECTED FROM EROSION AT ALL TIMES. HAY BALES, FILTER BERMS, OR OTHER MEANS SHALL BE EMPLOYED TO PREVENT TURBID RUNOFF TO ADJOINING PROPERTIES.
- UNNECESSARY GRADING AND DISTURBING OR SOIL SHALL BE AVOIDED.
- ANY EXCESS MATERIAL SHALL BE DISPOSED OF OFF-SITE OR STOCKPILED IN A MANNER TO AVOID RUNOFF ONTO ADJOINING PROPERTIES.
- UPON COMPLETION OF CONSTRUCTION, ALL REMAINING EXPOSED AREAS SHALL BE PERMANENTLY RE-VEGETATED PER LANDSCAPE PLANS.
- ANY MATERIAL STOCKPILED DURING CONSTRUCTION SHALL BE COVERED WITH PLASTIC.
- DURING CONSTRUCTION, NO TURBID SITE WATER SHALL BE PERMITTED TO ENTER STORM DRAIN SYSTEM. USE OF SILT AND GREASE TRAPS, FILTER BERMS, OR HAY BALES MAY BE USED TO PREVENT SUCH DISCHARGE.
- CONTRACTOR SHALL COORDINATE WITH CONSTRUCTION MANAGER FOR ADDITIONAL EROSION CONTROL MEASURES DURING CONSTRUCTION PHASING.

LEGEND

- SILT FENCE
- STRAW WADDLE/FIBER ROLL
- DIRECTION OF FLOW WITH STORM DRAIN INSTALLED
- STABILIZED CONSTRUCTION ENTRANCE/EXIT

REVISIONS	BY

EROSION CONTROL PLAN

REGISTERED PROFESSIONAL ENGINEER
TODD R. CREMER
No. C 64561
Exp. 6/30/21
CIVIL
STATE OF CALIFORNIA

C2G / CIVIL CONSULTANTS GROUP, INC.

Engineers/Planners
44000 Old Calaveras Rd, Suite 6
Milpitas, CA 95035
T (831) 438-4420 F (831) 438-4420

DHAMI RESIDENCE
2100 OLD CALAVERAS RD
MILPITAS CA 95035

Date: 09/09/2020

Scale: 1" = 20"

Drawn: JR

Job: 9010.01

Sheet: C5.1

Of 9 Sheets

Drawing: Z:\Drawn\CAD\B0102.01 - Dhami Residence\Design\CAD\Sheets\B0102.01 - C5.1 - EROSION CONTROL PLAN.dwg

Layout: 24x36


Last Saved: Thu Sep 17, 2020 - 11:00am

Last Plotted: Fri Sep 18, 2020 - 12:23pm

By: jmr


3 Stabilized Construction Entrance/Exit

CASQA Detail TC-1



4 Velocity Dissipation Devices

CASQA Detail EC-10




* Length per ABAG Design Standards

Source for Graphics: California Stormwater BMP Handbook, California Stormwater Quality Association, January 2003. Available from www.cabmphandbooks.com.

Silt Fence

CASQA Detail SE-1




NOTES

- Construct the length of each reach so that the change in base elevation along the reach does not exceed 1/3 the height of the linear barrier, in no case shall the reach length exceed 500'.
- The last B'-0" of fence shall be turned up slope.
- Stake dimensions are nominal.
- Dimension may vary to fit field condition.
- Stakes shall be spaced at B'-0" maximum and shall be positioned on downstream side of fence.
- Stakes to overlap and fence fabric to fold around each stake one full turn. Secure fabric to stake with 4 staples.
- Stakes shall be driven tightly together to prevent potential flow-through of sediment at joint. The tops of the stakes shall be secured with wire.
- For end stake, fence fabric shall be folded around two stakes one full turn and secured with 4 staples.
- Minimum 4 staples per stake. Dimensions shown are typical.
- Cross barriers shall be a minimum of 1/3 and a maximum of 1/2 the height of the linear barrier.
- Maintenance openings shall be constructed in a manner to ensure sediment remains behind silt fence.
- Joining sections shall not be placed at sump locations.
- Sandbag rows and layers shall be offset to eliminate gaps.

Silt Fence

CASQA Detail SE-1



STANDARD BEST MANAGEMENT PRACTICE NOTES

- Solid and Demolition Waste Management:** Provide designated waste collection areas and containers on site away from streets, gutters, storm drains, and waterways, and arrange for regular disposal. Waste containers must be watertight and covered at all times except when waste is deposited. Refer to Erosion & Sediment Control Field Manual, 4th Edition (page C3) or latest.
- Hazardous Waste Management:** Provide proper handling and disposal of hazardous wastes by a licensed hazardous waste material hauler. Hazardous wastes shall be stored and properly labeled in sealed containers constructed of suitable materials. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-5 to C-6) or latest.
- Spill Prevention and Control:** Provide proper storage areas for liquid and solid materials, including chemicals and hazardous substances, away from streets, gutters, storm drains, and waterways. Spill control materials must be kept on site where readily accessible. Spills must be cleaned up immediately and contaminated soil disposed properly. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-7 to C-8, C-13 to C-14) or latest.
- Vehicle and Construction Equipment Service and Storage:** An area shall be designated for the maintenance, where on-site maintenance is required, and storage of equipment that is protected from stormwater run-on and runoff. Measures shall be provided to capture any waste oils, lubricants, or other potential pollutants and these wastes shall be properly disposed of off site. Fueling and major maintenance/repair, and washing shall be conducted off-site whenever feasible. Refer to Erosion & Sediment Control Field Manual, 4th Edition (page C9) or latest.
- Material Delivery, Handling and Storage:** In general, materials should not be stockpiled on site. Where temporary stockpiles are necessary and approved by the County, they shall be covered with secured plastic sheeting or tarp and located in designated areas near construction entrances and away from drainage paths and waterways. Barriers shall be provided around storage areas where materials are potentially in contact with runoff. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-11 to C-12) or latest.
- Handling and Disposal of Concrete and Cement:** When concrete trucks and equipment are washed on-site, concrete wastewater shall be contained in designated containers or in a temporary lined and watertight pit where wasted concrete can harden for later removal. If possible have concrete contractor remove concrete wash water from site. In no case shall fresh concrete be washed into the road right-of-way. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-15 to C-16) or latest.
- Pavement Construction Management:** Prevent or reduce the discharge of pollutants from paving operations, using measures to prevent run-on and runoff pollution and properly disposing of wastes. Avoid paving in the wet season and reschedule paving when rain is in the forecast. Residue from saw-cutting shall be vacuumed for proper disposal. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-17 to C-18) or latest.
- Contaminated Soil and Water Management:** Inspections to identify contaminated soils should occur prior to construction and at regular intervals during construction. Remediating contaminated soil should occur promptly after identification and be specific to the contaminant identified, which may include hazardous waste removal. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-19 to C-20) or latest.
- Sanitary/Septic Water Management:** Temporary sanitary facilities should be located away from drainage paths, waterways, and traffic areas. Only licensed sanitary and septic waste haulers should be used. Secondary containment should be provided for all sanitary facilities. Refer to Erosion & Sediment Control Field Manual, 4th Edition (page C-21) or latest.
- Inspection & Maintenance:** Areas of material and equipment storage sites and temporary sanitary facilities must be inspected weekly. Problem areas shall be identified and appropriate additional and/or alternative control measures implemented immediately, within 24 hours of the problem being identified.

STANDARD EROSION CONTROL NOTES

- Sediment Control Management:**
 - Tracking Prevention & Clean Up:** Activities shall be organized and measures taken as needed to prevent or minimize tracking of soil onto the public street system. A gravel or proprietary device construction entrance/exit is required for all sites. Clean up of tracked material shall be provided by means of a street sweeper prior to an approaching rain event, or at least once at the end of each workday that material is tracked, or, more frequently as determined by the County Inspector. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages B-31 to B-33) or latest.
 - Storm Drain Inlet and Catch Basin Inlet Protection:** All inlets within the vicinity of the project and within the project limits shall be protected with gravel bags placed around inlets or other inlet protection. At locations where exposed soils are present, staked fiber roles or staked silt fences can be used. Inlet filters are not allowed due to clogging and subsequent flooding. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages B-49 to B-51) or latest.
 - Storm Water Runoff:** No storm water runoff shall be allowed to drain in to the existing and/or proposed underground storm drain system or other above ground watercourses until appropriate erosion control measures are fully installed.
 - Dust Control:** The contractor shall provide dust control in graded areas as required by providing wet suppression or chemical stabilization of exposed soils, providing for rapid clean up of sediments deposited on paved roads, furnishing construction road entrances and vehicle wash down areas, and limiting the amount of areas disturbed by clearing and earth moving operations by scheduling these activities in phases.
 - Stockpiling:** Excavated soils shall not be placed in streets or on paved areas. Borrow and temporary stockpiles shall be protected with appropriate erosion control measures (tarps, straw bales, silt fences, etc.) to ensure silt does not leave the site or enter the storm drain system or neighboring watercourse.

- Erosion Control:** During the rainy season, all disturbed areas must include an effective combination of erosion and sediment control. It is required that temporary erosion control measures are applied to all disturbed soil areas prior to a rain event. During the non-rainy season, erosion control measures must be applied sufficient to control wind erosion at the site.
- Inspection & Maintenance:** Disturbed areas of the Project's site, locations where vehicles enter or exit the site, and all erosion and sediment controls that are identified as part of the Erosion Control Plans must be inspected by the Contractor before, during, and after storm events, and at least weekly during seasonal wet periods. Problem areas shall be identified and appropriate additional and/or alternative control measures implemented immediately, within 24 hours of the problem being identified.
- Project Completion:** Prior to project completion and signoff by the County Inspector, all disturbed areas shall be reseeded, planted, or landscaped to minimize the potential for erosion on the subject site.
- It shall be the Owner's/Contractor's responsibility to maintain control of the entire construction operation and to keep the entire site in compliance with the erosion control plan.
- Erosion and sediment control best management practices shall be operable year round or until vegetation is fully established on landscaped surfaces.

REVISIONS	BY

EROSION CONTROL DETAILS

REGISTERED PROFESSIONAL ENGINEER
TODD R. CREMER
No. C 64561
Exp. 6/30/21
CIVIL
STATE OF CALIFORNIA

C2G/CIVIL CONSULTANTS GROUP, INC.

C2G/CIVIL CONSULTANTS GROUP, INC.
Engineers/Planners
1400 Old Calaveras Rd., Suite 6
San Jose, CA 95128
T (408) 438-4420 F (408) 438-4420
By: jrmw

DHAMI RESIDENCE
2100 OLD CALAVERAS RD
MILPITAS CA 95035

Date: 09/09/2020

Scale: NTS

Drawn: JR

Job: 9010.01

Sheet: C5.2

Of 9 Sheets

PROJECT SCOPE & RATIONALE:


The scope of this project is a major remodel (>500 sq. ft) and bedroom addition to the main house. The bedroom count is proposed to be increased from 4 BR to 5 BR. This as-built plan is to show that the existing septic system serving the residence has adequate capacity for the intensification, and that the system largely meets current septic regulations.

The existing septic system serving the main house, installed under DEH permit #61131 in 1998, was recently investigated in August 2020. Excavations of representative sections of the existing drainfields were examined showing drainrock and drainpipe to be in good condition. A percolation test was conducted with results indicating the existing system to have more than 2.8 times the required infiltrative area and trench length. Soil profiles showed adequate separation to potential high groundwater, except for SP2 which had refusal about 1 ft below trench depth. Note that additional soil profiles are on file with DEH that further demonstrate adequate separation, although the specific locations of the test pits are apparently not identified. A geotech report addressing slope stability and setback to nearby steep slopes is being provided to support this proposal.

A small section of the lower drainfields appears to be sited in slope >30%, and it appears that some of the drainfields may not meet the 10 ft property line setback. Except for these variances, the rest of the system appears to meet code. The system should not be modified to eliminate these minor variances because this would reduce the overall capacity of the system which has been operating without any problems and because correction of the items would be an unnecessary expense.

Areas shaded gray on this side of property represent steep slope apparently >50% with height estimated at 25 ft and greater.

SITE PLAN PROVIDED BY DANIEL SILVERNAIL ARCHITECT, INC.



County of Santa Clara - Department of Environmental Health															
SOIL PERCOLATION TEST RECORDED MEASUREMENTS (Electronic Version by Chris Day, R.E.H.S.)															
OWNER/APPLICANT: Gursavai Dhami		SR# 864119		APN FILE # 029-31-011		DATE: 8/17/2020		PROJECT: 2100 Old Calaveras Rd, Milpitas, CA 95035							
LOCATION: 2100 Old Calaveras Rd, Milpitas, CA 95035		PHONE: 650-993-1045													
CONTACT PERSON: CHRIS DAY, R.E.H.S.															
HOLE #1		DEPTH: 4 ft		(21.1" on ruler)		HOLE #2		DEPTH: 3 1/2 ft		(26" on ruler)					
TIME		WATER LEVEL				TIME		WATER LEVEL							
START	FINISH	START	FINISH	Δ MIN	Δ INCH	MPH	START	FINISH	START	FINISH	Δ MIN	Δ INCH	MPH		
9:46	10:14	1 1/8	1 1/4	1/8	3	1/8	9:46	10:16	1 1/4	DRY	30				
10:15	10:47	1 1/8	1 1/4	1/8	3	1/8	10:17	10:47	1 1/4	DRY	30				
10:48	11:15	1 1/8	1 1/4	1/8	3	3/8	10:48	10:58	1 1/8	7/8	28	3	7/8	3	
10:59	11:26	1 1/8	1 1/4	1/8	3	3/8	10:59	11:26	1 1/8	7/8	28	3	3/4	3	
11:16	11:45	1 1/8	1 1/4	1/8	3	3/8	11:16	11:20	1 1/8	7/8	28	3	7/8	3	
11:46	12:12	1 1/8	1 1/4	1/8	3	3/8	11:22	11:32	1 1/8	3/4	17/8	10	1 1/2	3	
12:13	12:41	1 1/8	1 1/4	1/8	3	3/8	11:33	11:44	1 1/8	3/4	27/8	11	1 7/8	3	
12:41	13:16	1 1/8	1 1/4	1/8	3	3/8	11:45	11:55	1 1/8	7/8	28	10	1 1/2	3	
HOLE #3		DEPTH: 4 ft		(39 1/2" on ruler)		HOLE #4		DEPTH: 3 1/2 ft		(26 5/8" on ruler)					
TIME		WATER LEVEL				TIME		WATER LEVEL							
START	FINISH	START	FINISH	Δ MIN	Δ INCH	MPH	START	FINISH	START	FINISH	Δ MIN	Δ INCH	MPH		
9:48	10:18	25	7/8	1/2	3	1 1/2	9:50	10:20	3 3/4	20	1 1/4	30	1 1/2	20	
10:19	10:29	25	7/8	1/2	3	1 1/2	10:21	10:31	3 3/4	1 1/4	20	1 1/4	20		
10:30	11:20	25	7/8	1/2	3	5/8	10:52	11:22	3 3/4	30	7/8	30	1 1/8	27	
11:21	11:50	25	7/8	1/2	3	5/8	11:23	11:53	32	31	30	2	30		
HOLE #5		DEPTH: 3 1/2 ft		(20 1/2" on ruler)		HOLE #6		DEPTH: 4 ft		(20 3/4" on ruler)					
TIME		WATER LEVEL				TIME		WATER LEVEL							
START	FINISH	START	FINISH	Δ MIN	Δ INCH	MPH	START	FINISH	START	FINISH	Δ MIN	Δ INCH	MPH		
10:23	10:53	26	1/2	DRY	30		10:25	10:28	3 3/4	1 1/4	20	1 1/4	38		
10:54	11:24	26	1/2	DRY	30		10:29	10:32	3 3/4	1 1/4	20	1 1/4	38		
11:04	11:14	26	1/2	DRY	30		11:27	11:57	3 3/4	3/4	5/8	30	1 1/8	27	
11:14	11:24	26	1/2	DRY	30										
11:24	11:34	26	1/2	DRY	30										
11:34	11:44	26	1/2	DRY	30										
11:44	12:04	26	1/2	DRY	28										
STOPWATCH READINGS BEING TAKEN AT 3:02.0 p.m.															
6:00	7:58	26	1/2	25	8.0	5	1.6								
8:00	8:17	26	1/2	25	8.3	5	1.9								
8:30	8:46	26	1/2	25	8.4	5	1.9								
STABILIZED															
Hole		1		2		3		4		5		6			
Stabilized MPI		R		11		3		11		27		17		29	
Adjusted Stabilized MPI		R _a		= R x 1.4		15		4		15		38		2.4	41
Average Adjusted Stabilized MPI R _a = (Σ R _a) / # Holes															
19															
# Bedrooms 5 FOR OFFICE USE ONLY															
Tank Size (Gall)										Each Line (Inch)					