- wall subdrain, (C) During placement of retaining wall backfill, (D) For observation of cut/fill slopes.





DRAINAGE CALCULATIONS AND QUANTITIES:

DRAINAGE:

- 1. Surface drainage should include provision for positive gradients so that run-off is not permitted to pond adjacent to foundations and pavements. Surface runoff should be diverted away from foundations. A minimum slope of 2 percent for 5 feet is recommended around structures.
- 2. Maintenance of the drainage system is the sole responsibility of the owner.
- 3. A detention facility has been designed keep the discharge of storm water to pre-development standards for the 100 year storm based off the 10 year pre-development flow rates. The rational method was used in accordance with the Santa Clara County Drainage Manual.
- 4. The system was designed using new impervious area of 5107 ft². This area includes the residence and driveway surfaces.

QUANTITIES:

- 1. The storage device consists of a 12 feet long by 12 inch diameter sealed ADS pipe or equivalent. Drainage into the
- detention facility shall be from impervious surfaces created during construction. 2. The retaining wall backdrain shall consist of 100 feet of 4 inch diameter perforated SDR 35 or equivalent pipe. Cleanouts
- shall be provided at both ends of the backdrain. 3. Solid 4 inch SDR 35 pipe shall be used as conduit from the rain leaders and retaining wall backdrain.

Drainage Pipe Quantities/Slopes

| Pipe Use | Pipe Type | Pipe Size (in) | Total Pipe Length (ft) | Pipe Slope (%) |
|---------------------|------------------|----------------|------------------------|----------------|
| Detention Facility* | Solid NDS | 36 | 60 | Level |
| Backdrain | Perforated SDR35 | 4 | 180 | 2% |
| Conduit/Overflow | Solid SDR35 | 4 | 90 | < 30% |
| Orofice | Solid SDR35 | 2 | 10 | < 30% |
| T-Dissipater | Perforated SDR35 | 6 | 7 | Level |

*Total Volume of Detention Facility to be Greater Than 465.4 Cubic Feet

DISTURBED AREA

CONSTRUCTION ENTRANCE PER BMP-1

2042 2033.7

2030-



AND CONCRETE WASHOUT TUB

2004 2026.59 ep/dwy

:

RE HYDRAN

+2002 +2023.65 fh

chk

2005 2028.40 dwy

PORTABLE RESTROOM -

2093 2034.64

2003 2030.ø







SEPTIC DESIGN SHEETS.





—___ Flow EI: 232.7







| E | | |
|-----------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---|
| 1. 2. | Best Management Practices (BMP's) (Materials and Their Installation) shall be applied according to the County of Santa Clara's BMP. Between October 15th and April 15th, exposed soil shall be protected from erosion at all times. Hay bales, filter berms, bioswales or other means shall be employed to prevent turbid runoff to the drainage area or to adjoining properties. These measures are intended to be used for interim erosion and | |
| 3 | sediment water pollution control only and are not to be used for final elevations or permanent improvements. | |
| 4. | Actual grading shall begin within 30 days of vegetation removal or the area shall be planted to control erosion. | |
| 5. | Contractor shall be responsible for monitoring erosion and sediment control prior to, during, and after storm events, and shall promptly correct any deficiencies noted | |
| 6. | Any excess material shall be disposed of off-site or stockpiled in a manner to avoid runoff onto adjoining properties. | |
| 7. 8. | Any material stockpiled during construction shall be covered with plastic. Reasonable care shall be taken when hauling any earth, sand, gravel, stone, debris, paper, or any other substance over any public street, alley or other | |
| | public place. Should any blow, spill or track over and upon said public or adjacent private property, immediately remedy shall occur. | |
| 9. | construction operations shall be carried out in such a manner that erosion and water pollution will be minimized. State and local laws concerning pollution abatement shall be complied with. | |
| 10 11 | Contractor shall provide dust control as required by federal, state, and local agency requirements. Provide temporary "effective soil cover" on all inactive disturbed areas (areas which have not been disturbed for at least 14 days) prior to installation of final landscaping, if required due to project scheduling. All areas exposed during construction, if not permanently landscaped per plans, shall be seeded with the following native California erosion control seed mixture and protected with erosion control blankets. | |
| | Seed Mixture (or equivalent as approved): -Prostrate Hordeum Californicum (Prostrate California Barley) @ 16 lb/acre | |
| | -Elymus Glaucus (Berkeley Blue Wildrye) @ 12 lo/acre -Bromus Carinatus (SF Bay Area California Brome) @ 10 lb/acre | |
| | -Vulpia Microstachys (Three-weeks Fescue) @ 5 lb/acre | |
| 12 | . Establish and maintain effective perimeter controls and stabilize all construction entrances and exits to sufficiently control erosion and sediment discharges from the site (straw wattles where indicated on plans). | |
| RI | QUIRED INSPECTION: | |
| 1. | Special inspections shall be performed per the approved geotechnical report, and the construction documents prepared by the design professionals shall be used to determine compliance. | |
| SI N/ | TE HOUSEKEEPING: te: No on-site storage of materials or supplies. All materials and construction shall be kent on this property. At no time shall materials or construction enter | |
| th | e adjacent parcel. | |
| 1. • | Construction Materials: All chemicals shall be stored in water tight containers off-site. | |
| • | Exposure of construction materials shall be minimized. | |
| • 2. | Best Management Practices to prevent the on-site tracking of loose construction and landscape materials shall be implemented. Waste Management: | |
| • | Disposal of any rinse or wash waters or materials on impervious or pervious site surfaces or into the storm drain system shall be prevented. | |
| · | drainage facility. | |
| • | Sanitation facilities shall be inspected regularly for leaks and spills and cleaned or replaced as necessary. | |
| • | Discharges from waste disposal containers to the storm water drainage system or receiving water shall be prevented. | |
| • | Stockpiled waste materials shall be contained and securely protected from wind and rain at all times unless actively being used. Procedures that effectively address bazardous and non-bazardous spills shall be implemented | i |
| • | Equipment and materials for cleanup of spills shall be available on site and that spills and leaks shall be cleaned up immediately and disposed of | |
| | properly. All concrete shall be poured using self contained concrete trucks | |
| • | A stabilized construction entrance per BMP-2/3 shall be maintained at all times. | |
| • | A suitable portable restroom shall be maintained on-site at all times during construction. | i |
| 3. | Vehicle Storage and Maintenance: | |
| • | No more than two contractors vehicles allowed on-site. | |
| • | Measures shall be taken to prevent oil, grease, or fuel to leak into the ground, storm drains or surface waters. | 9 |
| • | All equipment or vehicles, which are to be fueled, maintained and stored onsite shall be in a designated area fitted wit appropriate BMPs as approved by the project civil engineer. | |
| • | Leaks shall be immediately cleaned and leaked materials shall be disposed of properly. | |
| LA | NDSCAPE MATERIALS: | |
| • | Contain fertilizers and other landscape materials when they are not actively being used. | |
| • | Discontinue the application of any erodible landscape material within 2 days before a forecasted rain event or during periods of precipitation. Apply erodible landscape material at quantities and application rates according to manufacture recommendations or based on written specification. Stack erodible landscape material on pallets and covering or storing such materials when not being used or applied. | |
| | INSTRUCTION WASTE: construction waste including but not limited to the concrete wash basin shall be discarded in a county approved location. It is the responsibility of the | |
| cc th | ntractor to comply with all county and state regulations for disposal of construction materials. The contractor shall track waste and provide the county with applicable Cal Green Construction Waste Management Form. These forms can be found on the CalGreen website: http://www.hcd.ca.gov/calgreen.html | |
| U 1. | ILITIES: All pipe systems shall be installed in accordance with ASTM D2321. | |
| | specified. | |
| 3 | Tracer wires shall be installed on all thermoplastic utilities. Caution tape shall be run above all bedding sand. Utilities in joint trenches to be separated per state and county standards. | |
| 2018 C | JST CONTROL: Impliance with standard dust control measures set forth by land engineering and Bay Area Air Quality Management | |
| 1984.E. ep | | |
| → 3@36 in DI | AMETER BY 20 ft LONG DETENTION | |
| FACILITY | | |
| SEALED O | IS 60 ft. PLACE ON CONTOUR, SEE | |
| | CTION FOR LAYOUT(P). | |
| DESIGNED | = 501.5 CUBIC FEET. | |
| | OUTLET T-DISSIPATER, | |
| CONFORM SEE BMP- | I O SURFACE (P) FOR ADDITIONAL | |
| | | |



OS I OS

PROJECT: 16-158-SCL

DATE: OCT.27.2017

DRAWN: PE/GAB

SCALE: 1"=10'

SHEET

PRO

INFORMATION













Note: The south and east retaining walls have been added to this version of the plans.

Пе



| TOW | BOW | Heights (ft) | WALL NAME |
|--------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 2017.8 | 2016.3 | 1.5 | E. WALL |
| 2016.8 | 2013.1 | 3.7 | E. WALL |
| 2015.8 | 2009.7 | 6.1 | E. WALL |
| 2014.8 | 2007.0 | 7.8 | E. WALL |
| 2013.8 | 2005.7 | 8.1 | E. WALL |
| 2012.8 | 2004.5 | 8.3 | E. WALL |
| 2012.3 | 2003.1 | 9.2 | E. WALL |
| 2011.8 | 2001.8 | 10.0 | E. WALL (Corner) |
| 2007.9 | 2000.3 | 7.6 | E. WALL & S. WALL (Corner) |
| 2005.9 | 2001.4 | 4.5 | S. WALL LOWER |
| 2005.9 | 2002.0 | 3.9 | S. WALL LOWER |
| 2005.9 | 2002.5 | 3.4 | S. WALL LOWER |
| 2005.9 | 2003.5 | 2.4 | S. WALL LOWER |
| 2005.9 | 2004.7 | 1.2 | S. WALL LOWER |
| 2006.0 | 2006.0 | 0.0 | S. WALL LOWER |
| 2011.8 | 2007.9 | 3.9 | S. WALL UPPER (Corner) |
| 2011.8 | 2007.9 | 3.9 | S. WALL UPPER |
| 2011.8 | 2007.9 | 3.9 | S. WALL UPPER |
| 2011.8 | 2007.9 | 3.9 | S. WALL UPPER |
| 2011.8 | 2007.9 | 3.9 | S. WALL UPPER |
| 2011.8 | 2007.9 | 3.9 | S. WALL UPPER |
| | TOW2017.82016.82015.82014.82013.82012.32012.32012.32007.92005.92005.92005.92005.92005.92005.92005.92005.92005.92005.92011.82011.82011.82011.82011.82011.82011.82011.82011.82011.8 | TOWBOW2017.82016.32016.82013.12015.82009.72014.82007.02013.82005.72012.82004.52012.32003.12011.82001.82005.92001.42005.92002.02005.92002.02005.92002.52005.92002.52005.92004.72005.92004.72005.92004.72006.02006.02011.82007.92011.82007.92011.82007.92011.82007.92011.82007.92011.82007.9 | TOWBOWHeights (ft)2017.82016.31.52016.82013.13.72015.82009.76.12014.82007.07.82013.82005.78.12012.82004.58.32012.32003.19.22011.82001.810.02007.92000.37.62005.92001.44.52005.92002.03.92005.92002.53.42005.92004.71.22005.92004.71.22005.92004.71.22005.92004.73.92011.82007.93.92011.82007.93.92011.82007.93.92011.82007.93.92011.82007.93.92011.82007.93.92011.82007.93.92011.82007.93.92011.82007.93.92011.82007.93.92011.82007.93.92011.82007.93.92011.82007.93.92011.82007.93.92011.82007.93.9 |

Note: Wall spacing 8 $\frac{1}{2}$ feet between piers 7 through 11. Pier spacing between piers 4 through 6 is 5 feet. All other spacing 10 feet. (Spacing per structural engineer).



