COUNTY OF SANTA CLARA <u>General Construction</u> <u>Specifications</u>

GENERAL CONDITIONS

- ALL CONSTRUCTION WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE SOILS AND/OR GEOTECHNICAL REPORT PREPARED BY BAEZ GEOTECHNICAL GROUP; PROJECT NO. G184.02 AND DATED JUNE 11, 2021 THIS REPORT IS SUPPLEMENTED BY: 1) THESE PLANS AND SPECIFICATIONS, 2) THE COUNTY OF SANTA CLARA STANDARD DETAILS. 3) THE COUNTY OF SANTA CLARA STANDARD SPECS, 4) STATE OF CALIFORNIA STANDARD DETAILS, 5) STATE OF CALIFORNIA STANDARD SPECIFICATIONS. IN THE EVENT OF CONFLICT THE FORMER SHALL TAKE PRECEDENCE OVER THE LATTER. THE PERFORMANCE AND COMPLETION OF ALL WORK MUST BE TO THE SATISFACTION OF THE COUNTY. DEVELOPER IS RESPONSIBLE FOR INSTALLATION OF THE IMPROVEMENTS SHOWN ON THESE
- PLANS AND HE OR HIS SUCCESSOR PROPERTY OWNERS ARE RESPONSIBLE FOR THEIR CONTINUED MAINTENANCE DEVELOPER SHALL BE RESPONSIBLE FOR CORRECTION OF ANY ERRORS OR OMISSIONS IN
- THESE PLANS. THE COUNTY SHALL BE AUTHORIZED TO REQUIRE DISCONTINUANCE OF ANY WORK AND SUCH CORRECTION AND MODIFICATION OF PLANS AS MAY BE NECESSARY TO COMPLY WITH COUNTY STANDARDS OR CONDITIONS OF DEVELOPMENT APPROVAL. DEVELOPER SHALL OBTAIN ENCROACHMENT PERMITS FROM THE SANTA CLARA VALLEY WATER DISTRICT AND CALIFORNIA DEPARTMENT OF TRANSPORTATION WHERE NEEDED. COPIES OF THESE PERMITS SHALL BE KEPT AT THE JOB SITE FOR REVIEW BY THE COUNTY'S INSPECTOR
- DEVELOPER SHALL REMOVE OR TRIM ALL TREES TO PROVIDE AN UNOBSTRUCTED FIFTEEN 3. SURPLUS EARTH FILL MATERIAL SHALL BE PLACED IN A SINGLE (8" MAX) THICK LAYER (15) FOOT VERTICAL CLEARANCE FOR ROADWAY AREA.
- THIS PLAN AUTHORIZES THE REMOVAL OF ONLY THOSE TREES WITH TRUNK DIAMETERS 4. NO ORGANIC MATERIAL SHALL BE PLACED IN ANY FILL. NO TREES SHALL BE REMOVED OUTSIDE 8 GREATER THAN 12 INCHES MEASURED 4.5 FEET ABOVE THE GROUND THAT ARE SHOWN TO BE REMOVED UNLESS AN AMENDED PLAN IS APPROVED OR A SEPARATE TREE REMOVAL PERMIT IS OBTAINED FROM THE PLANNING OFFICE. IT IS THE CONTRACTOR'S RESPONSIBILITY TO ENSURE THAT REMOVAL OF ADDITIONAL TREES HAS BEEN PERMITTED. 6. MAXIMUM CUT SLOPE SHALL BE 2 HORIZONTAL TO 1 VERTICAL. MAXIMUM FILL SLOPE SHALL BE 9. DEVELOPER SHALL PROVIDE ADEQUATE DUST CONTROL AS REQUIRED BY THE COUNTY
- INSPECTOR.
- ALL PERSONS MUST COMPLY WITH SECTION 4442 OF THE PUBLIC RESOURCES CODE AND SECTION 13005 OF THE HEALTH AND SAFETY CODE RELATING TO THE USE OF SPARK ARRESTERS.
- UPON DISCOVERING OR UNEARTHING ANY BURIAL SITE AS EVIDENCED BY HUMAN SKELETAL REMAINS OR ARTIFACTS, THE PERSON MAKING SUCH DISCOVERY SHALL IMMEDIATELY NOTIFY THE COUNTY CORONER AT (408) 454-2520 AND LAND DEVELOPMENT ENGINEERING OFFICE AT (408) 299-5730. NO FURTHER DISTURBANCE OF THE SITE MAY BE MADE EXCEPT AS AUTHORIZED BY THE LAND DEVELOPMENT OFFICE IN ACCORD WITH PROVISIONS OF THIS ORDINANCE (COUNTY ORDINANCE CODE SECTION B6–18).
- THESE PLANS ARE FOR THE WORK DESCRIBED IN THE SCOPE OF WORK ONLY. A
- SEPARATE PERMIT WILL BE REQUIRED FOR THE SEPTIC LINE CONSTRUCTION. ANY DEVIATION FROM THESE APPROVED PLANS SHALL BE RE-APPROVED IN WRITING BY THE COUNTY ENGINEER PRIOR TO CONSTRUCTION.

CONSTRUCTION STAKING

- THE DEVELOPER'S ENGINEER IS RESPONSIBLE FOR THE INITIAL PLACEMENT AND REPLACEMENT OF CONSTRUCTION GRADE STAKES. THE STAKES ARE TO BE ADEQUATELY IDENTIFIED, LOCATED, STABILIZED, ETC. FOR THE CONVENIENCE OF CONTRACTORS. LATERAL OFFSET OF STAKES SET FOR CURBS AND GUTTERS SHALL NOT EXCEED 2 1/2 FEET FROM BACK OF CURB.
- ANY PROPERTY LINE STAKES OR ROAD MONUMENTS DISTURBED DURING CONSTRUCTION SHALL BE REPLACED BY DEVELOPER'S ENGINEER AND LICENSED LAND SURVEYOR.
- PROPERTY LINE STAKING MUST BE PERFORMED BY THE PROJECT ENGINEER OR LAND SURVEYOR TO ESTABLISH OR RE-ESTABLISH THE PROJECT BOUNDARY AND SHALL BE INSPECTED BY THE COUNTY INSPECTOR PRIOR TO THE BEGINNING OF THE WORK.
- PROPER CONSTRUCTION STAKES SHALL BE SET IN THE FIELD BY THE PROJECT ENGINEER OR LAND SURVEYOR AND VERIFIED BY THE COUNTY INSPECTOR PRIOR TO THE COMMENCEMENT OF GRADING.
- IN ACCORDANCE WITH THE CALIFORNIA PROFESSIONAL LAND SURVEYORS' ACT (BUSINESS AND PROFESSIONS CODE) CHAPTER 15 SECTIONS 8771 AND 8725.1, CALIFORNIA PENAL CODE 605, AND CALIFORNIA GOVERNMENT CODE 27581, ANY PERSON PERFORMING CONSTRUCTION ACTIVITIES THAT WILL OR MAY DISTURB AN EXISTING ROADWAY/STREET MONUMENT, PROPERTY CORNER, OR ANY OTHER PERMANENT SURVEYED MONUMENT AND/OR AS SHOWN ON THIS TENTATIVE MAP SHALL ENSURE THAT A CORNER RECORD AND/OR RECORD OF SURVEY ARE FILED WITH THE OCUNTY SURVEYOR OFFICE PRIOR TO DISTURBING SAID MONUMENTS. ALL DISTURBED OR DESTROYED MONUMENTS SHALL BE RESET AND FILED IN COMPLIANCE WITH SECTION 8771.

CONSTRUCTION INSPECTION

- CONTRACTOR SHALL NOTIFY PERMIT INSPECTION UNIT, SANTA CLARA COUNTY PRIOR TO COMMENCING WORK AND FOR FINAL INSPECTION OF WORK AND SITE.
- THE COUNTY REQUIRES A MINIMUM OF 24 HOURS ADVANCE NOTICE FOR GENERAL INSPECTION, 48 HOURS FOR ASPHALT CONCRETE INSPECTION. INSPECTION BY SANTA CLARA COUNTY SHALL BE LIMITED TO INSPECTION OF
- MATERIALS AND PROCESSES OF CONSTRUCTION TO OBSERVE THEIR COMPLIANCE WITH PLANS & SPECIFICATIONS BUT DOES NOT INCLUDE RESPONSIBILITY FOR THE SUPERINTENDENT OF CONSTRUCTION, SITE CONDITIONS, EQUIPMENT OR PERSONNEL CONTRACTOR SHALL NOTIFY THE COUNTY LAND DEVELOPMENT INSPECTOR AT PHONE (408) 299-6868 AT LEAST 24 HOURS PRIOR TO COMMENCING WORK AND FOR FINAL INSPECTION OF WORK AND SITE.
- DEVELOPER AND/OR HIS AUTHORIZED REPRESENTATIVE MUST SUBMIT WRITTEN REQUEST FOR FINAL INSPECTION AND ACCEPTANCE. SAID REQUEST SHALL BE DIRECTED TO THE INSPECTION OFFICE NOTED ON THE PERMIT FORM.
- THE CONTRACTOR SHALL PROVIDE TO THE COUNTY CONSTRUCTION INSPECTOR WITH PAD ELEVATION AND LOCATION CERTIFICATES, PREPARED BY THE PROJECT ENGINEER OR LAND SURVEYOR, PRIOR COMMENCEMENT OF THE BUILDING FOUNDATION.

SITE PREPARATION (CLEARING AND GRUBBING)

- EXISTING TREES AUTHORIZED FOR REMOVAL, ROOTS, AND FOREIGN MATERIAL IN AREAS 3. SEE EXISTING TREE PROTECTION DETAILS FOR MORE INFORMATION. TO BE IMPROVED WILL BE REMOVED TO AN AUTHORIZED DISPOSAL SITE AS FOLLOWS:
- TO A MINIMUM DEPTH OF TWO FEET BELOW THE FINISHED GRADE OF PROPOSED ROADWAYS (EITHER PRIVATE OR TO BE DEDICATED TO PUBLIC USE)
- FROM AREAS AFFECTED BY THE PROPOSED GRADING EXCEPT WHERE NOTED ON THE PLANS.
- IT SHALL BE THE RESPONSIBILITY OF THE DEVELOPER TO MOVE OR RELOCATE UTILITY POLES AND OTHER OBSTRUCTIONS IN THE WAY OF CONSTRUCTION.

<u>UTILITY LOCATION, TRENCHING & BACKFILI</u>

- CONTRACTOR SHALL NOTIFY USA (UNDERGROUND SERVICE ALERT) AT 1-800-277-2600 A MINIMUM OF 24 HOURS BEFORE BEGINNING UNDERGROUND WORK FOR VERIFICATION OF THE LOCATION OF UNDERGROUND UTILITIES.
- ACCURATE VERIFICATION AS TO SIZE, LOCATION, AND DEPTH OF EXISTING UNDERGROUND CONDUITS OR FACILITIES SHALL BE THE INDIVIDUAL CONTRACTORS RESPONSIBILITY. PLAN LOCATIONS ARE APPROXIMATE AND FOR GENERAL INFORMATION ONLY.
- ALL UNDERGROUND INSTALLATIONS SHALL BE IN PLACE AND THE TRENCH BACKFILLED AND COMPACTED BEFORE PLACING AGGREGATE BASE MATERIAL OR SURFACE STRUCTURES. SURFACING MAY BE DONE IF THE UTILITY COMPANY CONCERNED INDICATES BY LETTER THAT IT WILL BORE. UNLESS SPECIFICALLY AUTHORIZED BY THE COUNTY, GAS AND WATER MAINS SHALL BE INSTALLED OUTSIDE THE PAVED AREAS.
- TRENCH BACKFILL IN EXISTING PAVEMENT AREAS SHALL BE SAND MATERIAL IN ACCORDANCE WITH THE APPLICABLE PROVISIONS OF THE STATE SPECIFICATIONS. THE STRUCTURAL SECTION FOR TRENCH REPLACEMENT SHALL CONSIST OF NOT LESS THAN 12 INCHES OF APPROVED AGGREGATE BASE MATERIAL COMPACTED TO A RELATIVE COMPACTION OF AT LEAST 95% AND 4 INCHES OF HOT ASPHALT CONCRETE PLACED IN TWO LIFTS. TRENCH RESTORATION FOR HIGHER TYPE PAVEMENTS SHALL BE MADE IN KIND OR AS DIRECTED BY THE COUNTY.
- TRENCH BACKFILL IN NEW CONSTRUCTION AREAS SHALL BE SAND MATERIAL COMPACTED TO A RELATIVE COMPACTION OF AT LEAST 90%. THE REQUIREMENT FOR SELECT MATERIAL MAY BE WAIVED BY COUNTY IF THE NATIVE SOIL IS SUITABLE FOR USE AS TRENCH BACKFILL BUT THE COMPACTION REQUIREMENTS WILL NOT BE
- THEREBY WAIVED. BACKFILL AND TRENCH RESTORATION REQUIREMENTS SHALL APPLY AS MINIMUM
- STANDARDS TO ALL UNDERGROUND FACILITIES INSTALLED BY OTHER FIRMS OR PUBLIC AGENCIES.

<u>RETAINING WALLS</u>

REINFORCED CONCRETE AND CONCRETE MASONRY UNIT RETAINING WALLS SHALL HAVE FOUNDATION AND REINFORCEMENT INSPECTED BY THE COUNTY ENGINEERING INSPECTOR AND ENGINEER OF RECORD PRIOR TO POURING THE FOUNDATION AND FORMING THE WALL. 2. SEGMENTAL BLOCK RETAINING WALLS SHALL HAVE FOUNDATION AND REINFORCEMENT INSPECTED BY THE COUNTY ENGINEERING INSPECTOR.

<u>GRADING</u>

- 1. EXCAVATED MATERIAL SHALL BE PLACED IN THE FILL AREAS DESIGNATED OR SHALL BE HAULED AWAY FROM THE SITE TO A COUNTY APPROVED DISPOSAL SITE. WHERE FILL MATERIAL IS TO BE PLACED ON NATURAL GROUND, IS SHALL BE STRIPPED OF ALL VEGETATION. TO ACHIEVE A PROPER BOND WITH THE FILL MATERIAL, THE SURFACE OF THE GROUND SHALL BE SCARIFIED TO DEPTH OF 6" BEFORE FILL IS PLACED. WHERE NATURAL GROUND IS STEEPER THAN 5:1, IT SHALL BE BENCHED AND THE FILL KEYED IN TO ACHIEVE STABILITY. WHERE NEW FILL IS TO BE PLACED ON EXISTING FILL THE EXISTING FILL SHALL BE REMOVED UNTIL MATERIAL COMPACTED TO 90% RELATIVE COMPACTION IS EXPOSED. THEN THE NEW FILL MATERIAL SHALL BE PLACED AS PER THESE CONSTRUCTION NOTES. FILL MATERIAL SHALL BE PLACED IN UNIFORM LIFTS NOT EXCEEDING 6" IN UNCOMPACTED THICKNESS. BEFORE COMPACTION BEGINS, THE FILL SHALL BE BROUGHT TO A WATER CONTENT THAT WILL PERMIT PROPER COMPACTION BY EITHER 1) AERATING THE FILL IF IT IS TOO WET OR 2) MOISTENING THE FILL WITH WATER IF IT IS TOO DRY. EACH LIFT SHALL BE THOROUGHLY MIXED BEFORE COMPACTION TO ENSURE A UNIFORM DISTRIBUTION OF MOISTURE. EXCESS CUT MATERIAL SHALL NOT BE SPREAD OR STOCKPILED ON THE SITE.
- COMPACTED TO WITHSTAND WEATHERING IN THE AREA(S) DELINEATED ON THE PLAN.
- OF CUT, FILL OR ROADWAY AREAS. 5. THE UPPER 6" OF SUBGRADE BELOW DRIVEWAY ACCESS ROAD OR PARKING AREA SHALL BE
- COMPACTED TO 95% OF MAXIMUM DENSITY. 2 HORIZONTAL TO 1 VERTICAL.

LOCATION	CUT (C.Y.)	FILL (C.Y.)	VERT. DEPTH
HOUSE	0	±94	0/±0.9
ADU	0	±36	0/±0.8
OFFICE	0	±317	0/±1.4
WAREHOUSE	0	±166	0/±1.0
DRIVEWAY (HOUSE)	±174	±9	$\pm 1.3 / \pm 0.6$
DRIVEWAY (OFFICE)	±105	±336	$\pm 0.9/\pm 1.5$
DRIVEWAY (AGG BASE)	±455	±40	±1.5/±1.0
POND #1	±491	0	±2.5/0
POND #2	±27	±15	±1.2/±1.3
TOTAL	±1,252	±1,013	

EXCESS CUT TO BE SPREAD OVER CROP AND ORCHARD AREAS

- NOTE: FILL VOLUMES INCLUDE 10% SHRINKAGE. EXCESS MATERIAL SHALL BE OFF HAULED TO A COUNTY APPROVED DUMP SITE. 7. NOTIFY SOILS ENGINEER TWO (2) DAYS PRIOR TO COMMENCEMENT OF ANY GRADING WORK TO
- COORDINATE THE WORK IN THE FIELD. 8. ALL MATERIALS FOR FILL SHOULD BE APPROVED BY THE SOILS ENGINEER BEFORE IT IS
- BROUGHT TO THE SITE. 9. THE UPPER 6" OF THE SUBGRADE SOIL SHALL BE SCARIFIED, MOISTURE CONDITIONED AND
- COMPACTED TO A MINIMUM RELATIVE COMPACTION OF 95% 10. ALL AGGREGATE BASE MATERIAL SHALL BE COMPACTED TO A MINIMUM 95% RELATIVE COMPACTION.
- 11. THE GEOTECHNICAL PLAN REVIEW LETTER MUST BE REVIEWED AND APPROVED BY THE COUNTY GEOLOGIST PRIOR TO FINAL APPROVAL BY THE COUNTY ENGINEER FOR BUILDING OCCUPANCY. 12. THE PROJECT GEOTECHNICAL ENGINEER SHALL PERFORM COMPACTION TESTING AND PRESENT
- THE RESULTS TO THE COUNTY ENGINEERING INSPECTOR PRIOR TO THE CONSTRUCTION OF ANY PAVED AREA. 13. GRADING WORK BETWEEN OCTOBER 15TH AND APRIL 15TH IS AT THE DISCRETION OF THE
- SANTA CLARA COUNTY GRADING OFFICIAL 14. TOTAL DISTURBED AREA FOR THE PROJECT 75,825 SF.
- 15. WDID NO.__
- 16. THE INSPECTOR MAY VERIFY THAT A VALID NOTICE OF INTENT (NOI) HAS BEEN ISSUED BY THE STATE AND THAT A CURRENT AND UP TO DATE STORM WATER POLLUTION PREVENTION PLAN (SWPPP) IS AVAILABLE ON SITE.

TREE PROTECTION

- 1. FOR ALL TREES TO BE RETAINED WITH A CANOPY IN THE DEVELOPMENT AREA OR INTERFACES WITH THE LIMITS OF GRADING FOR ALL PROPOSED DEVELOPMENT ON SITE, THE TREES SHALL BE PROTECTED BY THE PLACEMENT OF RIGID TREE PROTECTIVE FENCING, CONSISTENT WITH THE COUNTY INTEGRATED LANDSCAPE GUIDELINES, AND INCLUDE THE FOLLOWING:
- A. FENCING SHOULD BE PLACED ALONG THE OUTSIDE EDGE OF THE DRIPLINE OF THE TREE OR GROVE OF TREES.
- B. THE FENCING SHALL BE MAINTAINED THROUGHOUT THE SITE CONSTRUCTION PERIOD AND SHALL BE INSPECTED PERIODICALLY FOR DAMAGE AND PROPER FUNCTION. C. FENCING SHALL BE REPAIRED, AS NECESSARY, TO PROVIDE A PHYSICAL BARRIER FROM CONSTRUCTION ACTIVITIES.
- D. SIGNAGE STATING, "WARNING- THIS FENCING SHALL NOT BE REMOVED WITHOUT PERMISSION FROM THE SANTA CLARA COUNTY PLANNING OFFICE (408) 299-5770. COUNTY OF SANTA BE PLACED ON THE TREE PROTECTIVE FENCING UNTIL FINAL OCCUPANCY.
- BE SECURELY IN PLACED AND INSPECTED BY THE LAND DEVELOPMENT ENGINEERING INSPECTOR.

ACCESS ROADS AND DRIVEWAYS

- 1. DRIVEWAY LOCATIONS SHALL BE AS SHOWN ON THE IMPROVEMENT PLANS WITH CENTERLINE STATIONING. THE MINIMUM CONCRETE THICKNESS SHALL BE 6 INCHES THROUGHOUT (WITH A MAXIMUM APPROACH SLOPE OF 1 1/4 INCHES PER FOOT).
- 2. ALL DRIVEWAY OR COMMON ACCESS ROAD SECTIONS IN EXCESS OF 15 LONGITUDINAL SLOPE MUST BE PAVED WITH A MINIMUM 2-INCH ASPHALT LIFT OR FULL DEPTH CONCRETE LIFT PRIOR TO ANY COMBUSTIBLE FRAMING.
- 3. THE OWNER AND PRIME CONTRACTOR ARE RESPONSIBLE FOR MAINTAINING PROJECT SITE ACCESS AND NEIGHBORHOOD ACCESS FOR EMERGENCY VEHICLES AND LOCAL RESIDENTS.
- 4. ROADWAYS DESIGNATED AS NOT COUNTY MAINTAINED ROADS AS SHOWN ON THE PLAN WILL NOT BE ELIGIBLE FOR COUNTY MAINTENANCE UNTIL THE ROADWAYS ARE IMPROVED (AT NO COST TO THE COUNTY) TO THE PUBLIC MAINTENANCE ROAD STANDARDS APPROVED BY THE BOARD OF SUPERVISORS AND IN EFFECT AT SUCH TIME THAT THE ROADWAYS ARE CONSIDERED FOR ACCEPTANCE INTO THE COUNTY'S ROAD SYSTEM.
- ALL WORK IN THE COUNTY ROAD RIGHT-OF-WAY REQUIRES AN ENCROACHMENT PERMIT FROM THE ROADS AND AIRPORTS DEPARTMENT. EACH INDIVIDUAL ACTIVITY REQUIRES A SEPARATE PERMIT - I.E. CABLE, ELECTRICAL, GAS, SEWER, WATER, RETAINING WALLS, DRIVEWAY APPROACHES, FENCES, LANDSCAPING, TREE REMOVAL, STORM DRAINAGE IMPROVEMENTS, ETC..

STREET LIGHTING

1. PACIFIC GAS & ELECTRIC ELECTROLIER SERVICE FEE SHALL BE PAID BY THE DEVELOPER AND/OR HIS AUTHORIZED REPRESENTATIVE.

SANITARY SEWER

- 1. THE SANITARY SEWER AND WATER UTILITIES SHOWN ON THESE PLANS ARE NOT PART OF THIS GRADING PERMIT AND ARE SHOWN FOR REFERENCE ONLY. 2. ALL MATERIALS AND METHODS OF CONSTRUCTION OF SANITARY SEWERS SHALL CONFORM TO
- THE SPECIFICATIONS OF THE JURISDICTION INVOLVED. INSPECTION OF SANITARY SEWER WORK SHALL BE DONE BY SAID JURISDICTION.

APPLICANT: APEX BAIT TECHNOLOGIES

PORTLAND CEMENT CONCRETE

1. CONCRETE USED FOR STRUCTURAL PURPOSES SHALL BE CLASS "A" (6 SACK PER CUBIC YARD) AS SPECIFIED IN THE STATE STANDARD SPECIFICATIONS. CONCRETE PLACED MUST DEVELOP A MINIMUM STRENGTH FACTOR OF 2800 PSI IN A SEVEN-DAY PERIOD. THE CONCRETE MIX DESIGN SHALL BE UNDER THE CONTINUAL CONTROL OF THE COUNTY INSPECTOR.

<u>AIR QUALITY, LANDSCAPING AND EROSION CONTROL</u>

1. WATER ALL ACTIVE CONSTRUCTION AREAS AT LEAST TWICE DAILY. COVER ALL TRUCKS HAULING SOIL, SAND, AND OTHER LOOSE MATERIALS OR REQUIRE ALL

- TRUCKS TO MAINTAIN AT LEAST TWO FEET OF FREEBOARD. 3. PAVE, APPLY WATER THREE TIMES DAILY, OR APPLY (NON-TOXIC) SOIL STABILIZERS ON ALL
- UNPAVED ACCESS ROADS, PARKING AREAS AND STAGING AREAS AT CONSTRUCTION SITES. 4. SWEEP DAILY (WITH WATER SWEEPERS) ALL PAVED ACCESS ROADS, PARKING AREAS AND STAGING AREAS AT CONSTRUCTION SITES. THE USE OF DRY POWDER SWEEPING IS PROHIBITED.
- 5. SWEEP STREETS DAILY (WITH WATER SWEEPERS) IF VISIBLE SOIL MATERIAL IS CARRIED ONTO ADJACENT PUBLIC STREETS. THE USE OF DRY POWDER SWEEPING IS PROHIBITED. 6. ALL CONSTRUCTION VEHICLES, EQUIPMENT AND DELIVERY TRUCKS SHALL HAVE A MAXIMUM SURVEY MONUMENT PRESERVATION IDLING TIME OF 5 MINUTES (AS REQUIRED BY THE CALIFORNIA AIRBORNE TOXIC CONTROL MEASURE TITLE 13, SECTION 2485 OF CALIFORNIA CODE OF REGULATIONS (CCR)). ENGINES SHALL BE SHUT OFF IF CONSTRUCTION REQUIRES LONGER IDLING TIME UNLESS NECESSARY
- FOR PROPER OPERATION OF THE VEHICLE. ALL VEHICLE SPEEDS ON UNPAVED ROADS SHALL BE LIMITED TO 15 MILES PER HOUR. ALL CONSTRUCTION EQUIPMENT SHALL BE MAINTAINED AND PROPERLY TUNED IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS. ALL EQUIPMENT SHALL BE CHECKED 3. BY A CERTIFIED MECHANIC AND DETERMINED TO BE RUNNING IN PROPER CONDITION PRIOR TO OPERATION.
- POST A SIGN THAT IS AT LEAST 32 SQUARE FEET MINIMUM 2 INCHES LETTER HEIGHT VISIBLE NEAR THE ENTRANCE OF CONSTRUCTION SITE THAT IDENTIFIES THE FOLLOWING REQUIREMENTS. OBTAIN ENCROACHMENT PERMIT FOR SIGN FROM ROADS DEPARTMENT OR OTHER APPLICABLE AGENCY IF REQUIRED.
- A. 15 MILES PER HOUR (MPH) SPEED LIMIT B. 5 MINUTES MAXIMUM IDLING TIME OF VEHICLES
- C. TELEPHONE NUMBER TO CONTACT THE BAY AREA AIR QUALITY MANAGEMENT DISTRICT REGARDING DUST COMPLAINTS. NOTE PHONE NUMBER OF THE BAY AREA AIR QUALITY MANAGEMENT DISTRICT AIR POLLUTION COMPLAIN HOTLINE OF 1-800-334-6367. 10. ALL FILL SLOPES SHALL BE COMPACTED AND LEFT IN A SMOOTH AND FIRM CONDITION
- CAPABLE OF WITHSTANDING WEATHERING. 11. ALL EXPOSED DISTURBED AREAS SHALL BE SEEDED WITH BROME SEED SPREAD AT THE RATE OF 5 LB. PER 1000 SQUARE FEET (OR APPROVED EQUAL). SEEDING AND WATERING SHALL BE MAINTAINED AS REQUIRED TO ENSURE GROWTH.
- 12. ALL DITCHES SHALL BE LINED PER COUNTY STANDARD SD8 13. ALL STORM DRAINAGE STRUCTURES SHALL BE INSTALLED WITH EFFECTIVE ENTRANCE & OUTFALL EROSION CONTROLS E.G. SACKED CONCRETE RIP-RAP. ENERGY DISSIPATERS SHALL BE INSTALLED AT ALL DITCH OUTFALLS. WHERE OUTFALLS ARE NOT INTO AN EXISTING CREEK OR WATER COURSE, RUNOFF SHALL BE RELEASED TO SHEET FLOW.
- 14. PRIOR TO GRADING COMPLETION AND RELEASE OF THE BOND, ALL GRADED AREAS SHALL BE RESEEDED IN CONFORMANCE WITH THE COUNTY GRADING ORDINANCE TO MINIMIZE THE VISUAL IMPACTS OF THE GRADE SLOPES AND REDUCE THE POTENTIAL FOR EROSION OF THE SUBJECT SITE
- 15. PERMANENT LANDSCAPING SHOWN ON THE ATTACHED LANDSCAPE PLAN MUST BE INSTALLED AND FIELD APPROVED BY THE COUNTY PLANNING OFFICE PRIOR TO FINAL APPROVAL BY THE COUNTY ENGINEER, AND FINAL OCCUPANCY RELEASE BY THE BUILDING INSPECTION OFFICE
- 16. THE OWNER SHALL PREPARE AND PRESENT A WINTERIZATION REPORT TO THE COUNTY INSPECTOR FOR REVIEW PRIOR TO OCTOBER 15TH OF EVERY YEAR.
- 17. THE OWNER, CONTRACTOR, AND ANY PERSON PERFORMING CONSTRUCTION ACTIVITIES SHALL INSTALL AND MAINTAIN CONSTRUCTION BEST MANAGEMENT PRACTICES (BMPS) ON THE PROJECT SITE AND WITHIN THE SANTA CLARA COUNTY ROAD RIGHT-OF-WAY THROUGHOUT THE DURATION OF THE CONSTRUCTION AND UNTIL THE ESTABLISHMENT OF PERMANENT STABILIZATION AND SEDIMENT CONTROL TO PREVENT THE DISCHARGE OF POLLUTANTS INCLUDING SEDIMENT, CONSTRUCTION MATERIALS, EXCAVATED MATERIALS, AND WASTE INTO THE SANTA CLARA COUNTY RIGHT-OF-WAY, STORM SEWER WATERWAYS, ROADWAY INFRASTRUCTURE. BMPS SHALL INCLUDE, BUT NOT BE LIMITED TO THE FOLLOWING;
- A. PREVENTION OF POLLUTANTS IN STORM WATER DISCHARGES FROM THE CONSTRUCTION SITE AND THE CONTRACTOR'S MATERIAL AND EQUIPMENT LAYDOWN / STAGING AREAS. B. PREVENTION OF TRACKING OF MUD, DIRT, AND CONSTRUCTION MATERIALS ONTO THE PUBLIC ROAD RIGHT-OF-WAY.
- C. PREVENTION OF DISCHARGE OF WATER RUN-OFF DURING DRY AND WET WEATHER CONDITIONS ONTO THE PUBLIC ROAD RIGHT-OF-WAY. 18. THE OWNER, CONTRACTOR, AND ANY PERSON PERFORMING CONSTRUCTION ACTIVITIES SHALL 1. PRIOR TO THE COMMENCEMENT OF ANY GRADING, TREE PROTECTIVE FENCING
- ENSURE THAT ALL TEMPORARY CONSTRUCTION FACILITIES, INCLUDING BUT NOT LIMITED TO CONSTRUCTION MATERIALS, DELIVERIES, HAZARDOUS AND NON-HAZARDOUS MATERIAL STORAGE, EQUIPMENT, TOOLS, PORTABLE TOILETS, CONCRETE WASHOUT, GARBAGE CONTAINERS, LAYDOWN YARDS, SECONDARY CONTAINMENT AREAS, ETC. ARE LOCATED OUTSIDE THE SANTA CLARA COUNTY ROAD RIGHT-OF-WAY.
- 19. EROSION CONTROL PLAN IS A GUIDE AND SHALL BE AMENDED AS NECESSARY TO PREVENT EROSION AND ILLICIT DISCHARGES ON A YEAR AROUND BASIS, DEPENDING ON THE SEASON, WEATHER, AND FIELD CONDITIONS. EROSION CONTROL MEASURES IN ADDITION TO THOSE NOTED IN THE PERMITTED PLANS MAY BE NECESSARY. FAILURE TO INSTALL SITE SITE AND SITUATIONALY APPROPRIATE EROSION CONTROL MEASURES MAY RESULT IN VIOLATIONS, FINES, AND A STOPPAGE OF WORK.

CLARA TREE PROTECTION MEASURES MAY BE FOUND AT http://www.sccplanning.gov." SHALL STORM DRAINAGE AND STORMWATER MANAGEMENT

- 2. PRIOR TO COMMENCEMENT OF ANY CONSTRUCTION ACTIVITY, TREE PROTECTIVE FENCING SHALL 1. DEVELOPER IS RESPONSIBLE FOR ALL NECESSARY DRAINAGE FACILITIES WHETHER SHOWN ON THE PLANS OR NOT AND HE OR HIS SUCCESSOR PROPERTY OWNERS ARE RESPONSIBLE FOR COUNTY OF SANTA CLARA DEPT. OF ROADS AND AIRP THE ADEQUACY AND CONTINUED MAINTENANCE OF THESE FACILITIES IN A MANNER WHICH WILL PRECLUDE ANY HAZARD TO LIFE, HEALTH, OR DAMAGE TO ADJOINING PROPERTY, CONSISTENT WITH NPDES PERMIT CAS612008 / ORDER NO. R2-2009-0047 AND NPDES PERMIT CAS000004/ ORDER NO. 2013-0001-DWQ.
 - 2. DROP INLETS SHALL BE COUNTY STANDARD TYPE 5 UNLESS OTHERWISE NOTED ON THE PLANS. THE DEVELOPER'S ENGINEER SHALL BE RESPONSIBLE FOR THE PROPER LOCATION OF DROP INLETS. WHERE STREET PROFILE GRADE EXCEEDS 6% DROP INLETS SHALL BE SET AT 500 ANGLE CURB LINE TO ACCEPT WATER OR AS SHOWN ON THE PLANS.
 - 3. WHERE CULVERTS ARE INSTALLED THE DEVELOPER SHALL BE RESPONSIBLE FOR GRADING TH OUTLET DITCH TO DRAIN TO AN EXISTING SWALE OR TO AN OPEN AREA FOR SHEET FLOW. 4. UPON INSTALLATION OF DRIVEWAY CONNECTIONS, PROPERTY OWNERS SHALL PROVIDE FOR
 - THE UNINTERRUPTED FLOW OF WATER IN ROADSIDE DITCHES. 5. THE COUNTY SHALL INSPECT UNDERGROUND DRAINAGE IMPROVEMENTS AND STORMWATER MANAGEMENT FEATURES PRIOR TO BACKFILL.

AS-BUILT PLANS STATEMENT

THIS IS A TRUE COPY OF THE AS-BUILT PLANS. THERE (____ WERE) (____ WERE NOT) MINOR FIELD CHANGES – MARKED WITH THE SYMBOL (^). THERE (___WERE) (___ WERE NOT) PLAN REVISIONS INDICATING SIGNIFICANT CHANGES REVIEWED BY THE COUNTY ENGINEER AND MARKED WITH THE SYMBOL \triangle .


SIGNATURE _____

NOTE: THIS STATEMENT IS TO BE SIGNED BY THE PERSON AUTHORIZED BY THE COUNTY ENGINEER TO PFRFORM THE INSPECTION WORK. A REPRODUCIBLE COPYOF THE AS-BUILT PLANS MUST BE FURNISHED TO THE COUNTY ENGINEER AFTERCONSTRUCTION.


GEOTECHNICAL ENGINEER OBSERVATION

1. A CONSTRUCTION OBSERVATION LETTER FROM THE RESPONSIBLE GEOTECHNICAL ENGINEER AND ENGINEERING GEOLOGIST DETAILING CONSTRUCTION OBSERVATIONS AND CERTIFYING THAT THE WORK WAS DONE IN ACCORDANCE WITH THE RECOMMENDATIONS IN THE GEOTECHNICAL AND GEOLOGIC REPORTS SHALL BE SUBMITTED PRIOR TO THE GRADING COMPLETION AND RELEASE OF THE BOND.





- THE LANDOWNER/CONTRACTOR MUST PROTECT AND ENSURE THE PERPETUATION OF SURVEY MONUMENTS AFFECTED BY CONSTRUCTION ACTIVITIES. 2. PRIOR TO THE START OF CONSTRUCTION, THE CONTRACTOR SHALL LOCATE, STAKE, AND FLAG ALL
- PERMANENT SURVEY MONUMENTS OF RECORD AND ANY UNRECORDED MONUMENTS THAT ARE DISCOVERED THAT ARE WITHIN 50 FEET OF THE CONSTRUCTION ACTIVITY. THE LANDOWNER. CONTRACTOR AND/OR ANY PERSON PERFORMING CONSTRUCTION ACTIVITIES THAT WILL OR MAY DISTURB AN EXISTING MONUMENT, CORNER STAKE, OR ANY OTHER PERMANENT SURVEYED MONUMENT SHALL CAUSE TO HAVE A LICENSED LAND SURVEYOR OR CIVIL ENGINEER, AUTHORIZED TO PRACTICE SURVEYING, ENSURE THAT A CORNER RECORD AND/OR RECORD OF SURVEY ARE FILED WITH THE COUNTY SURVEYOR'S OFFICE PRIOR TO DISTURBING SAID MONUMENTS AND RESET PERMANENT MONUMENT(S) TO PERPETUATE THE LOCATION IF ANY PERMANENT MONUMENT COULD BE DESTROYED. DAMAGED, COVERED, DISTURBED, OR OTHERWISE OBLITERATED. THE LICENSED LAND SURVEYOR OR CIVIL ENGINEER SHALL FILE A CORNER RECORD OR RECORD OF SURVEY WITH COUNTY SURVEYOR PRIOR TO



EXISTING TREE PROTECTION DETAILS

- SHALL BE IN PLACE IN ACCORDANCE WITH THE TREE PRESERVATION PLAN AND INSPECTED BY A CERTIFIED ARBORIST. THE ARBORIST SHALL MONITOR CONSTRUCTION ACTIVITY TO ENSURE THAT THE TREE PROTECTION MEASURES ARE IMPLEMENTED AND ADHERED TO DURING CONSTRUCTION. THIS CONDITION SHALL BE INCORPORATED INTO THE GRADING PLANS.
- 2. FENCE SHALL BE MINIMUM 5 FEET TALL CONSTRUCTED OF STURDY MATERIAL (CHAIN-LINK OR EQUIVALENT STRENGTH / DURABILITY).
- FENCE SHALL BE SUPPORTED BY VERTICAL POSTS DRIVEN 2 FEET (MIN) INTO THE GROUND AND SPACED NOT MORE THAN 10 FEET APART.
- TREE FENCING SHALL BE MAINTAINED THROUGHOUT THE SITE DURING THE CONSTRUCTION PERIOD, INSPECTED PERIODICALLY FOR DAMAGE AND PROPER FUNCTION, REPAIRED AS NECESSARY TO PROVIDE A PHYSICAL BARRIER FROM CONSTRUCTION ACTIVITIES, AND REMAIN IN PLACE UNTIL THE FINAL INSPECTION.
- 5. A SIGN THAT INCLUDES THE WORDS, "WARNING: THIS FENCE SHALL NOT BE REMOVED WITHOUT THE EXPRESSED PERMISSION OF THE SANTA CLARA COUNTY PLANNING OFFICE," SHALL BE SECURELY ATTACHED TO THE FENCE IN A VISUALLY PROMINENT LOCATION.

ISSUED BY: _____ DATE: _

ENCROACHMENT PERMIT NO.

NO WORK SHALL BE DONE IN THE COUNTY'S RIGHT-OF-W WITHOUT AN ENCROACHMENT PERMIT, INCLUDING THE STAGING OF CONSTRUCTION MATERIAL AND THE PLACEMENT OF PORTABLE TOILETS.

ENGINEER'S STATEMENT

I HEARBY STATE THAT THESE PLANS ARE IN COMPLIANCE WITH ADOPTED COUNTY STANDARDS, THE APPROVED TENTATIVE MAR (OR PLAN) PROFESSIONA AND CONDITIONS OF APPROVAL PERTAINING THERETO DATED FILE(S) NO. ON MUSI 52 69278 DATE R.C.E. NO.

COUNTY ENGINEER'S NOTE

ISSUANCE OF A PERMIT AUTHORIZING CONSTRUCTION DOES NOT RELEASE THE DEVELOPER, PERMITTEE OF ENGINEER FROM RESPONSIBILITY FOR THE CORRECTION OF ERRORS OR OMISSIONS CONTAINED IN THE PLANS. IF, DURING THE COURSE OF CONSTRUCTION, THE PUBLIC INTEREST REQUIRES A MODIFICATION OF (OR DEPARTURE FROM) THE SPECIFICATIONS OF THE PLANS. THE COUNTY SHALL HAVE THE AUTHORITY TO REQUIRE THE SUSPENSION OF WORK, AND THE NECESSARY MODIFICATION OR DEPARTURE AND TO SPECIFY THE MANNER IN WHICH THE SAME IS TO BE MADE.

DATE _____

FINAL ACCEPTANCE OF THE PROJECT BY THE LAND DEVELOPMENT ENGINEERING INSPECTOR.

PORTS	COUNTY OF SANTA CLARA LAND DEVELOPMENT ENGINEERING & SURVEYING
	GRADING/DRAINAGE PERMIT NO

PRELIMINARY PLANS NOT FOR CONSTRUCTION



	-	
	PROJECT	
	Je PROJECT	s Avenue
Burnett Aven	SITE	
		tote High
Average Honnes	Avenue	Store Highway 101
titton Avenue Mantal Pacebles	wey	
THE NOT	cone Portsway	rone Boad
		VICINITY MAP

🔽 🛛 NO SCALE

SCOPE OF WORK

- 1. THE DEVELOPER IS RESPONSIBLE FOR THE INSTALLATION OF THE WORK PROPOSED ON THE EROSION CONTROL PLAN. THE ENGINEER OF RECORD IS RESPONSIBLE FOR THE DESIGN OF THE EROSION CONTROL PLANS AND ANY MODIFICATIONS OF THE EROSION CONTROL PLANS TO PREVENT ILLICIT DISCHARGES FROM THE SITE DURING CONSTRUCTION.
- 2. A CONSTRUCTION OBSERVATION LETTER FROM THE RESPONSIBLE GEOTECHNICAL ENGINEER AND CERTIFIED ENGINEERING GEOLOGIST DETAILING CONSTRUCTION OBSERVATIONS AND CERTIFYING THAT THE WORK WAS DONE IN ACCORDANCE WITH THE RECOMMENDATIONS IN THE GEOTECHNICAL AND GEOLOGICAL REPORTS SHALL BE SUBMITTED PRIOR TO GRADING COMPLETION AND RELEASE OF BOND.
- CLEAR AND GRUB BUILDING PAD AND DRIVEWAY.
- BUILDING PAD AND DRIVEWAY GRADING.
- CONSTRUCT DRIVEWAY
- CONSTRUCT BIORETENTION PONDS NO TREES TO BE REMOVED; EXISTING TREES TO BE PROTECTED
- SEPARATE PERMIT REQUIRED WORK:
- CONSTRUCT DRIVEWAY APPROACH
- 2. FURNISH & INSTALL SEPTIC SYSTEM
- 3. FURNISH & INSTALL WATER AND FIRE PROTECTION SYSTEM



- COVER SHEET
- SITE PLAN
- PRELIMINARY GRADING & DRAINAGE PLAN 3 - 4
- 5 NOTES, DETAILS & SECTIONS EROSION CONTROL PLAN
- BMP1&2 BEST MANAGEMENT PRACTICES

ENGINEER'S NAME: HANNA & BRUNETTI

ADDRESS: 7651 EIGLEBERRY STREET, GILROY CA 95020

PHONE NO. <u>408</u>842-2173

FAX NO. 408 842-3662

PRELIMINARY GRADING & DRAINAGE PLAN

FOR THE DEVELOPMENT OF THE LANDS FOR APEX BAIT TECHNOLOGIES, INC. **BURNETT & VISTA DE LOMAS AVENUE**

A PARCEL OF LAND BEING A PART OF THE ORIGINAL J.M. TONEY TRACT FORMERLY OWNED BY JAMES A. CLAYTON & COMPANY IN THE RANCHO LA LAGUNA SECA

SANTA CLARA COUNTY, CALIFORNIA A.P.N.: 728-38-001


NO SCALE

Sheet


of

8

	JUNE 2022			NO S
DARRELL K.H. WONG	Revision 1	Date	APN TOO TOO TOO	She
R.C.E. NO. 63958	Revision 2	Date	728-38-001 Co. File	of
R.C.E. NO. 03938	Revision 3	Date	PLN21-222	
22			JOB NO. 200	58




PROFESSION	REFERENCES	
date:22 Hanna — Brunetti		
Amanda Joy Musy−Verdel		Lands of Apex Bait Te



EGMENT OF A SHARED TRAIL ROUTE FROM THE COUNTYWIDE TRAILS PLAN IN JUAN BAUTISTA DE ANZA NATIONAL HISTORIC TRAIL AND COYOTE CREEK/LL GIONAL TRAIL, LOCATED ALONG BURNETT AVENUE ON THE NORTHERN BORDE AS WELL AS AN ADJACENT PARCEL OWNED BY SANTA CLARA VALLEY WATEF IE SOUTH-WEST BOUNDARY OF THE PROJECT SITE. THE WILLOW SPRINGS BI AIL IS PROPOSED ALONG BURNETT AVENUE WITHIN THE ROAD RIGHT-OF-WA	AGAS IR OF THE R IKEWAY	P
date:22 Hanna - Brunetti Amanda Joy Musy-Verdel	REFERENCES	Preliminary Lands of Apex Bait Technologies

		/					_
ROAD:	BURNETT	&	VISTA	DE	LOMAS	AVENU	E




		BITED. IONS.	PR	OJECT NOTES:			
		T, IS PROHIBITED. RESTRICTIONS.	1.	STATING THAT HE/SHE HAS LOCATED THE BUI	A LETTER S	ONS ARE TO BE ESTABLISHED BY A PERSON IGNED AND SEALED BY THAT AUTHORIZED PERSON, ERS, AND THEIR LOCATIONS CONFORM TO COUNTY ILDING PLANS IS REQUIRED TO BE SUBMITTED TO THE	
		OR PAR THESE	2.	'THIS PLAN AUTHORIZES THE REMOVAL OF ON MEASURED 4.5 FEET ABOVE GROUND WHICH A	RE SHOWN 1 IS APPROVED	REES WITH TRUNK DIAMETERS GREATER THAN 12 INCHES TO BE REMOVED. ANY OTHER SUCH TREES ARE NOT O OR A SEPARATE TREE REMOVAL PERMIT IS OBTAINED ESPONSIBILITY TO ENSURE THAT REMOVAL OF	THE OVE THA THE CON
		METHOD, IN WHOLE ACCEPTANCE OF	3. 4. 5.	SLOPES AND REDUCE THE POTENTIAL FOR ERG	RDINANCE TO OSION ON TH	MINIMIZE THE VISUAL IMPACTS OF THE GRADED	DET. EXC COU
		ANY THE	6.	THE PROPOSED SEPTIC DESIGN WILL ACTUALLY REQUIRED SETBACKS. IF ARCHAEOLOGICAL RESOURCES OR HUMAN R	Y FIT INTO TI REMAINS ARE	HE PROPOSED LEACHFIELD AREA, AND CONFORM TO ALL DISCOVERED DURING CONSTRUCTION, WORK SHALL BE	
		ATION BY NCE OF	7.	HALTED WITHIN 50 METERS (150 FEET) OF THI ARCHAEOLOGIST. IF THE FIND IS DETERMINED FORMULATED AND IMPLEMENTED. NOTIFY SOILS ENGINEER TWO (2) DAYS PRIOR	TO BE SIGN	IFICANT, APPROPIATE MITIGATION MEASURES SHALL BE	
		R PUBLICATION E EVIDENCE C	8.	COORDINATE THE WORK IN THE FIELD. ALL MATERIALS FOR FILL SHOULD BE APPROVI TO THE SITE.			
		REPRODUCTION OR	9.	IN THE EVENT THAT ARCHEOLOGICAL FEATURE THE GRADING, SCRAPING OR EXCAVATION, ALL THE FIND AND AN ARCHAEOLOGIST SHOULD BI DISCOVERED MATERIAL TO ASSESS ITS AREAL IF THE DISCOVERED MATERIAL IS DEEMED POT SHOULD MONITOR ANY SUBSEQUENT ACTIVITY	WORK SHOU E CONTACTED EXTENT, CO ENTIALLY SIG	JLD BE HALTED IN THE VICINITY OF D IMMEDIATELY TO EVALUATE THE DNDITION, AND SCIENTIFIC SIGNIFICANCE. SNIFICANT, A QUALIFIED ARCHAEOLOGIST	
		L CONSTITUTE	10.	IN THE EVENT THAT HUMAN SKELETAL REMAIN ORDINANCE NO. B6–18 TO IMMEDIATELY NOTIF CORONER THAT THE REMAINS ARE NATIVE AM AMERICAN HERITAGE COMMISSION, PURSUANT CODE AND THE COUNTY COORDINATOR OF IN MADE EXCEPT AS AUTHORIZED BY THE COUNT	IS ARE ENCO Y THE COUN ERICAN, THE TO SUBDIVISI DIAN AFFAIR TY CHAPTER.	DUNTERED, THE APPLICANT IS REQUIRED BY COUNTY ITY CORONER. UPON DETERMINATION BY THE COUNTY CORONER SHALL CONTACT THE CALIFORNIA NATIVE ON (c) OF SECTION 7050.5 OF THE HEALTH AND SAFET S. NO FURTHER DISTURBANCE OF THE SITE MAY BE IF ARTIFACTS ARE FOUND ON THE SITE A QUALIFIED	Y
		AL	11.	OF THE ARTIFACTS MAY BE MADE EXCEPT AS THESE PLANS ARE FOR THE WORK DESCRIBED WILL BE REQUIRED FOR THE SEPTIC LINE CONS	AUTHORIZED		
		SLY LIMIT ATIONS	12.	UPPER 6" OF THE SUBGRADE SOIL SHALL BE A MINIMUM RELATIVE COMPACTION OF 95%.	SCARIFIED, M		
		IF IS EXPRESSLY LIMITED	13.	ALL AGGREGATE BASE MATERIAL SHALL BE CO ROADWAYS DESIGNATED AS NOT COUNTY MAIN ELIGIBLE FOR COUNTY MAINTENANCE UNTIL TH COUNTY) TO PUBLIC MAINTENANCE ROAD STAN AND IN EFFECT AT SUCH TIME THAT THE ROA COUNTY'S ROAD SYSTEM.	ITAINED ROA E ROADWAYS NDARDS APP	DS AS SHOWN ON THIS PLAN WILL NOT BE S ARE IMPROVED (AT NO COST TO THE ROVED BY THE BOARD OF SUPERVISORS	
		N THEREOF ANS AND		AN APPROVED RESIDENTIAL FIRE SPRINKLER S CFMO—SP6 IS REQUIRED TO BE INSTALLED TH	ROUGHOUT T	HE STRUCTURE.	
		ATION E PL		ALL NEW ON-SITE UTILITIES, MAINS AND SERV TO SERVE THE PROPOSED RESIDENCE. A CONSTRUCTION OBSERVATION LETTER FROM	THE RESPON	ISIBLE GEOTECHNICAL ENGINEER AND CERTIFIED	
		AND PUBLICA	10	ACCORDANCE WITH THE RECOMMENDATIONS IN PRIOR TO GRADING COMPLETION AND RELEAS	N THE GEOTI SE OF BOND.	VATIONS AND CERTIFYING THAT THE WORK WAS DONE IN ECHNICAL AND GEOLOGICAL REPORTS SHALL BE SUBMITT OR NATURAL AREAS AWAY FROM BUILDING FOUNDATIONS.	ED
		CONTACT V		TO ALLOW FOR STORM WATER INFILTRATION IN			
		THEY WERE PRE VISUAL CON	CON COU REC SH/ ALL	NTRACTOR AGREES THAT HE SHALL ASSUME SOL JRSE OF CONSTRUCTION OF THIS PROJECT, INCL QUIREMENT SHALL APPLY CONTINUOUSLY AND NO ALL DEFEND, INDEMNIFY AND HOLD THE OWNER A	UDING SAFET OT BE LIMITE AND THE EN	PLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING IY OF ALL PERSONS AND PROPERTY; THAT THIS D TO NORMAL WORKING HOURS; AND THAT THE CONTRA GINEER HARMLESS FROM ANY AND ALL LIABILITY, REAL ON N THIS PROJECT, EXCEPTING FOR LIABILITY ARISING FROM	.CTOR DR
		D TO THE ORIGINAL SITE FOR WHICH TENGINEER WITHOUT PREJUDICE.	THE OTH CON	<u>)TE:</u> CONTRACTOR SHALL BE RESPONSIBLE FOR THE HER SURVEY MARKERS DURING CONSTRUCTION. A INSTRUCTION SHALL BE REPLACED AT THE CONTR ERE THE FIRM OF HANNA & BRUNETTI DOES NO	ALL SUCH MO RACTOR'S EX	DNUMENTS OR MARKER'S DESTROYED DURING PENSE.	
		IAL SITE HOUT F	ASS	SUME NO RESPONSIBILITY WHATSOEVER FOR IMPR			
		E ORIGIN EER WIT	FOL	NTRACTOR TO VERIFY PRIOR TO CONSTRUCTION OF INDIATION TO DETERMINE BUILDING PAD ELEVATION	DN.		
		d to th Engine		E SOILS REPORT AND/OR STRUCTURAL F THE BUILDING FINISH FLOOR AND PAD.	PLANS TU	DETERMINE THE ELEVATION	
		E RESTRICTED NS IN THE E					
		SHALL BE RI S REMAINS					
		ONS SHA					
	1	SPECIFICATIONS (
	OF	PLANS AND SPE ANS AND SPE					
AN #		DF THESE THE PL	DATE	REVISIONS: DESCRIPTION	BY:	HANNA-BRUNETTI EST. 1910 CIVIL ENGINEERS • LAND SURVEYORS CONSTRUCTION MANAGERS	DATE: JUNE 2022 HORIZ. SCALE: $ ''=30'''$ VERT. SCALE: $ ''= 0''''= 0''''= 0''''= 0''''= 0''''= 0'''''= 0''''= 0''''''''$
PLA	SHEE ⁻	HE USE (TLE TO				7651 EIGLEBERRY STREET • GILROY • 95020 • CALIFORNIA OFFICE (408) 842-2173 • FAX (408) 842-3662 EMAIL: ENGINEERING @ HANNABRUNETTI.COM	DESIGNED BY: <u>AM</u> CHECKED BY: <u></u> DRAWN BY: <u></u> T.M.

APPLICANT: APEX BAIT TECHNOLOGIES, INC

ESE QUANTITIES DO NOT INCLUDE ANY SHRINKAGE, SUBSIDENCE, ER-EXCAVATION, OR ANY SPECIAL CONDITIONS OR REQUIREMENTS AT MAY BE SPECIFIED IN THE GEOTECHNICAL INVESTIGATION REPORT. ESE QUANTITIES IN THE AREA FOR PERMIT PURPOSES ONLY. ALL NTRACTORS BIDDING ON THIS PROJECT SHOULD MAKE THEIR OWN TERMINATION OF EARTHWORK QUANTITIES PRIOR TO SUBMITTING A BID. CESS MATERIAL SHALL BE OFF-HAULED. IF LOCATION IS WITHIN THE DUNTY A SEPERATED PERMIT SHALL BE REQUIRED.

380		PROPOSED RESEARCH FF 371.3 PAD 370.3	60' DRIVEWAY AND PARKING STALLS	380
370	EXISTING GROUND			
360		SCALE: HORIZONTAL 1"=30' VERTICAL 1"=10'		360


-380					380
	PROPOSED RESEARCH	FUTURE RESEARCH FF-371.3 PAD 370.3 PAD 370.3	PROPOSED WAREHOUSE	PROPOSED WAREHOUSE FF-371.3 PAD 370.3	
	5% MIN GRADE AWAY FROM BUILDING FOUNDATION; TYPICAL	EXISTING GROUND			<u>3</u> 70
360		SCALE: HORIZONTAL 1"=30' VERTICAL 1"=10'			360




	REFERENCES	PROFESSION	
Notes,		AL JOY MUST EN	date:22 Hanna — Brunetti
		ERDE 1 NEE	
Lands of Apex Bait Technologies			Amanda Joy Musy–Verdel
UNINCORPORATED JUNE 2022		OF CALIFORNIA	R.C.E. # 69278
		CTA DE LONARS AV	ULDNETT & VIC

ROAD: BURNETT & VISTA DE LOMAS AVENUE

COUNTY FILE NO .: PLN21-222








APPLICANT: APEX BAIT TECHNOLOGIES, INC


ROL	
<u>DF SILTS.</u>	
ERIMETER	

D: BURNETT & VISTA DE LOMA	AS AVENUE	COUNTY FILE NO .: PLN
R.C.E. # 69278		UNINCORPORATED JUNE 2022
Amanda Joy Musy-Verdel		Lands of Apex Bait Technologies
date:22 Hanna – BrunettiS S F F Z		Ero:
PROFESSION	REFERENCES	









STANDARD BEST MANAGEMENT PRACTICE NOTES

- 1. Solid and Demolition Waste Management: Provide designated waste collection areas and containers on site away from streets, gutters, storm drains, and waterways, and arrange for regular disposal. Waste containers must be watertight and covered at all times except when waste is deposited. Refer to Erosion & Sediment Control Field Manual, 4th Edition (page C3) or latest.
- 2. <u>Hazardous Waste Management</u>: Provide proper handling and disposal of hazardous wastes by a licensed hazardous waste material hauler. Hazardous wastes shall be stored and properly labeled in sealed containers constructed of suitable materials. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-5 to C-6) or latest.
- 3. <u>Spill Prevention and Control</u>: Provide proper storage areas for liquid and solid materials, including chemicals and hazardous substances, away from streets, gutters, storm drains, and waterways. Spill control materials must be kept on site where readily accessible. Spills must be cleaned up immediately and contaminated soil disposed properly. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-7 to C-8, C-13 to C-14) or latest.
- 4. <u>Vehicle and Construction Equipment Service and Storage</u>: An area shall be designated for the maintenance, where onsite maintenance is required, and storage of equipment that is protected from stormwater run-on and runoff. Measures shall be provided to capture any waste oils, lubricants, or other potential pollutants and these wastes shall be properly disposed of off site. Fueling and major maintenance/repair, and washing shall be conducted off-site whenever feasible. Refer to Erosion & Sediment Control Field Manual, 4th Edition (page C9) or latest.
- 5. <u>Material Delivery, Handling and Storage</u>: In general, materials should not be stockpiled on site. Where temporary stockpiles are necessary and approved by the County, they shall be covered with secured plastic sheeting or tarp and located in designated areas near construction entrances and away from drainage paths and waterways. Barriers shall be provided around storage areas where materials are potentially in contact with runoff. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-11 to C-12) or latest.
- 6. Handling and Disposal of Concrete and Cement: When concrete trucks and equipment are washed on-site, concrete wastewater shall be contained in designated containers or in a temporary lined and watertight pit where wasted concrete can harden for later removal. If possible have concrete contractor remove concrete wash water from site. In no case shall fresh concrete be washed into the road right-of-way. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-15 to C-16) or latest.
- . <u>Pavement Construction Management</u>: Prevent or reduce the discharge of pollutants from paving operations, using measures to prevent run-on and runoff pollution and properly disposing of wastes. Avoid paving in the wet season and reschedule paving when rain is in the forecast. Residue from saw-cutting shall be vacuumed for proper disposal. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-17 to C-18) or latest.
- 5. Contaminated Soil and Water Management: Inspections to identify contaminated soils should occur prior to construction and at regular intervals during construction. Remediating contaminated soil should occur promptly after identification and be specific to the contaminant identified, which may include hazardous waste removal. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-19 to C-20) or latest.
- 2. <u>Sanitary/Septic Water Management</u>: Temporary sanitary facilities should be located away from drainage paths, waterways, and traffic areas. Only licensed sanitary and septic waste haulers should be used. Secondary containment should be provided for all sanitary facilities. Refer to Erosion & Sediment Control Field Manual, 4th Edition (page C-21) or latest.
- 10. Inspection & Maintenance: Areas of material and equipment storage sites and temporary sanitary facilities must be inspected weekly. Problem areas shall be identified and appropriate additional and/or alternative control measures implemented immediately, within 24 hours of the problem being identified.

Best Management Practices and Erosion Control Details Sheet 1 County of Santa Clara

STANDARD EROSION CONTROL NOTES

1. Sediment Control Management:

Tracking Prevention & Clean Up: Activities shall be organized and measures taken as needed to prevent or minimize tracking of soil onto the public street system. A gravel or proprietary device construction entrance/exit is required for all sites. Clean up of tracked material shall be provided by means of a street sweeper prior to an approaching rain event, or at least once at the end of each workday that material is tracked, or, more frequently as determined by the County Inspector. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages B-31 to B-33) or latest.

Storm Drain Inlet and Catch Basin Inlet Protection: All inlets within the vicinity of the project and within the project limits shall be protected with gravel bags placed around inlets or other inlet protection. At locations where exposed soils are present, staked fiber roles or staked silt fences can be used. Inlet filters are not allowed due to clogging and subsequent flooding. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages B-49 to B-51) or latest.

Storm Water Runoff: No storm water runoff shall be allowed to drain in to the existing and/or proposed underground storm drain system or other above ground watercourses until appropriate erosion control measures are fully installed.

<u>Dust Control</u>: The contractor shall provide dust control in graded areas as required by providing wet suppression or chemical stabilization of exposed soils, providing for rapid clean up of sediments deposited on paved roads, furnishing construction road entrances and vehicle wash down areas, and limiting the amount of areas disturbed by clearing and earth moving operations by scheduling these activities in phases.


Stockpiling: Excavated soils shall not be placed in streets or on paved areas. Borrow and temporary stockpiles shall be protected with appropriate erosion control measures(tarps, straw bales, silt fences, ect.) to ensure silt does not leave the site or enter the storm drain system or neighboring watercourse.


- 2. Erosion Control: During the rainy season, all disturbed areas must include an effective combination of erosion and sediment control. It is required that temporary erosion control measures are applied to all disturbed soil areas prior to a rain event. During the non-rainy season, erosion control measures must be applied sufficient to control wind erosion at the site.
- 3. Inspection & Maintenance: Disturbed areas of the Project's site, locations where vehicles enter or exit the site, and all erosion and sediment controls that are identified as part of the Erosion Control Plans must be inspected by the Contractor before, during, and after storm events, and at least weekly during seasonal wet periods. Problem areas shall be identified and appropriate additional and/ or alternative control measures implemented immediately, within 24 hours of the problem being identified.
- 4. <u>Project Completion</u>: Prior to project completion and signoff by the County Inspector, all disturbed areas shall be reseeded, planted, or landscaped to minimize the potential for erosion on the subject site.
- 5. It shall be the Owner's/Contractor's responsibility to maintain control of the entire construction operation and to keep the entire site in compliance with the erosion control plan.
- 6. Erosion and sediment control best management practices shall be operable year round or until vegetation is fully established on landscaped surfaces.


GRADING & DRAINAGE PLAN	FOR THE	DEVELOPMENT OF THE LANDS	FOR APEX BAIT TECHNOLOGIES, INC.	BURNETT & VISTA DE LOMAS AVENUE	A PARCEL OF LAND BEING A PART OF THE ORIGINAL J.M. TONEY TRACT FORMERLY OWNED BY JAMES A. CLAYTON & COMPANY IN THE RANCHO LA LAGUNA SECA	SANTA CLARA COUNTY, CALIFORNIA	A.P.N.: 728-38-001
t Tw	r i uject muumation						


BMP-1





















 \mathbf{A}











11 11
11 11
-1111













PLAN #

Y QTY	SIZE	WATER RATING	BOTANICAL NAME	COMMON NAME	MATURE SIZE
REEN TR	REES				
2 40 51 4) 5) 5	low High	Cedrus deodara Sequoia sempervirens	Deodar Cedar Coast Redwood	fast to 80' tall 50' to 100' tall
REEN SH	IRUBS				
2115) 1	LOW	Elaeagnus pungens Fruitlandii	Silverberry	10-15' ta ll
č 109 (1	LOW	Xylosma congestum	Xylosma	8-10' tall
20	1	LOW	Callistemon citrinus	Lemon Bottlebrush	n10-15' tall






Job No.: 21031 | APN: 728-38-001 | **1** of 2

PROJECT DESCRIPTION

A conventional pump up treatment system utilizing Quick4 Plus High-Capacity Infiltrator Chambers is proposed to serve a 4000 square foot research facility and potential future expansion of an additional 4000 square foot second facility. There will be a maximum of 10 employees on site. The research buildings intent is to study agricultural pests and pest control. Proposed research building will be located on Vista De Lomas Ave at Burnett Ave, Morgan Hill, CA.

CONSTRAINTS & DESIGN CRITERIA

- The proposed system is designed to serve the two research buildings and agricultural employees with a design wastewater flow of 150 gallons per day (gpd) plus an additional 150 gallons per day (gpd) for future expansion per County DEH guidelines.
- Soil profiles did not exhibit any evidence of seasonally high groundwater conditions. Based on two soil profiles observed in the proposed dispersal area, seasonally high groundwater is estimated to occur at greater than 14' below grade.
- No wells, springs or watercourses are situated within 100' of the proposed Onsite Wastewater Treatment System (OWTS).



312.5 SF ÷ 4 SF/LF = 78.13 LF OF TRENCH REQUIRED

- 80 LF = 20 INFILTRATOR CHAMBERS 80 LF (20 CHAMBERS PRIMARY) + 80 LF (20 CHAMBERS SECONDARY)
- TOTAL: 160 LF / 40 QUICK4 PLUS HIGH-CAPACITY INFILTRATOR CHAMBERS

PRIMARY AND SECONDARY DRAINFIELDS, EACH CONSISTING OF ONE 3 FT-WIDE, 80 FT-LONG TRENCH COMPOSED OF 20 QUICK4 PLUS HIGH-CAPACITY INFILTRATOR CHAMBERS EACH TRENCH SHALL HAVE A TOTAL DEPTH OF 2.5 FEET (SEE DETAIL) TRENCHES SHALL BE SPACED 6 FT ON CENTER

SPECIFICATIONS


- 1. Building Sewer Lines, & Proposed Processing Tank
- 1.1. A 4" ABS building sewer line shall be installed to convey all raw sewage from dwelling to the septic tank. All gravity sewer piping must maintain a minimum 2% continuous gradient. All wastewater including graywater shall be discharged to the septic tank.
- 1.2. Locate a 2-way, 4" ABS cleanout fitting on the building sewer to facilitate snaking and line location. 1.3. The septic tank shall be a 1,500 gallon, septic tank manufactured by Roth Global Plastics. The tank shall have 24"
- diameter OSI access risers with fiberglass, bolt-down lids (brown). The tank shall be installed according to the manufacturer's guidelines including anti-flotation specifications.
- 1.4. The tank hole shall be excavated so that the tank sits level. Install the access risers with a watertight joint using the adhesives supplied by manufacturer. Access riser lids shall be brown unless otherwise requested.
- 1.5. Install the tank inlet fitting with a watertight joint. Cap off or use a test plug on this fitting and fill the tank with clean water 2" above the joint between the riser and the tank top. Repair any leaks.
- 1.6. Obtain a watertight tank inspection by DEH with 24 hours notice.
- 1.7. Install an OSI Effluent Filter (Model: FTS0444-36V) at tank outlet.
- Discharge Pump Tank and Filtrate Pumping
- 2.1. A 1,000 gallon Roth pump tank shall be installed adjacent to the septic tank.
- 2.2. The pump tank shall be installed according to the manufacturer's instructions including anti-floatation specifications and be made watertight.
- 2.3. Install the pump and float tree according to the instructions provided by manufacturer/dealer. 2.4. A 1/2 hp OSI high head effluent pump (PF1005) is specified for pressurized dispersal discharge.
- 2.5. The filtrate *transport pipe to dispersal system shall be 1.0"* schedule 40 PVC.
- 3. Effluent Distribution and Dispersal Trenches
- 3.1. A bull run valve shall be installed to divert effluent flow between the two proposed drainfields as shown on the plan. 3.2. 4" ABS or SCH 40 PVC tightline shall be used to make gravity flow connections between the septic tank and the drainfield trenches. All gravity lines shall maintain a continuous 2% min. gradient.
- 3.3. Primary and secondary drainfields shall each consist of a total of 20 Quick4 Plus High-Capacity Infiltrator
- Chambers. 3.4. Trenches shall be spaced 6' on center and shall be installed with a total depth of 2.5 feet.


3.5. Installer shall assure that surface drainage is directed away from the proposed septic tank and dispersal trenches. 4. Piping Schedule


- 4.1. All piping shall be installed to conform to requirements in the current California Plumbing Code.
- 4.2. The house sewer pipe to the septic tank shall be constructed of 4" ABS and shall include a 2-way clean out
- fitting near dwelling as shown on the plan.
- Installer Qualifications and Responsibilities
- 5.1. The system installer shall be licensed by the State of California, Department of Consumer Affairs, to install septic
- 5.2. All piping shall conform to the current edition of the California Plumbing Code.
- 5.3. The installer shall be responsible for locating any property lines, underground utilities or piping. Any damage to these facilities shall be the responsibility of the installer.
- 5.4. For tree setback requirements, refer to the Santa Clara County Ordinance C-16 Tree Preservation and Revision. 5.5. The appropriate Environmental Health Office or Specialist must be notified by the installation contractor at least 48hours prior to starting construction and for each required inspection: Main Office (1555 Berger Drive, Suite 300, San Jose) 408-918-3400 or South County Office (80 Highland Ave, San Martin) 408-918-3400 . Site Clean up and Erosion Control Measures
- 6.1. All excavated areas shall be smoothed and all construction debris shall be removed from the site.
- 6.2. All disturbed soils shall be seeded and mulched. Erosion Control Mix seed shall be used at the coverage recommended on the package for all disturbed soil.
- 6.3. Straw shall be used to cover all disturbed soil.
- 6.4. PER DIVISION C12, CHAPTER III OF THE COUNTY CODE (Sec. C12-513. Temporary erosion control.) "The permittee and any person(s) doing, causing or directing the grading shall install and maintain all precautionary measures necessary to protect adjacent watercourses and public or private property from damage by erosion, flooding, or deposition of mud or debris originating from the site. Precautionary measures must include provisions of properly designed erosion prevention and sediment control measures, so that downstream properties are not affected by upstream erosion or sediment transport by stormwater."


SYSTEM OPERATION AND MAINTENANCE

- The septic tank should be pumped when the total thickness of the scum and sludge layers in the inlet side of
- the tank is greater than 1/3 of total liquid level depth, typically about 2 feet. The effluent filter in the septic tank should be removed yearly and cleaned by hosing off into the inlet side of
- the septic tank. Less frequent cleanings may be acceptable.
- Grease and oils should not be put into the home drains.
- The septic tank is alive with microorganisms performing oxidation and reduction of the contents. Do not add any materials (paint thinner, paint, motor oil, unused medicine, cat litter, etc.) that may disrupt this process.
- DO NOT ROUTE WATER SOFTENER BACKFLUSH DISCHARGE TO TREATMENT SYSTEM! This
- discharge may be routed directly to an approved dispersal field.
- Repair all plumbing leaks (especially toilet leaks) promptly.
- Keep the area over the leach fields trimmed to prevent the growth of trees and shrubs. Do not construct anything or drive/park over the septic tanks or dispersal trenches.











	DFILE FIELD LOG Srownstone after Birkeland, 1999; Table A1.3 Test hole																
								eta T)e Lo	ma	а А л		NI 72	8-38-001	D	SP.	-1
me		M		V	egeta	tion	1 1	Grass	(crop)		, 1 .		IN <u>7</u>	0-00-001			
lie	nt _	~L	evel		As	pe	ct _	N./.	A	(Geoi	norpl	hic Su	rface Fluv	ial Terrac	e	
/R	iveı	D	epo	sits		Γ)esc	cribed	by 🔥	.B.						_	
M	[ottl	es	Clay	Films	Gravel	Ro	ots	0	onsiste	ence		Tex	ture	Color	Horizon	Con	tacts
quantity	size	contrast	amount	distinct	%	quantity	size	soft/ hard	loose/ friable	sticky 🔬		sund 100	clay 50 0 silt	Munsell (moist)	A E	distinct	topo
f c m	1 2 3	f d p	v1 1 2 3	f d p 	<10 10 25 50 75 >75 >75	f c m	f m lg	lo so sh	lo vfr fr fi vfi efi	SO SS S	po ps	S LS SL CD L CL	SiL SiC C SC	Light Grayish Brown	AB or EB E/B AC B BA or BE B/E BC or CB C	a c g d	s w i b
	\sim	l						dry	moist	w	>t		clav				
quantity	size	contrast	amount	distinct	%	quantity	size	soft/ hard	loose/ li friable	sticky 3	plastic	sand 100	50 0 silt	Munsell (moist)	Å	distinct	topo
f c m		f d p	2 3	d p 	<10 10 25 50 75 >75		m lg	lo so sh h vh eh	lo vfr fr fi vfn efi	so ss vs	p p vp	S SL SL L CL	SiL SiC C SC	Light Grayish Brown	AB or EB E/B AC BA or BE B/E BC or CB C		i b
1	one)	10	n	none	n	ne										
quantity	size	contrast	amount	distinct	%	quantity	size	soft/ hard	loose/ friable	sticky _§		sand 100	clay 50 0 silt	Munsell (moist)	O A E	distinct	topo
f c m	1 2 3	f d p	v1 1 2 3	f d p 	10 25 50 75 >75	f c m	f s lg	lo so sh h vh eh	lo vfr fi vfi efi	<u>so</u>	p p vp	S LS SL SCL L CL	ŝ	Medium Grayish Brown	AB or EB E/B AC B BA or BE B/E BC or CB C	a c g d N.	
1	one		10	ne	none	nc	ne					Gra	velly			11.	11
quantity	size	contrast		distinct	%	quantity	size	soft/ hard	loose/ friable tsiou	sticky _§	plastic	sand 100	clay 50 0 silt	Munsell (moist)	O A E	distinct	topo
f c	1	d		f d p	<10 10 25 50 75 >75	f c m		h vh	lo vfr fr fi vfi	so ss s vs	po ps p vp	S LS SL SCL L CL	SiCL SiL SiC SiC C	Dark Brown	AB or EB E/B AC B BA or BE B/E BC or CB	u	s w i b
	on	 ;	6	n	none	60	me	eh	efi				velly		\bigcirc	N./	A

	Source Consulting Source Consulting Test hole (modified by Andrew Brownstone after Birkeland, 1999; Table A1.3) Test hole (I.D.) Specified by Andrew Brownstone after Birkeland, 1999; Table A1.3) Job Number/Name: 21031- Apex Bait Location Vista De Lomas Ave APN 728-38-001 Specified by Andrew Brownstone after Birkeland, 1999; Table A1.3)															-2											
	Job Ni	umbe	r/Nai	me:	2	103	1-	A	pex	κB	ait		I	ocat	ion	Vi	sta E)e Lo	mas	s Av	e AP	יN 72	8-38-001	· · · N			
	Date S																	crop)				- ·					
	Elevati	ion	-			Slop	be (Gra	dier	nt	N	[/A		As	pec	t	N	V/A	(Geoi	norpł	nic Su	rface Fluv	ial Terrac	e		
	Parent	Mater	ial(s) _F	luvi	al D	epo	osit	ts						D	esc	cribed	by A	.B.						_		
	GRAP LOG	HIC	Moietu	ra Sti	ructi	ire	Po	res	м	ottle	26	Clay	Filme	Gravel	Ro	ofe	C	Consiste	nco		Tev	ture	Color	Horizon	Cont	tacts	
0 -		Sampla												Graver			dry	moist	w	•t	н	clay	COIOI	110112011		lucis	
1_	mus	Depth 1.5"	prior to analysis	grade	size	ype	quantity	size	quantity	size	contrast	amount	listinct	%	<u>quantity</u>	ize	soft/ f	- e	sticky		sand 100		Munsell (moist)	ò	distinct	topo	
•	1.		dry	m	vf		f		f !	1	f	v1				s f	lo			-	S	SiCL		ABOTER	a	\bigcirc	
2 –	1111		sm m vm wet	sg		pl (c	m	c m	2 3	d p	1	d p	25 50 75	c∣ m∣	s	so sh h vh	lo vfi fr fi vfi	so ss s vs	po ps p vp	LS SL CD L	SiL Si SiC C	Light to Medium Gray Brown	E/B AC B BA or BE B/E	c M	w i	
3 –	9°C					sbk								>75			eh	efi			CL	SC	DIOWI	BC or CB C			
	N.W				none	e	no	ne	i	on		no	ne	none	101	n					Gra	velly					
4 -		Sample Depth 3.0'	prior to analysis	grade	size	type	$\underline{quantity}$	size	quantity	size	contrast	amount	distinct	%	quantity	size	soft/ hard hard	loose/ misiom	sticky _≶		and 100	50 0 silt	Munsell (moist)	O A E	distinct	topo	
5 -	200		dry	m	vf	gr	f		f	1	f	v 1	f		f		lo	lo	60	ро	S	SiCL	Light to	AB or EB E/B	a	s	
č	.a. r		sm	sg		pl	сi	m	c	2	d	1	d	<10 10	ci	s	so	vfr	SS	ps	LS	SiL	Medium	AC	c	w	
6 -	0.0		m vm wet	$\frac{1}{2}$	c vc	pr cpr abk	m 	lg	m 	3	p	2 3	р	25 50 75 >75	m 	m lg	h vh eh	fr fi vfi efi	s vs	p vp	SL CD L CL	Si SiC C SC	Gray Brown	B BA or BE B/E BC or CB	g d	i b	
-	0:0				none		no	ne	1	one		10	ne	non	n	ne	en	en			Gra	velly		C	N./	A	
7-		Sample Depth	12. O				۲ ۲		2		ït	t	t		y		dry	moist	W	et	ŝ	clay			st _		
8 -	CIE	7.0 °	prior to analysis	grade		type	$\frac{1}{2}$ $\frac{1}{2}$ $\frac{1}{2}$	size		size	contrast		distinct	%	quantity	size	soft/ hard	loose/ friable	sticky	plastic	sand 100		Munsell (moist)	O A E AB or EB	distinct	topo	
	0-		dry	m sg		gr nl	f		f	$\frac{1}{2}$	f d	v1 1	f d	<10	f		lo	lo	SO	po ps	S LS	SiCL SiL	Medium	E/B	a c	s W	
9 -	140		Sm m		n	pl pr		m lg	m		u p	2	p p	10	c m		so sh	vfr	ss s	ps p	SD	Si	to	AC B	g	i	
	0.0		vm	2	c	cpr		-8		 	1	3	1	$\frac{25}{50}$		lg	h	fr	vs	vp	SCL	0.0	Brown	BA or BE B/E	d	b	
10-	(wet	3	vc	abk sbk	i		į	į				75 ≥15	İ		vh	vfi			L CL		(Varie- gated)	BC or CB	i		
	0.0				non		10	ne	1	one		10	ne	none	noi	ne	eh	efi				avelly	gated)	C	N.	A	
		Sample Depth	o.s				<u>y</u> _		V +		t	t	t		<u>y</u>		dry	moist	W		. W	clay			it _		
11–	10		prior to analysis	qe	i i	J	intit	0	Intit	, i	tras	uno	tinc		ntit		, p	se/ ble	ky	stic	*		Munsell	0	distinct	topo	
	0."		pri ané		size	type	qua	size	quantity	size	contrast	amount	dis	%	quantity	size	soft/ hard	loose/ friable	sticky	pla	sand 100	7 18 50 0 silt	(moist)	A E	diš	tol	
12-	140		dry	m	vf	gr	f	s	f	1	f	v1	f		f	f	lo	lo	50	60	S	SiCL		AB or EB E/B	a	s	
	P.C.		Sm	sg	f	pl		m	c	2	d	1	d	<10 10	c	s	so	vfr	SS	ps	LS SD	SiL Si	Brown	AC	C o	w i	
12	4		m vm	12	m c	pr cpr		ıg	m 	3	р	23	р	25 50	m	m lg	sh h	fr fi	s vs	p vp	SCL	SiC	(Varie-	B BA or BE	g d	b	
13-	024		wet	3		abk						-		(75)		-0	vh	vfi		'P	L	С	gated)	B/E BC or CB			
	· · ·				none	sbk	60	n	-6	one		6	n	>75 none	60	n	eh	efi			CL	SC avelly		-0°-	N./	A	
14-	BOTP	AT 14			and the	-		<u></u>		510		10	~	none							GI	aveny					
	(NO G			/ED)																						

SOIL PERCOLATION SUMMARY TABLE -- 8/31/21

	13	14	4	5	15	6	
	2.10'	2.21'	2.57'	2.61'	2.05'	2.25'	
3	2.30	2.50	5.40	15.00	69.40	2.60	
$R_1 = R \times 1.4$	3.22	3.50	7.56	21.00	97.16	3.64	
$R_2 = (\sum R_1) / #Holes$							7.78
FICE USE ONLY	TANK SIZE (Gal))		Leach Lin	ie (Ft)		





DREW	IST	Ma
7453 . 12/31/23	•]]	Ow
EW ROWSDE	<i>۲</i>	Dat
DE ONLIF		REVI

Job No.: 21031 | APN: 728-38-001 | **1** of 2

PROJECT DESCRIPTION

An onsite wastewater system specifying gravity-flow dispersal to a grid system drainfield with Infiltrator Quick4 Plus High-Capacity leaching chambers is proposed to serve a four bedroom single family dwelling and a two bedroom ADU to be constructed on Vista De Lomas Ave at Burnett Ave, Morgan Hill, Santa Clara County, CA.

DESIGN CONSTRAINTS & CRITERIA

- The proposed septic tanks and drainfield system are sized to serve a 4 bedroom single family dwelling and a 2 bedroom ADU with a total combined design wastewater flow of 825 gallons of wastewater per day (gpd) based on guidelines outlined in the Santa Clara County Code.
- Seasonal groundwater is estimated to be below 14' based on the results of the site evaluation and backhoe test-pits.
- No wells, springs or watercourses are situated within 100' of the proposed Onsite Wastewater Treatment System.

DRAINFIELD SIZING CALCULATIONS

(P) 4 BEDROOM HOUSE = 525 GPD (P) 2 BEDROOM ADU = 300 GPD TOTAL DESIGN FLOW = 825 GPD

AVG ADJ STABILIZED PERC RATE = 53 MPI 53 MPI = 0.40 GAL/SF APPLICATION RATE

825 GPD ÷ 0.40 GPD/SF = 2062.5 SF

2062.5 SF ÷ 6.6 SF/LF = 313 LF OF TRENCH REQUIRED 75 INFILTRATOR CHAMBERS = 300 LF

CROSS-OVER END TRENCH CONNECTION CREDIT: 6 LF × 4 = 24 LF 300 LF + 24 LF = 324 LF

324 LF (PRIMARY) + 324 LF (SECONDARY) = 648 LF OF TRENCH 75 INFILTRATORS (PRIMARY) + 75 INFILTRATORS (SECONDARY) = 150 INFILTRATORS TOTAL

SPECIFICATIONS

1. Building Sewer, Septic Tank

- 1.1. New 4" ABS building sewer lines shall be installed to convey all raw sewage from the dwellings to the new septic tank. All gravity sewer piping must maintain a minimum 2% continuous gradient. *All wastewater including graywater shall be discharged to the septic tank.*
- 1.2. Locate 2-way, 4" ABS cleanout fittings on the building sewer to facilitate snaking and for line location.
 1.3. One 2,000 gallon concrete, pinnacle-style Chapin Pre-Cast septic tank is specified. Tank shall have two 24" diameter, OSI access risers with fiberglass bolt-down lids (brown). Riser heights will be determined by tank burial depth (ideally 12" to 24"). Risers shall be installed 2" above finished grade. The tank shall be installed according to the manufacturer's guidelines.
- I.4. Install the access risers with a watertight joint using the adhesives supplied by the manufacturer. Access riser lids shall be brown unless otherwise requested.
- 1.5. The tank hole shall be excavated so that the tank sits level.
- 1.6. Install the tank inlet fitting with a watertight joint. Cap off or use a test plug on this fitting and fill the tank with clean water 2" above the joint between the riser and the tank top. Repair any leaks.1.7. Install an OSI Effluent Filter (Model: FTS0444-36V) at tank outlet.
- 2. Distribution Device & Gravity Flow Dispersal Trenches
- 2.1. A Bull Run Valve diversion valve shall be installed to divert the effluent flow between primary and secondary drainfields.

2.2. 4" ABS or SCH 40 PVC tightline shall be used to make gravity flow connections between the septic tank and the drainfield trenches. All gravity lines shall with maintain a continuous 2% min. gradient.


- 2.3. Dispersal trench bottoms shall be installed level and sidewalls scarified.
- 2.4. Dispersal trenches shall each have a depth of 3 feet. Trenches shall be installed in the general location shown on the plan and shall be spaced 10' on center.
- 2.5. Primary and secondary trench grid system fields are proposed. The grid fields shall each consist of 75 Quick 4 Plus High Capacity Infiltrator chambers.
- 2.6. A 4" ABS inspection riser with tight cap shall be installed at corner ends of each grid and shall extend a minimum of 12" above grade or remain accessible by means of a 10" round valve box to grade. Installer Qualifications and Responsibilities


3.1. The system installer shall be licensed by the State of California, Department of Consumer Affairs, to install

- septic systems.
- 3.2. All piping shall conform to the current edition of the California Plumbing Code.
- 3.3. The installer shall be responsible for locating any property lines, underground utilities or piping. Any damage to these facilities shall be the responsibility of the installer.
 3.4. The installer shall give at least 48 hours notice to County of Santa Clara Department Environmental Health
- 3.4. The installer shall give at least 48 hours notice to County of Santa Clara Department Environmental Health Service for all inspections requested.
 Site Class up and Enciper Control Measures
- 4. Site Clean up and Erosion Control Measures
- 4.1. All excavated areas shall be smoothed and all construction debris shall be removed from the site.4.2. All disturbed soils shall be seeded and mulched. Erosion Control Mix seed shall be used at the coverage recommended on the package for all disturbed soil.
- 4.3. Straw shall be used to cover all disturbed soil.
- 4.4. PER DIVISION C12, CHAPTER III OF THE COUNTY CODE (Sec. C12-513. Temporary erosion control.)
 "The permittee and any person(s) doing, causing or directing the grading shall install and maintain all precautionary measures necessary to protect adjacent watercourses and public or private property from damage by erosion, flooding, or deposition of mud or debris originating from the site. Precautionary measures must include provisions of properly designed erosion prevention and sediment control measures, so that downstream properties are not affected by upstream erosion or sediment transport by stormwater."

SYSTEM OPERATION AND MAINTENANCE

- The septic tank should be pumped when the total thickness of the scum and sludge layers in the inlet side of the tank is greater than 1/3 of total liquid level depth, typically about 2 feet.
- The effluent filter in the septic tank should be removed yearly and cleaned by hosing off into the inlet side of the septic tank. Less frequent cleanings may be acceptable.
- Grease and oils should not be put into the home drains.
- The septic tank is alive with microorganisms performing oxidation and reduction of the contents. Do not add any materials (paint thinner, paint, motor oil, unused medicine, cat litter, etc.) that may disrupt this process.
 DO NOT ROUTE WATER SOFTENER BACKFLUSH DISCHARGE TO TREATMENT SYSTEM! This discharge may be routed directly to an approved dispersal field.
- Repair all plumbing leaks (especially toilet leaks) promptly.
- Keep the area over the leach fields trimmed to prevent the growth of trees and shrubs. Do not construct anything or drive/park over the septic tanks or dispersal trenches.





INFILTRATOR QUICK4 PLUS HIGH-CAPACITY PLUS SEPTIC DRAINFIELD TRENCH CONSTRUCTION DETAIL

i	ista De Lomas Ave APN 728-38-001													
G	i rass (crop)												
	N/A			Geoi	norph	ic Su	rface Fluy	ial Terrac	e					
(cribed	by A	.B.						_					
	C	Consiste	ence		Text	ture	Color	Horizon	Con	tacts				
	dry	moist	w	et	100.0	iay N			ן נכ					
	soft/ hard	loose/ friable	sticky	plastic	sand 100	Z SO 0 silt	Munsell (moist)		distinct	topo				
	lo so sh h vh eh	lo vfr fr fi vfi efi	so ss s vs	po ps vp	S LS SL L CL	SiL Si SiC C SC	Light Gray Brown	AB of EB E/B AC B BA or BE B/E BC or CB C		s W i b				
	soft/ p hard kl	loose/ friable sign	sticky _≷	plastic #	sand 100	Lay Z S0 0 silt	Munsell (moist)	O A E	distinct	topo				
	lo so sh h vh eh	lo vfr fr fi vfi efi	SO SS VS	po ps p vp	S SL SL L CL	SiL SiC C SC	Light to Medium Gray Brown	ABor EB E/B AC BA or BE B/E BC or CB C		s w i b				
	soft/ hard hard	loose/ mision	sticky _≦	plastic	sand 100	lay Z B S0 0 silt	Munsell (moist)	O A E	distinct	topo				
	lo so sh h vh eh	lo vfr fr fi vfi efi	so ss s vs	ps p vp	S LS S C L	SiCL SiL Si SiC C SC velly	Gray Brown	AB or EB E/B AC BA or BE B/E BC or CB	a c g d N.	s w i b				
	soft/ hard Ap	loose/ friable	sticky _≦	plastic		T So 0 silt	Munsell (moist)	O A E	distinct	topo				
	lo so sh h vh	lo vfr fr fi vfi	so ss s vs	ම	S S S LS S L S C L	SiCL SiL Si SiC	Brown to Dark Brown (Varie-	E/B AC B BA or BE B/E	a c g d	s w i b				
	eh	efi			CL Grav	<u>€∂</u> velly	gated)	BCorCB	N./	A				

BioSp	hereCo	onsul	iding										1999; Ta									Т	est hole I.D.	SP	-4
Job N	umbe	r/Na	me:	2	103	1-	A	pe	x B	ait	t	Ι	locat	ion	Vi	sta I)e Lo	ma	s Av	e AP	N 72	8-38-001	1 1	$\wedge \wedge$	$ \square$
Date	Soil Sa	mple	d_	8	-4-21		Т	ime	1	2:45	5 PN	1 V	egeta	tior	1 <u>G</u>	Frass (crop)		_						
Eleva	tion _				Slop	be (Gra	die	nt _		N/.	4	As	spec	ct	N/A			Geor	norph	ic Su	rface Fluy	ial Terra	e:e	
	t Mater	rial(s)	Fl	uvial	De	pos	sits						D	esc	cribed	by A	.B.						_	
GRA LOG	PHIC	Moistu	re St	ruct	ure	Po	res	Μ	ottl	es	Clay	Films	Gravel	Ro	ots	C	Consiste	ence		Text	ture	Color	Horizon	Con	tact
1564	Sample Depth	12. O				N.		<u>V</u>		st	t			<u>S</u>		dry	moist	W		ŝ	lay A ^o			ct	
144-01	1.5"	prior to analysis	de	่อ	e	mtit	0	intit	a	contrast	uno	distinct		intit	n	,, p	loose/ friable	sticky	plastic	×.	1.6	Munsell	O A	distinct	topo
10.5	1.5	pr an	gra	size	type		size	quantity	siz	coi	am	dis	%	quantity	siz	soft/ hard	loo friɛ	stic	pla	sand 100	Z 8 50 0 silt	(moist)	E		
1.6		dry	m	vf	gr	f	s	f	1	f	v1	f		f	f	lo	lo	SO	po	S	SICL	Light	AB r EB E/B		
31		sm	sg		pl		m		2	d	1	d		c		so	vfr	SS	ps	LS SL	SiL Si	Gray	AC	Ĝ	w
1.1		m vm	$\frac{1}{2}$		pr (cpr	m	lg	m	3	р	2 3	p	25	m		sh	fr	s	р		SiC	Brown	B BA or BE	d	i b
111.14		wet	<u>ح</u>	vc	abk	ļ		į			5		50 75		lg	h vh	n vfi	vs	vp	L	С	DIOWI	B/E		ļ
31			\sim		sbk			l					>75		_	eh	efi		1	CL	SC		BC or CB C		
	Sample			non	e	no	ne	1	one		no	ne	none	10	ne				<u> </u>						
21	Depth	prior to analysis				ΣÌ		_بت ا		ıst	nt	נד		ΣÌ		dry	moist	W		, ¹⁰⁰ ,	lay N	N 11		lct	ļ
(1)(1/1)	3'	naly	grade	e l	type	quantity	e.	ant_	size	ntra	amount	distinct	%	quantity	õ	soft/ hard	loose/ friable	sticky	plastic	Å	15	Munsell (moist)	O A	distinct	topo
00'	ľ		50										70			so ha	ĒĒ			sand 100	50 0 silt	(moist)	E AB or EB		
000		dry	m	vf		f		f	1	f d	v1		610		f	lo	lo		po	S LS	SiCL SiL	* * *	E/B	a c	S
10.		sm m	sg 1		pl pr		m la	c m	2 3		1 2	∣d ∣p	(10) 10	c∣ m∣		so	fr	SS S		SL	Si	Light to	B	g	i w
0.00		vm	(2)	c	cpr		1g		5	Р	3	P	25 50		lg	h	fi	s vs	p vp		SiC	Medium	BA or BE	ď	b
1 13		wet	3	vc	abk								75		0	vh	vfi		P	Ĺ	С	Gray	BC or CB		
) = 1				none	sbk	no	<u>n0</u>	ļ	one		10		>75 none	60		eh	efi			CL	SC	Brown	C		į.
4 (Sample		-						\sim				none			dry	moist	W	d t						1
CP.	Depth	prior to analysis	a			quantity		quantity		contrast	amount	nct		quantity			्राणांडा २०२			a.	N.	Munsell	0	distinct	
De O	5 '	orio	grade	IZe	type	uan	Ze	uan	Ize	ontı	om	listi	%	uan	ze	soft/ hard	loose/ friable	sticky	plastic	and Series	Z	(moist)	А	disti	topo
911	╠┶╼═┙	-						ज। f		5 f		f		ठ f	. <u>S</u>				1	S	SiCL		E AB or EB	a	s
30		dry sm	m sg	vf	gr pl	f	s m		1 2	ı d	v1 1		<10	I c		lo so	lo vfr	SO	po ps	LS	SiL		E/B AC	c a	W
5 Gm.		m		m	pr			m		p	2	l p	10	m		sh	fr	55 5	ps p	SD	Si	Medium	B	g	i
101		vm	2	c	cpr		Ũ			1	3		25 50		lg	h	fi	vs	vp	$\overline{\mathbb{O}}$	SiC	Brown	BA or BE B/E	d	b
UD		wet	3	vc		li		i					75 >75	i		vh	vfi			L CL	C SC	(Varie-	B/E BC or CB		
0"0				non	sbk e	6	n	1	on		10	ne	none	no	ne	eh	efi			Grav		gated)	C	N.	/A
ac	Sample	o s				+		- 1	\sim							dry	moist	W	et		lay			it.	
- De	Depth	or te	de			ntit		ntit		tras	unc	inct		ntit			se/ ble			\$	15	Munsell	0	distinct	l g
×6	14'	prior to analysis	grade	size	type	quantity	size	quantity	size	contrast	amount	dist	%	quantity	size	soft/ hard	loose/ friable	sticky	plastic	sand 100	Z 38 50 0 silt	(moist)	A E	dis	topo
00		dry	m	vf	gr	f		f	1	f	v1	f		f	f	lo	lo	so	00		SiCL		AB or EB E/B	а	s
0		sm	sg		pl	ci	m	c			1		<10 10	c	s	so	vfr	SS	ps		SiL	Medium	AC	с	w
20		m vm	12	m	pr	m	lg	m	3	р	2 3	p	25	m		sh	fr	s vs	р		Si SiC	to	B BA or BE		i b
00		wet		c vc	cpr abk						9		50 75		lg	h_{vh}	(fi) vfi	VS	vp	L	C	Dark	B/E	_	ľ
0s'					sbk	نرا							>75			eh	efi		1	CL	SC	Brown	BC or CB	N./	A
51				norle	e	ho	ne		ione	;	ko	ne	none	ko	ne	ļ				Grav	velly			1	r *
	PAT 14 GW OB			`																					
(INO (SER	v ED	,																					

SOIL PERCOLATION SUMMARY TABLE -- 8/6/21

Percolation Hole (PH)		7	8	9	10	11	12	1
Depth		2.68'	2.80'	2.63'	2.71'	2.60'	2.58'	
Stabilized MPI	R	37.70	34.90	13.20	65.50	250.00	130.60	
Adjusted Stabilized MPI	$R_1 = R \ge 1.4$	52.78	48.86	18.48	91.70	350.00	182.84	1
Avg. Adj. Stabilized MPI	$\mathbf{R}_2 = (\sum \mathbf{R}_1) / \# \mathbf{Holes}$							52.
# Bedrooms:	FOR OFFICE USE ONLY	TANK SIZE (Gal	TANK SIZE (Gal)		Leach Line (Ft)			

COUNTY E.H. ACCEPTANCE/APPROVAL STAMPS




Site Evaluation & Mapping
Soil Analysis & Percolation Testing
New Development, Upgrade & Repairs
Residential & Commercial

1315 King Street bairs Santa Cruz, CA 95060 **Tel: (831) 430-9116** www.biosphere-consulting.com

A Incorporated

Alternative Wastewater System Design

ONSITE WASTEWATER TREATMENT SYSTEM DESIGN PLAN



Proje	roject Location: Vista De Lomas Ave at Burnett Ave, Morgan Hill, CA						
Prope	erty Owner:						
Maili	Mailing Address: 309 Laurelwood Rd, Santa Clara, CA 95054						
Owne		email: dliang@apexbait.com					
Date:	02/04/22	By: David Quinn / Andrew Brownstone					
REVISION:		Job N	o.: 21031	APN: 728-38-00	1 2 OF 2		