

W.U.I. NOTES

-This parcel is located in the WUI (Wildland Urban Interface).
-This parcel is located in the State Response Area. Therefore the responding agency is CAL Fire and must comply with SRA Fire Safety Regulations- PRC 4290.
-A defensible space to be maintained at all times.

Materials, Systems and Methods of Construction

Roofing Assemblies:
Roofing assemblies shall be designed to prevent the intrusion of flames and embers between the roof covering and the roof decking.
Roof valley flashing shall be made of not less than 26-gage galvanized sheet metal installed over a minimum 36" wide underlayment of one layer of 72# cap sheet running the full length of the valley.
Roof gutters shall be designed to prevent the accumulation of leaves and debris in the gutter.

Attic Ventilation:
Ventilation openings for enclosed attics, enclosed eave soffit spaces, enclosed rafter spaces formed where ceilings are applied directly to underside of roof rafters & underfloor ventilation openings shall be fully covered with Wildland Flame & Ember Resistant (WUI) vents approved & listed to ASTM E2886 as per CRC code section R337.6.2.

Vents shall not be installed on underside of eaves & cornices unless vents are Wildland Flame & Ember Resistant (WUI) vents approved & listed by the California State Fire Marshal, or WUI vents listed to ASTM E2886 as per CRC code section R337.6.3.

Eave protection: Eaves & soffits shall be protected by ignition-resistant materials or noncombustible construction on the exposed underside as per CRC R337.7.4 & R337.7.5

Exterior Walls:
Exterior walls shall be designed using ignition-resistant materials, noncombustible construction, heavy timber, log wall construction, or equivalent.
Exterior wall coverings shall extend from the top of the foundation to the roof, and terminate at 2" nominal solid wood blocking between the rafters at all roof overhangs, or terminate at an eave enclosure.

Exterior vertical wall vents: Per CRC R337.6.2.1, requirements of 706.A.2 shall apply to gable ends, ridge ends, crawl spaces, foundations and all other ventilation vents that mount on a vertical wall. Wildland Flame & Ember Resistant vents approved & listed by the CA State Fire Marshal or WUI vents listed to ASTM E2886 shall be used.

Exterior window, window wall, and glazed door assemblies shall have a 20 minute fire-resistant rating, or be designed using insulating glass units with a minimum of one tempered pane, or glass block units.

Exterior door assemblies shall have a 20-minute fire-resistant rating, or be designed using noncombustible construction, or be constructed of solid-core wood having stiles and rails not less than 1-3/8" thick, and field panels not less than 1-1/4" thick.

Exterior vehicle access doors shall be non-combustible or exterior fire-retardant treated wood.

Weather stripping:
Exterior garage doors shall be provided with weather stripping to resist the intrusion of embers from entering through gaps between doors and door openings when visible gabs exceed 1/8 inch (3.2mm). Weather stripping or seals shall be installed on the bottom, sides, and tops of doors to reduce gaps between doors and door openings to 1/8 inch or less. CRC Sec. R337.8.4.

Decking: Deck surfaces; stair treads, risers and landings; porches; and balconies within 10 feet of the primary structure shall comply with the following:
* Shall be designed using ignition-resistant materials, noncombustible construction, heavy timber, exterior fire-retardant treated wood or equivalent.
* The use of paints, coatings, stains or other surface treatments are not an approved method of protection.

Underfloor and appendages protection

The underside of cantilevered and overhanging appendages and floor projections shall maintain the ignition-resistant integrity of exterior walls, or the projections shall be enclosed to grade.

Ancillary buildings and structures, and detached accessory structures, shall comply with the above provisions.

Prior to building permit final approval, the property shall be in compliance with the state's vegetation clearance requirements prescribed in California Fire Code Sec. 4906, incl. California Public Resources Code 4291 or California Government Code Section 51182 per CRC R337.1.5.

FIRE NOTES

FIRE SPRINKLER SYSTEM:
AN APPROVED RESIDENTIAL FIRE SPRINKLER SYSTEM COMPLYING WITH CFMO-SP6 SHALL BE INSTALLED THROUGHOUT THE STRUCTURE SYSTEM & FINALED BY THE FIRE MARSHAL OFFICE.

RESIDENTIAL FIRE SPRINKLER SYSTEM WILL BE A DEFERRED SUBMITTAL.

THE FIRE SPRINKLER SYSTEM SHALL BE INSTALLED AND FINALED BY THE COUNTY OF SANTA CLARA FIRE DEPARTMENT PRIOR TO OCCUPANCY. A SEPARATE PERMIT SHALL BE OBTAINED FROM THE COUNTY OF SANTA CLARA FIRE DEPARTMENT BY A STATE LICENSED C-16 CONTRACTOR PRIOR TO INSTALLATION. PLEASE ALLOW FOR A MINIMUM OF 30 DAYS FOR PLAN REVIEW OF FIRE SPRINKLER PLANS BY THE COUNTY OF SANTA CLARA FIRE DEPARTMENT.

MAINTENANCE:
FIRE PROTECTION WATER SYSTEMS AND EQUIPMENT SHALL BE ACCESSIBLE AND MAINTAINED IN OPERABLE CONDITION AT ALL TIMES, AND SHALL BE REPLACED OR REPAIRED WHERE DEFECTIVE. FIRE PROTECTION WATER SHALL BE MADE AVAILABLE TO THE FIRE DEPT.

FIRE DEPT. ACCESS ROADS, DRIVEWAYS, TURNOUTS, & TURNAROUNDS SHALL BE MAINTAINED FREE & CLEAR & ACCESSIBLE AT ALL TIMES FOR FIRE DEPT. USE. GATES SHALL BE MAINTAINED IN GOOD WORKING ORDER, & SHALL REMAIN IN COMPLIANCE WITH FIRE MARSHAL STANDARD CFMO-A3 AT ALL TIMES.

APPROVED NUMBER OR ADDRESSES shall be placed on all new buildings in such a position to be plainly visible & legible from the street or road fronting the property. Address numbers shall be Arabic & contrast with their background & be min. of 4" in ht. w/min. stroke width of 0.5 in. If means of private road and building cannot be viewed from public right of way, a pole or other sign/means shall be used to identify the structure. Numbers to be maintained per cfc sec. 505.1.

GEN. CONSTRUCTION NOTES

ANY VARIATION FROM THE SPECIFIED DESIGN, FINISH PRODUCTS OR EXTERIOR ELEVATION STYLE IS TO BE BROUGHT TO THE ATTENTION OF THE DESIGNER PRIOR TO CONSTRUCTION.

ANY DISCREPANCY DISCOVERED ON THESE PLANS SHALL BE BROUGHT TO THE ATTENTION OF D&Z DESIGN ASSOCIATES PRIOR TO COMMENCEMENT OF THE WORK IN QUESTION. ALL WRITTEN DIMENSIONS SHALL TAKE PRECEDENCE OVER SCALED DIMENSIONS.

ALL WORK TO BE IN CONFORMANCE WITH
2022 CALIFORNIA BUILDING CODE
2022 CALIFORNIA RESIDENTIAL CODE
2022 CALIFORNIA MECHANICAL CODE
2022 CALIFORNIA PLUMBING CODE
2022 CALIFORNIA ENERGY CODE
2022 CALIFORNIA HISTORICAL BUILDING CODE
2022 CALIFORNIA FIRE CODE
2022 CALIFORNIA EXISTING BUILDING CODE
2022 CALIFORNIA GREEN BUILDING STANDARDS CODE
2022 CALIFORNIA REFERENCED STANDARDS CODE
2022 CALIFORNIA ELECTRICAL CODE
AS WELL AS THE STATE, LOCAL, CODES & COUNTY OF SANTA CLARA ORDINANCE CODE

CONTRACTOR ASSUMES FULL RESPONSIBILITY FOR METHOD & MANNER OF CONSTRUCTION & FOR ALL JOB SITE SAFETY DURING CONSTRUCTION. VERIFY LOCATION OF UTILITIES AND EXISTING CONDITIONS AT SITE PRIOR TO CONSTRUCTION AND BIDDING.

SLOPE ALL FINISH GRADES A MIN. OF 5% FOR 10'-0" AWAY FROM STRUCT. FOR POSITIVE DRAINAGE @ LANDSCAPED AREAS & SLOPE GRADE 2% MIN. @ PAVED AREAS.


THE BUILDER SHALL PROVIDE THE BUILDING OWNER, MANAGER, & ORIGINAL OCCUPANTS A LIST OF ENERGY-SAVING CONSERVATION FEATURES DEVICES, MATERIALS, & COMPONENTS INSTALLED IN THE BUILDING, & INSTRUCTIONS ON HOW TO USE THEM EFFICIENTLY, SUCH FEATURES INCL. HEATING, COOLING, WATER HEATING, & LIGHTING SYSTEMS, AS WELL AS INSULATION, WEATHER-STRIPPING WINDOW SHADES, & THERMAL MASS MATERIALS. THE INSTRUCTIONS SHALL BE CONSISTANT WITH SPECS. SET FORTH BY THE EXECUTIVE DIRECTOR

ALL WORK APPLIANCES AND EQUIPMENT SHALL COMPLY WITH C.E.C. TITLE 24 RESIDENTIAL ENERGY STANDARDS.

SEE SHEET T24.1 & T24.2 FOR ADDITIONAL ENERGY COMPLIANCE NOTES
IF ARCHEOLOGICAL RESOURCES OR HUMAN SKELETAL REMAINS ARE DISCOVERED DURING CONSTRUCTION, WORK SHALL STOP IMMEDIATELY, AND THE COUNTY RECORDER'S OFFICE NOTIFIED.

ALL CONSTRUCTION ACTIVITIES SHALL BE IN CONFORMANCE WITH THE SANTA CLARA COUNTY NOISE ORDINANCE SECTION B11-154 & PROHIBITED BETWEEN THE HOURS OF 7:00 P.M. & 7:00 A.M. ON WEEKDAYS & SATURDAYS, OR AT ANY TIME SUNDAYS FOR THE DURATION OF CONSTRUCTION.

SYMBOLS




SCOPE OF WORK

Construction of a new 4,868 s.f. two level Single Family Residence w/lower level living space w/400 s.f. unconditioned storage space, attached 946 s.f. 3-car Garage & 107 s.f. covered Entry Porch. The proposed project includes site retaining walls and is located on a vacant parcel within an existing subdivision.

CONSULTANTS

SOILS ENGINEER
Geo-Logic Associates
6300 San Ignacio Avenue, Ste. A
San Jose, California 95119
(408) 778-2818
Project: PA21.1036.00
Dated: February 9, 2022
CIVIL ENGINEER & SEPTIC DESIGN
Le Engineering
598 E. Santa Clara Street, Suite #270
San Jose, California 95112
(408) 806-7187
BIOLOGIST
Coast Range Biological, LLC
PO Box 1238
Santa Cruz, California 95061
(831) 426-6226
LANDSCAPE ARCHITECT
Karen Aitken & Associates
8262 Rancho Real
Gilroy, California 95020
(831) 842-0245
ARBORIST
David Hamilton
Mighty Tree Movers, Inc.
P.O. Box 12
Los Gatos, California 95031
(408) 464-5200

VICINITY MAP



DRAWING INDEX

T1 Title Sheet

Civil Drawings

- 1 of 5 Site Plan
- 2 of 5 Grading & Drainage Plan
- 3 of 5 Driveway Profile & Cross Sections
- 4 of 5 Driveway Sections
- △ 5 of 5 Disturbed Areas

Septic Drawings

- 1 of 1 Septic System Plan (Stamped)

Architectural Drawings

- A1.1 Site Plan
- A1.2 BMP-1/ Erosion Control Details
- A1.3 BMP-2/ Erosion Control Details
- A2.1 Entry Level Floor Plan
- A2.2 Lower Level Floor Plan
- A2.3 Floor Area Diagrams
- A3 Exterior Elevations
- A4 Cross Sections
- A5 Roof Plan

Landscape Drawings

- L-1 Planting Plan
- L-2 Irrigation Plan
- L-3 Irrigation Details
- L-4 Irrigation & Planting Details

PROJECT DATA

OWNER:
Brooke Rahn
695 E. Brokaw Road
San Jose, Calif. 95112
(650) 868-6716

LOT DATA:

APN: 776-35-012
ZONING: HS-d (95.1%) RR (4.9%)
LOT SIZE: 5.4 Ac. (236,531 S.F.)
LOT: 2355 Rockwood Ranch Rd.
Morgan Hill, California
Lot 12
Chesbro Lake Estates
Tract 8520

Occupancy Group: R3/U

Type of Construction: VB

PROJECT GROSS FLOOR AREA:

4084 sq. ft. Entry Level Living Area
784 sq. ft. Lower Level Living Area
4868 sq. ft. Total Living Area
946 sq. ft. Garage
400 sq. ft. Unconditioned Storage
107 sq. ft. Covered Entry Porch
6321 sq. ft. Total Gross Area

RAHN RESIDENCE


2355 Rockwood Ranch Road

Morgan Hill, California

NO./ DATE/ REVISION

△ PLANNING
9-1-2022
△ PLANNING
10-20-2022

THESE PLANS ARE INTENDED ONLY FOR THE ORIGINAL SITE FOR WHICH THEY WERE DESIGNED. ANY REUSE OF THESE PLANS FOR ANY OTHER PROJECT OR AT ANY OTHER LOCATION WITHOUT THE WRITTEN CONSENT OF D&Z DESIGN ASSOCIATES, ANY USE OF THESE PLANS ON OTHER SITES IS PROHIBITED WITHOUT THE CONSENT OF D&Z DESIGN ASSOCIATES. PRIOR TO THE ATTENTION OF D&Z DESIGN ASSOCIATES PRIOR TO COMMENCEMENT OF THE PROJECT, ANY REUSE OF THESE PLANS SHALL TAKE PRECEDENCE OVER SCALED DIMENSIONS.



DRAWING TITLE Title Sheet
JOB TITLE Rahn Residence
JOB ADDRESS 2355 Rockwood Ranch Road
Morgan Hill, California

DATE JAN. 24, 2021
SCALE NONE
PROJECT MANAGER M. DAVIS
DRAWN MIKE
JOB NO. DZ3521
SHEET

T1


PRELIMINARY GRADING PLAN
FOR
LANDS OF RAHN
2355 ROCKWOOD RANCH ROAD
APN 776-35-012

PROJECT DATA

LOT SIZE: 5.40 AC
ZONING: HS-d (95.1%) RR (4.9%)
(N) HOUSE DATA: 5,137 SF BUILDING FOOTPRINT
(N) PORCH, PATIO & WALKWAY: 744 SF
(N) DRIVEWAY: 5,963 SF

MUTUAL WATER CO INFORMATION: ROCKWOOD ESTATES MUTUAL WATER CO.
STORAGE CAPACITY: APPROX. 90,000 GAL

VICINITY MAP
NTS



EARTHWORK QUANTITY

| LOCATION | CUT (C.Y.) | FILL (C.Y.) | VERT. DEPTH |
|-----------------------|------------|-------------|-------------|
| RESIDENCE | 207 | 259 | 7' |
| LANDSCAPE | 148 | 388 | 3' |
| DRIVEWAY | 1,669 | 79 | 12' |
| DETENTION | 45 | - | - |
| OFF SITE IMPROVEMENTS | - | - | - |
| TOTAL | 2,070 | 726 | - |

DISTURBED AREAS

| NO. | DESCRIPTION | AREA (SQUARE FEET) | |
|------------|-------------|--------------------|----------|
| | | ON-SITE | OFF-SITE |
| 1. | TEMPORARY | 22,792 | 0 |
| 2. | PERMANENT | 15,232 | 444 |
| TOTAL AREA | | 38,024 | 444 |

TREES TO BE REMOVED

| TREE NO. | SPECIES | DIAMETER (IN) | CANOPY DIA (FT) | AREA (SF) |
|----------|----------------|---------------|-----------------|-----------|
| 1 | VALLEY OAK | 21 | 20 | 314 |
| 2 | COAST LIVE OAK | 15 | DEAD | |
| 3 | VALLEY OAK | 10 | 20 | 314 |
| 6 | VALLEY OAK | 15 | 30 | 707 |
| 7 | VALLEY OAK | 16 | 20 | 314 |
| 11 | OAK | 12 | DEAD | |
| 12 | VALLEY OAK | 17 | 15 | 177 |
| 13 | VALLEY OAK | 16 | 25 | 491 |
| 14 | VALLEY OAK | 15 | 25 | 491 |
| 21 | OAK | 18 | 25 | 491 |
| 22 | VALLEY OAK | 22 | 22 | 380 |
| 26 | OAK | 28 | 35 | 962 |
| 30 | VALLEY OAK | 22 | 30 | 707 |
| 31 | VALLEY OAK | 24 | 25 | 491 |
| 33 | OAK | 22 | 20 | 314 |
| 34 | VALLEY OAK | 15 | 20 | 314 |
| 35 | OAK | 13 | 15 | 177 |
| 36 | VALLEY OAK | 14 | 25 | 491 |
| 40 | VALLEY OAK | 12 | 15 | 177 |
| 41 | VALLEY OAK | 10 | 20 | 314 |
| TOTAL | | 20 | | 7626* |

* OAK CANNOPY TO BE REMOVED

NOTES:

- FIRE SPRINKLERS ARE TO BE A DEFERRED SUBMITTAL.
- ROCKWOOD RANCH ROAD & DRIVEWAY TO BE CAPABLE OF SUPPORTING A 75,000 LBS FIRETRUCK AND THAT THE DRIVEWAY BE MAINTAINED TO SUPPORT 40,000 LBS.
- THE RUNOFF ON SITE SHALL BE COLLECTED BY STORM DRAIN INLETS AND DRAINED TO THE RETENTION BY THE PIPE.



APPROVED FOR ISSUANCE
REFER TO ENCROACHMENT AND/OR
CONSTRUCTION PERMIT AND PLAN
COVER SHEET FOR SPECIAL
CONDITIONS AND PERMIT NUMBERS

LEGEND:

- MIXED OAK WOODLAND AND FOREST
- MIXED RIPARIAN FOREST AND WOODLAND
- RURAL RESIDENTIAL
- SERPENTINE BUNCHGRASS GRASSLAND
- col COLLUVIUM; SHOWN WHERE THICKER THAN THREE FEET
- Qa ALLUVIUM
- sp SERPENTINITE
- KJfm FRANCISCAN COMPLEX MELANGE
- KJfs FRANCISCAN COMPLEX SANDSTONE AND SHALE
- CONTACT BETWEEN UNITS: DASHED WHERE APPROXIMATELY LOCATED
- FAULT TRACE; DASHED WHERE APPROXIMATELY LOCATED, DOTTED WHERE CONCEALED

388 M5
PARCEL C
APN 776-35-017

LOT 13
APN 776-35-013

LOT 8
APN 776-35-003

LOT 11
APN 776-35-011

TRACT NO. 8520
"CHESBRO LAKE ESTATES"
LOT 12
APN 776-35-012
LOT SIZE AREA = 5.43 ACRES (NET)
= 4.67 ACRES (GROSS)
KJfs

LEACH FIELD SIZING

STANDARD WASTEWATER APPLICATION RATES (SWAR)
AVERAGE ADJUSTED PERCOLATION RATE = 49 MPI
FROM PREVIOUS APPLICATION PER EACH 1/2 DUAL SYSTEM

$$SWAR = 0.23$$

TRENCH LENGTH CALCULATIONS

$$L = \frac{Q}{RA}$$

L = TRENCH LENGTH;
Q = DESIGN WASTEWATER FLOW (GPD)
R = SWAR (GPD/SF)
A = TOTAL INFILTRATIVE AREA PER LINEAL FOOT OF TRENCH (SF)

USE INFILTRATIVE SURFACE OF 4 SF

$$L = \frac{525}{(0.23)4} = 570.65'$$

30% INFILTRATOR CHAMBER REDUCTION

$$570.65 \times 0.7 = 399.45'; \text{ USE } 402'$$

APPLICANT : RAHN

ROAD NAME : ROCKWOOD RANCH ROAD





COUNTY FILE NO :

| DATE | BY | DATE | REVISIONS |
|----------|----|----------|-------------------|
| 11/17/21 | PT | 11/17/21 | DESIGNED |
| 11/17/21 | PT | 11/17/21 | DRAWN |
| 10/20/22 | PT | 9/7/22 | PLANNING COMMENTS |
| 9/7/22 | PT | 9/7/22 | PLANNING COMMENTS |
| 11/17/21 | PT | 11/17/21 | CHECKED |

| DATE | BY | DATE | REVISIONS |
|----------|----|----------|-------------------|
| 11/17/21 | PT | 11/17/21 | DESIGNED |
| 11/17/21 | PT | 11/17/21 | DRAWN |
| 10/20/22 | PT | 9/7/22 | PLANNING COMMENTS |
| 9/7/22 | PT | 9/7/22 | PLANNING COMMENTS |
| 11/17/21 | PT | 11/17/21 | CHECKED |

ENGINEERING
598 E Santa Clara St #270
San Jose, CA 95112
Phone: (408) 806-7187

SITE PLAN
LANDS OF RAHN
2355 ROCKWOOD RANCH ROAD
APN 776-35-012
California
Morgan Hill
SHEET NO. 1 OF 5
FILE NO. 1
CONTRACT NO. PROJECT NO.



- NOTES:
- THE BACKFILL MATERIAL WITHIN TEST PITS FROM THE GEOLOGIC INVESTIGATION, WHICH ARE LOCATED WITHIN THE BUILDING'S ENVELOPE, SHOULD BE SUBEXCAVATED, RECOMPACTED AND TESTED AS OUTLINED IN THE PROJECT SOILS REPORT.
 - SHALLOW HARD ROCK CONDITIONS MAY BE ENCOUNTERED DURING GRADING. ALL UNDERGROUND CONTRACTORS SHOULD BE AWARE OF THESE CONDITIONS.



FILE NO.

2 OF 5

SHEET NO.

CONTRACT NO.

PROJECT NO.

California

2355 ROCKWOOD RANCH ROAD

LANDS OF RAHN

GRADING, DRAINAGE PLAN

APN 776-35-012

Morgan Hill

ENGINEERING

598 E Santa Clara St #270

San Jose, CA 95112

Phone: (408) 806-7187

DESIGNED

11/17/21

DATE

DRAWN

11/17/21

DATE

CHECKED

11/17/21

DATE

BY

DATE

APPROVED


DATE

PLANNING COMMENTS



9/7/22

REVISIONS

NO.











NOTES: Outlets for subdrains shall be located by the geotechnical engineer.
The necessity for subdrains shall be field determined by the geotechnical engineer.



COUNTY FILE NO :

| | | | | | |
|-------------|--|--|--|--------------------------------------|--|
| DRAWING NO. | | DRIVEWAY PROFILE AND CROSS SECTIONS LANDS OF RAHN 2355 ROCKWOOD RANCH ROAD APN 776-35-012 | | California PROJECT NO. | |
| SHEET NO. | | 3 OF 5 | | Morgan Hill CONTRACT NO. | |
| FILE NO. | | 1 | | | |




| ESTIMATE EARTHWORK QUANTITY | | | | | | | |
|-----------------------------|-----------|---------|--------------------|--------|-----------------------------|---------------------|------------|
| No. | STATION | | AREA (SQUARE FEET) | | DISTANCE | VOLUME (CUBIC YARD) | |
| | | | CUT | FILL | (FEET) | CUT | FILL |
| 1 | A-A | MIDDLE | 80.00 | 100.00 | 70.00 | 207.41 | 259.26 |
| 1 | A-A | (LEFT) | | 70.00 | 80.00 | 0.00 | 207.41 |
| 2 | B-B | (LEFT) | | 61.00 | 80.00 | 0.00 | 180.74 |
| 3 | A-A | (RIGHT) | | | COUNTED ON DRIVEWAY SECTION | | |
| 4 | B-B | (RIGHT) | 40.00 | | 100.00 | 148.15 | 0.00 |
| 5 | 10+50 | | 197.00 | | | | |
| 6 | 11+00 | | 276.00 | | 50.00 | 437.96 | 0.00 |
| 7 | 11+50 | | 97.00 | | 50.00 | 345.37 | 0.00 |
| 8 | 12+00 | | 152.00 | | 50.00 | 230.56 | 0.00 |
| 9 | 12+50 | | 278.00 | | 50.00 | 398.15 | 0.00 |
| 10 | 13+00 | | | 85.00 | 50.00 | 257.41 | 78.70 |
| | DETENTION | | | | | 45.19 | |
| | | | | | | | |
| | | | | | TOTAL | 2,070.00 | 726.00 |
| | | | | | | | |
| | | | | | IMPORT | 0 | CUBIC YARD |
| | | | | | EXPORT | 1,344 | CUBIC YARD |

[illegible]

LC ENGINEERING
598 E Santa Clara St #270
San Jose, CA 95112
Phone: (408) 806-7187

| | | | |
|-------------|--|------|--|
| DRAWING NO. | <div> <div>DRIVEWAY SECTIONS</div> <div>LANDS OF RAHN</div> <div>2355 ROCKWOOD RANCH ROAD</div> <div>APN 776-35-012</div> </div> | | CALIFORNIA |
| SHEET NO. | 4 | OF 5 | <div> <div>Morgan Hill</div> <div>CONTRACT NO.</div> <div>PROJECT NO.</div> </div> |
| FILE NO. | | | |



FILE NO.

5

of 5

SHEET NO.

PROJECT NO.

2355 ROCKWOOD RANCH ROAD

LANDS OF RAHN

DISTURBED AREAS

CONTRACT NO.

Morgan Hill

California

DATE

11/17/21

CHECKED

NL

SCALE

1" = 30'

DATE

11/17/21

BY

DATE

11/17/21


APPROVED

REVISIONS


NO.

ENGINEERING

598 E Santa Clara St #270
San Jose, CA 95112
Phone: (408) 806-7187



Concrete tanks must be used where possible. Alternative materials are approved on a site specific basis. The Department of Environmental Health maintains a list of approved septic tanks.




Two drainfields, each 100% of the total size required shall be installed and interconnected with an approved diversion valve. The valve must be capable of directing the septic tank effluent to one drainfield at a time.

Drainline pipes shall be of approved, perforated pipe at least 4 inches in diameter. The tightline from the septic tank to the diversion valve must be ABS or schedule 40 PVC joined with glue, cement or elastomeric seal to be water tight.


The drainline trench bottom must be level. They must be at least 24 inches wide and 3 to 8 feet deep. At least 18 inches of clean, washed drainrock must be placed beneath the drainpipe and filled around and over the pipe at least 2 inches. The rock must be covered with untreated building paper or filter fabric to prevent clogging the rock with earth prior to backfilling.

Illustration #3 shows typical drainline installations for level land and hillside or sloping land.
Illustration #3

DRAINFIELD SYSTEM ON LEVEL LAND




DRAINFIELD SYSTEM ON HILLSIDE OR SLOPING LAND (ONE SIDE)



SEPTIC SYSTEM CONSTRUCTION NOTES

1. SYSTEM TO SERVE A NEW 4 BEDROOM, 5,235 SF (LIVING AREA). INSTALLATION OF SYSTEM TO CONFORM TO SANTA CLARA COUNTY SEWAGE DISPOSAL ORDINANCE. CALL SANTA CLARA COUNTY DEPARTMENT OF ENVIRONMENTAL HEALTH 24 HOURS MIN. PRIOR TO START OF WORK (408) 918-3400.
2. SEWAGE DISPOSAL SYSTEM CONSISTS OF A NEW 2,000 GALLON CONCRETE SEPTIC TANK WITH WATERTIGHT ACCESS RISERS TO GRADE; A BULL-RUN DIVERSION VALVE, AND TWO 375 LF - 36" ROCK (EQUIVALENT TO 650'x650') OF LEACHFIELDS WITH INSPECTION RISERS TO GRADE.
3. GROUND SLOPE OF LEACHFIELD #1 & LEACH FIELD #2 ARE BETWEEN 13% AND 23%. LEACH FIELDS TO BE INSTALLED LEVEL AND ON CONTOURS AS SHOWN ON PLAN. EXCESS SPOIL FROM LEACHFIELD CONSTRUCTION SHALL BE SPREAD ON SITE AT A DEPTH OF 8" MAX OR BE REMOVED OFF-SITE.
4. THE SEPTIC TANK SHALL BE INSTALLED IN UNDISTURBED NATIVE SOIL.
5. THE DIVERSION VALVE SHALL BE OPERATED ANNUALLY TO ROTATE THE USE OF LEACHFIELDS TO EXTEND THE LIFE OF THE SEPTIC SYSTEM.
6. MARK CAPS OF ALL BULL RUN VALVES (DV) AND RISERS (R) WITH A PERMANENT MARKET OR LABEL.
7. SWIMMING POOLS OR SPAS MUST NOT BE DRAINED OR BACKWASHED INTO THE SEPTIC SYSTEM.
8. AVOID PLANTING TREES IN LEACHFIELD OR CLOSE TO SEPTIC TANK.
9. GARBAGE DISPOSAL IS NOT RECOMMENDED. IF THEY ARE INSTALLED, THEY SHOULD BE USED SPARINGLY OR NOT AT ALL.
10. THE SOLIDS THAT ACCUMULATE IN THE SEPTIC TANK SHOULD BE REMOVED BY PUMPING EVERY 3-5 YEARS TO PREVENT SOLIDS FROM ENTERING AND CLOGGING THE LEACHFIELDS.
11. ALL WORK IN TO BE PERFORMED BY AN APPROPRIATELY LICENSED CONTRACTOR.
12. PRIOR TO STARTING CONSTRUCTION, CONTRACTOR SHALL CONTACT USA AT 1-800-227-2600 TO LOCATE ALL UNDERGROUND UTILITIES.



SEWAGE SYSTEM REVIEW
SANTA CLARA COUNTY
DEPARTMENT OF ENVIRONMENTAL HEALTH
Project Description: *SFE 640004 of 4 B.R.*

APPROVAL RECOMMENDED

☐ With existing system


☒ Install/modify system per plan (describe below)

2000 gallon tank 650 + 650
375 + 375 w/ 36" rock

R.E.H.S. *Ana Bel* Date *12/12/12*

Not A Sewage System Permit

APPROVED FOR ISSUANCE.
REFER TO ENCROACHMENT AND/OR
CONSTRUCTION PERMIT AND PLAN
COVER SHEET FOR SPECIAL
CONDITIONS AND PERMIT NUMBERS



ENGINEERING

1291 Oakland Road
San Jose, CA 95128
Phone: (408) 806-7187
Fax: (408) 583-4006

SEPTIC SYSTEM PLAN
LANDS OF LEISCH
2355 ROCKWOOD RANCH ROAD
APN 776-35-07

California

Morgan Hill

DRAWING NO.

SHT NO. 1 OF 1

FILE NO.

CONTRACT NO.

PROJECT NO.

REVISIONS

NO.


APPLICANT : LEISCH

ROAD NAME : ROCKWOOD RANCH ROAD

COUNTY FILE NO :


3 Stabilized Construction Entrance/Exit

CASQA Detail TC-1



4 Velocity Dissipation Devices

CASQA Detail EC-10




* Length per ABAG Design Standards

Source for Graphics: California Stormwater BMP Handbook, California Stormwater Quality Association, January 2003. Available from www.cabmphandbooks.com.

1 Silt Fence

CASQA Detail SE-1




NOTES


- Construct the length of each reach so that the change in base elevation along the reach does not exceed 1/3 the height of the linear barrier. In no case shall the reach length exceed 500'.
- The last B'-0" of fence shall be turned up slope.
- Stake dimensions are nominal.
- Dimension may vary to fit field condition.
- Stakes shall be spaced at B'-0" maximum and shall be positioned on downstream side of fence.
- Stakes to overlap and fence fabric to fold around each stake one full turn. Secure fabric to stake with 4 staples.
- Stakes shall be driven tightly together to prevent potential flow-through of sediment at joint. The tops of the stakes shall be secured with wire.
- For end stake, fence fabric shall be folded around two stakes one full turn and secured with 4 staples.
- Minimum 4 staples per stake. Dimensions shown are typical.
- Cross barriers shall be a minimum of 1/3 and a maximum of 1/2 the height of the linear barrier.
- Maintenance openings shall be constructed in a manner to ensure sediment remains behind silt fence.
- Joining sections shall not be placed at sump locations.
- Sandbag rows and layers shall be offset to eliminate gaps.

2 Silt Fence


CASQA Detail SE-1




SECTION A-A



DETAIL A



END DETAIL



OPTIONAL MAINTENANCE OPENING DETAIL (SEE NOTE 11)

STANDARD BEST MANAGEMENT PRACTICE NOTES

- Solid and Demolition Waste Management:** Provide designated waste collection areas and containers on site away from streets, gutters, storm drains, and waterways, and arrange for regular disposal. Waste containers must be watertight and covered at all times except when waste is deposited. Refer to Erosion & Sediment Control Field Manual, 4th Edition (page C3) or latest.
- Hazardous Waste Management:** Provide proper handling and disposal of hazardous wastes by a licensed hazardous waste material hauler. Hazardous wastes shall be stored and properly labeled in sealed containers constructed of suitable materials. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-5 to C-6) or latest.
- Spill Prevention and Control:** Provide proper storage areas for liquid and solid materials, including chemicals and hazardous substances, away from streets, gutters, storm drains, and waterways. Spill control materials must be kept on site where readily accessible. Spills must be cleaned up immediately and contaminated soil disposed properly. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-7 to C-8, C-13 to C-14) or latest.
- Vehicle and Construction Equipment Service and Storage:** An area shall be designated for the maintenance, where on-site maintenance is required, and storage of equipment that is protected from stormwater run-on and runoff. Measures shall be provided to capture any waste oils, lubricants, or other potential pollutants and these wastes shall be properly disposed of off site. Fueling and major maintenance/repair, and washing shall be conducted off-site whenever feasible. Refer to Erosion & Sediment Control Field Manual, 4th Edition (page C9) or latest.
- Material Delivery, Handling and Storage:** In general, materials should not be stockpiled on site. Where temporary stockpiles are necessary and approved by the County, they shall be covered with secured plastic sheeting or tarp and located in designated areas near construction entrances and away from drainage paths and waterways. Barriers shall be provided around storage areas where materials are potentially in contact with runoff. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-11 to C-12) or latest.
- Handling and Disposal of Concrete and Cement:** When concrete trucks and equipment are washed on-site, concrete wastewater shall be contained in designated containers or in a temporary lined and watertight pit where wasted concrete can harden for later removal. If possible have concrete contractor remove concrete wash water from site. In no case shall fresh concrete be washed into the road right-of-way. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-15 to C-16) or latest.
- Pavement Construction Management:** Prevent or reduce the discharge of pollutants from paving operations, using measures to prevent run-on and runoff pollution and properly disposing of wastes. Avoid paving in the wet season and reschedule paving when rain is in the forecast. Residue from saw-cutting shall be vacuumed for proper disposal. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-17 to C-18) or latest.
- Contaminated Soil and Water Management:** Inspections to identify contaminated soils should occur prior to construction and at regular intervals during construction. Remediating contaminated soil should occur promptly after identification and be specific to the contaminant identified, which may include hazardous waste removal. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-19 to C-20) or latest.
- Sanitary/Septic Water Management:** Temporary sanitary facilities should be located away from drainage paths, waterways, and traffic areas. Only licensed sanitary and septic waste haulers should be used. Secondary containment should be provided for all sanitary facilities. Refer to Erosion & Sediment Control Field Manual, 4th Edition (page C-21) or latest.
- Inspection & Maintenance:** Areas of material and equipment storage sites and temporary sanitary facilities must be inspected weekly. Problem areas shall be identified and appropriate additional and/or alternative control measures implemented immediately, within 24 hours of the problem being identified.

STANDARD EROSION CONTROL NOTES

1. Sediment Control Management:

Tracking Prevention & Clean Up: Activities shall be organized and measures taken as needed to prevent or minimize tracking of soil onto the public street system. A gravel or proprietary device construction entrance/exit is required for all sites. Clean up of tracked material shall be provided by means of a street sweeper prior to an approaching rain event, or at least once at the end of each workday that material is tracked, or, more frequently as determined by the County Inspector. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages B-31 to B-33) or latest.

Storm Drain Inlet and Catch Basin Inlet Protection: All inlets within the vicinity of the project and within the project limits shall be protected with gravel bags placed around inlets or other inlet protection. At locations where exposed soils are present, staked fiber roles or staked silt fences can be used. Inlet filters are not allowed due to clogging and subsequent flooding. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages B-49 to B-51) or latest.

Storm Water Runoff: No storm water runoff shall be allowed to drain in to the existing and/or proposed underground storm drain system or other above ground watercourses until appropriate erosion control measures are fully installed.

Dust Control: The contractor shall provide dust control in graded areas as required by providing wet suppression or chemical stabilization of exposed soils, providing for rapid clean up of sediments deposited on paved roads, furnishing construction road entrances and vehicle wash down areas, and limiting the amount of areas disturbed by clearing and earth moving operations by scheduling these activities in phases.

Stockpiling: Excavated soils shall not be placed in streets or on paved areas. Borrow and temporary stockpiles shall be protected with appropriate erosion control measures (tarps, straw bales, silt fences, etc.) to ensure silt does not leave the site or enter the storm drain system or neighboring watercourse.

- Erosion Control:** During the rainy season, all disturbed areas must include an effective combination of erosion and sediment control. It is required that temporary erosion control measures are applied to all disturbed soil areas prior to a rain event. During the non-rainy season, erosion control measures must be applied sufficient to control wind erosion at the site.
- Inspection & Maintenance:** Disturbed areas of the Project's site, locations where vehicles enter or exit the site, and all erosion and sediment controls that are identified as part of the Erosion Control Plans must be inspected by the Contractor before, during, and after storm events, and at least weekly during seasonal wet periods. Problem areas shall be identified and appropriate additional and/or alternative control measures implemented immediately, within 24 hours of the problem being identified.
- Project Completion:** Prior to project completion and signoff by the County Inspector, all disturbed areas shall be reseeded, planted, or landscaped to minimize the potential for erosion on the subject site.
- It shall be the Owner's/Contractor's responsibility to maintain control of the entire construction operation and to keep the entire site in compliance with the erosion control plan.
- Erosion and sediment control best management practices shall be operable year round or until vegetation is fully established on landscaped surfaces.

Project Information

NO./ DATE/ REVISION

THESE PLANS ARE INTENDED ONLY FOR THE ORIGINAL SITE FOR WHICH THEY WERE DESIGNED AND ARE THE PROPERTY OF DMZ. NO PART OF THESE PLANS SHALL BE REPRODUCED OR COPIED IN ANY MANNER WITHOUT THE WRITTEN CONSENT OF DMZ. ANY REUSE OF THESE PLANS ON OTHER SITES IS PROHIBITED WITHOUT THE CONSENT OF DMZ. DMZ SHALL BE RESPONSIBLE FOR THE DESIGN OF THE EROSION CONTROL MEASURES AND THE DESIGN ASSOCIATES SHALL TAKE PRECEDENCE OVER SCALED DIMENSIONS.

Design Associates, Inc.
A California Corporation
18646 Sutter Blvd., Suite 500
Morgan Hill, California 95037
Phone: (408) 778-7045 Fax: (408) 778-7004
Email: info@designassoc.com

DRAWING TITLE BMP 1/Erosion Control Details
JOB TITLE Rahn Residence
JOB ADDRESS 2355 Rockwood Ranch Road
Morgan Hill, California

DATE JAN. 24, 2021
SCALE NONE
PROJECT MANAGER T. DAVIS
DRAWN DZ
JOB NO. DZ3521
SHEET









A1.2

Best Management Practices and Erosion Control Details Sheet 1
County of Santa Clara



BMP-1

D:\design\21 3\12022 417 PM Z\projects\2021\ids3521-Rahn\Architectural\Design\23521-A1.3.dwg



Project Information

Source for Graphics: California Stormwater BMP Handbook, California Stormwater Quality Association, January 2003.
Available from www.cabmphandbooks.com.

Best Management Practices and Erosion Control Details Sheet 2 County of Santa Clara



BMP-2

| NO./ DATE/ REVISION |
|---------------------|
| |
| |
| |
| |
| |
| |
| |

THESE PLANS ARE INTENDED ONLY FOR THE ORIGINAL SITE FOR WHICH THEY WERE DESIGNED AND ARE THE PROPERTY OF DAZ. NO PART OF THESE PLANS MAY BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, WITHOUT THE WRITTEN PERMISSION OF DAZ. ANY REUSE OF THESE PLANS ON OTHER SITES IS PROHIBITED WITHOUT THE CONSENT OF DAZ. DAZ ASSOCIATES, INC. SHALL BE RESPONSIBLE FOR THE DESIGN AND CONSTRUCTION OF THE BMP'S AND SHALL BE RESPONSIBLE FOR THE MAINTENANCE OF THE BMP'S. DAZ ASSOCIATES, INC. SHALL BE RESPONSIBLE FOR THE MAINTENANCE OF THE BMP'S. DAZ ASSOCIATES, INC. SHALL BE RESPONSIBLE FOR THE MAINTENANCE OF THE BMP'S.




| | |
|---------------|---|
| DRAWING TITLE | BMP 2/Erosion Control Details |
| JOB TITLE | Rahn Residence |
| JOB ADDRESS | 2355 Rockwood Ranch Road Morgan Hill, California |

| | |
|-----------------|---------------|
| DATE | JAN. 24, 2021 |
| SCALE | NONE |
| PROJECT MANAGER | DAVIS |
| DRAWN | DZ |
| JOB NO. | D23521 |
| SHEET | |

A1.3


D:\design\24_3\2023\403 PM Z:\projects\2021\1023521-Rahn\Architectural\Design\23521-A2.1.dwg



Entry Level Floor Plan

4084 sq. ft. Entry Level Living Area
784 sq. ft. Lower Level Living Area
4868 sq. ft. Total Living Area
946 sq. ft. Garage
400 sq. ft. Unconditioned Storage
107 sq. ft. Covered Entry Porch
6321 sq. ft. Total Gross Area

scale: 3/16" = 1'-0"



NO./ DATE/ REVISION


THESE PLANS ARE INTENDED ONLY FOR THE ORIGINAL SITE FOR WHICH THEY WERE DESIGNED AND ARE THE PROPERTY OF DAZ. NO PART OF THESE PLANS MAY BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN PERMISSION OF DAZ. NO OTHER SITES ARE TO BE CONSIDERED FOR CONSTRUCTION WITHOUT THE WRITTEN PERMISSION OF DAZ. DESIGN ASSOCIATES SHALL BE RESPONSIBLE FOR THE ATTENTION OF THE CLIENT AND THE ASSOCIATES PRIOR TO COMMENCEMENT OF THE PROJECT. ANY CHANGES SHALL BE MADE IN WRITING AND SHALL BE PRECEDENCE OVER SCALED DIMENSIONS.

DZ Design Associates, Inc.
A California Corporation
18446 Sutter Blvd., Suite 500
Morgan Hill, California 95037
Phone: (408) 778-7045 Fax: (408) 778-7004
Email: dzdesign@barracuda.com

Entry Level Floor Plan
Rahn Residence
2355 Rockwood Ranch Road
Morgan Hill, California

DATE: JAN. 24, 2021
SCALE: 3/16" = 1'-0"
PROJECT MANAGER: T. DAVIS
DRAWN: DES
JOB NO.: DZ3521
SHEET


A2.1



Lower Level Floor Plan

784 sq. ft. Lower Level Living Area
400 sq. ft. Unconditioned Stg. Area

scale: 3/16"=1'-0"



| NO./ DATE/ REVISION |
|---------------------|
| |
| |
| |
| |
| |
| |


THESE PLANS ARE INTENDED ONLY FOR THE ORIGINAL SITE FOR WHICH THEY WERE PREPARED. ANY REUSE OF THESE PLANS FOR ANY OTHER PROJECT OR AT ANY OTHER LOCATION WITHOUT THE WRITTEN CONSENT OF DAZ DESIGN ASSOCIATES, INC. IS PROHIBITED. THESE PLANS ARE THE PROPERTY OF DAZ DESIGN ASSOCIATES, INC. AND ARE NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM. ANY UNAUTHORIZED REUSE OF THESE PLANS IS PROHIBITED WITHOUT THE WRITTEN CONSENT OF DAZ DESIGN ASSOCIATES, INC. ANY USE OF THESE PLANS ON OTHER SITES IS PROHIBITED WITHOUT THE WRITTEN CONSENT OF DAZ DESIGN ASSOCIATES, INC. ANY USE OF THESE PLANS ON OTHER SITES SHALL BE BROUGHT TO THE ATTENTION OF DAZ DESIGN ASSOCIATES, INC. PRIOR TO COMMENCEMENT OF THE PROJECT. DAZ DESIGN ASSOCIATES, INC. SHALL TAKE PRECEDENCE OVER SCALED DIMENSIONS.



DAZ Design Associates, Inc.
A California Corporation
18646 Sutter Blvd., Suite 500
Morgan Hill, California 95037
Phone: (408) 778-7045 Fax: (408) 778-7064
email: dazdesign@gahc.com


| | |
|---------------|---|
| DRAWING TITLE | Lower Level Floor Plan |
| JOB TITLE | Rahn Residence |
| JOB ADDRESS | 2355 Rockwood Ranch Road Morgan Hill, California |

| | |
|-----------------|---------------|
| DATE | JAN. 24, 2021 |
| SCALE | 3/16" = 1'-0" |
| PROJECT MANAGER | M. DAVIS |
| DRAWN | DEB |
| JOB NO. | DZ3521 |
| SHEET | |




Entry Level

scale: 1/8"=1'-0"



Lower Level


scale: 1/8"=1'-0"



| Entry Level | | | |
|-------------|--------------------|--------|------------------------------|
| a1 | 7'-6" x 16'-6" | 124.0 | s.f. |
| b1 | 56'-0" x 24'-6" | 1372.0 | s.f. |
| c1 | 17'-6" x 16'-6" | 289.0 | s.f. |
| d1 | 26'-0" x 18'-0" | 468.0 | s.f. |
| f1 | 13'-0" x 2'-0" | 26.0 | s.f. |
| g1 | 8'-0" x 2'-0" | 16.0 | s.f. |
| h1 | 31'-6" x 18'-0" | 567.0 | s.f. |
| i1 | 10'-0" x 12'-6" | 125.0 | s.f. |
| j1 | 13'-0" x 2'-0" | 26.0 | s.f. |
| k1 | 12'-0" x 27'-6" | 330.0 | s.f. |
| l1 | shape | 47.5 | s.f. |
| m1 | 2'-0" x 11'-0" | 22.0 | s.f. |
| n1 | 21'-6" x 29'-6" | 634.0 | s.f. |
| o1 | 12'-6" x 3'-0" | 37.5 | s.f. |
| ➡ | total living: | 4084.0 | s.f. |
| | | | |
| p1 | 32'-6" x 24'-0" | 780.0 | s.f. (garage) |
| q1 | shape | 166.0 | s.f. (garage) |
| e1 | shape | 107.0 | s.f. (porch) |
| | total non-living: | 1053.0 | s.f. |
| | | | |
| Lower Level | | | |
| a2 | 28'-4" x 18"-10" | 532.0 | s.f. |
| b2 | 12'-6" x 20'-0" | 252.0 | s.f. |
| ➡ | total living: | 784.0 | s.f. |
| | | | |
| c2 | 15'-6" x 8'-0" | 124.0 | s.f. (unconditioned storage) |
| d2 | 23'-0" x 12'-0" | 276.0 | s.f. (unconditioned storage) |
| | total non-living: | 400.0 | s.f. |
| | | | |
| ➡ | Total Living Area: | 4868.0 | s.f. |

[illegible]

THESE PLANS ARE INTENDED ONLY FOR THE ORIGINAL SITE FOR WHICH THEY WERE PREPARED. ANY REUSE OF THESE PLANS BY DESIGN ASSOCIATES, THESE PLANS ARE PROTECTED UNDER COPYRIGHT LAWS AND MAY NOT BE REPRODUCED OR REPRODUCED IN ANY MANNER WITHOUT THE WRITTEN CONSENT OF D&Z DESIGN ASSOCIATES, ANY USE OF THESE PLANS ON OTHER SITES IS PROHIBITED WITHOUT THE CONSENT OF D&Z DESIGN ASSOCIATES. ANY REUSE OF THESE PLANS ON THESE PLANS SHALL BE BROUGHT TO THE ATTENTION OF D&Z DESIGN ASSOCIATES IMMEDIATELY UPON DISCOVERY OF THE WORK IN QUESTION. ALL WRITTEN DIMENSIONS SHALL TAKE PRECEDENCE OVER SCALED DIMENSIONS.




DZ Design Associates, Inc.
A California Corporation
18640 Sutter Blvd., Suite 500
Morgan Hill, California 95037
Phone: (408) 778-7005; Fax: (408) 778-7004;
e-mail: dzdesign@gentle.com


| | |
|---------------|---|
| DRAWING TITLE | Floor Area Diagrams |
| JOB TITLE | Rahn Residence |
| JOB ADDRESS | 2355 Rockwood Ranch Road Morgan Hill, California |

| | |
|-----------------|----------------|
| DATE | JAN. 24, 2021 |
| SCALE | 1/8" = 1' - 0" |
| PROJECT MANAGER | M. DAVIS |
| DRAWN | MB |
| JOB NO. | DZ3521 |
| SHEET | A2.3 |

D:\design\24-411\2023-728-AM-Z\drawings\2021\243521-Rahn\Architectural\Design\243521-44.dwg



A Cross Section



B Cross Section

| NO./ DATE/ REVISION |
|---------------------|
| |
| |
| |
| |
| |
| |
| |
| |
| |

THESE PLANS ARE INTENDED ONLY FOR THE ORIGINAL SITE FOR WHICH THEY WERE DESIGNED AND ARE THE PROPERTY OF DAZ WHICH THEY WERE DESIGNED AND ARE THE PROPERTY OF DAZ. NO PART OF THESE PLANS MAY BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN PERMISSION OF DAZ. ANY REUSE OR MODIFICATION OF THESE PLANS ON OTHER SITES IS PROHIBITED WITHOUT THE CONSENT OF DAZ. DAZ ASSUMES NO LIABILITY FOR THE ACCURACY OF THE INFORMATION PROVIDED HEREON, AND THE USER SHALL BE RESPONSIBLE FOR THE ACCURACY OF THE INFORMATION PROVIDED HEREON. THE USER SHALL TAKE PRECEDENCE OVER SCALED DIMENSIONS.



| DRAWING TITLE |
|---|
| Cross Sections |
| JOB TITLE |
| Rahn Residence |
| JOB ADDRESS |
| 2355 Rockwood Ranch Road Morgan Hill, California |

| DATE |
|-----------------|
| JAN. 24, 2021 |
| SCALE |
| 1/4" = 1'-0" |
| PROJECT MANAGER |
| M. DAVIS |
| DRAWN |
| MB |
| JOB NO. |
| DZ3521 |
| SHEET |

A4





Design Associates, Inc.
A California Corporation
18640 Sutter Blvd., Suite 500
Morgan Hill, California 95037
Phone: (408) 778-7005, Fax: (408) 778-7004
email: cdesign@geartek.com

| | |
|-----------------|---------------|
| DATE | JAN. 24, 2021 |
| SCALE | 3/16" = 1'-0" |
| PROJECT MANAGER | M. DAVIS |
| DRAWN | DEB |
| JOB NO. | DZ3521 |
| SHEET | |

Page 10 of 10







SOIL PREPARATION, MULCH AND AMENDMENTS

THE FOLLOWING CRITERIA SHALL BE USED IN THE PREPARATION OF ON-SITE SOILS AND FOR MULCHING PROCEDURES:

A) PRIOR TO THE PLANTING OF ANY MATERIALS, COMPACTED SOILS SHALL BE TRANSFORMED TO A FRIABLE CONDITION. ON ENGINEERED SLOPES, ONLY AMENDED PLANTING HOLES NEED MEET THIS REQUIREMENT;

B) SOIL AMENDMENTS SHALL BE INCORPORATED ACCORDING TO RECOMMENDATIONS OF THE SOIL REPORT AND WHAT IS APPROPRIATE FOR THE PLANTS SELECTED;

C) FOR LANDSCAPE INSTALLATIONS, COMPOST AT A RATE OF A MINIMUM OF FOUR CUBIC YARDS PER 1,000 SQUARE FEET OF PERMEABLE AREA SHALL BE INCORPORATED TO A DEPTH OF SIX INCHES INTO THE SOILS WITH GREATER THAN 6% ORGANIC MATTER IN THE TOP 6 INCHES OF SOIL ARE EXEMPT FROM ADDING COMPOST AND TILLING;

D) A MINIMUM 3 INCH (3") LAYER OF BARK MULCH SHALL BE APPLIED ON ALL EXPOSED SOIL SURFACES OF PLANTING AREAS EXCEPT IN TURF AREAS, CREEPING OR ROOTING GROUNDCOVERS, OR DIRECT SEEDING APPLICATIONS WHERE MULCH IS CONTRAINDICATED. TO PROVIDE HABITAT FOR BENEFICIAL INSECTS AND OTHER WILDLIFE, UP TO 5 % OF THE LANDSCAPE AREA MAY BE LEFT WITHOUT MULCH. DESIGNATED INSECT HABITAT MUST BE INCLUDED IN THE LANDSCAPE DESIGN PLAN AS SUCH;

E) STABILIZING MULCHING PRODUCTS SHALL BE USED ON SLOPES THAT MEET CURRENT ENGINEERING STANDARDS;

F) THE MULCHING PORTION OF THE SEED/MULCH SLURRY IN HYDRO-SEEDED APPLICATIONS SHALL MEET THE MULCHING REQUIREMENT;

G) ORGANIC MULCH MATERIALS MADE FROM RECYCLED OR POST-CONSUMER SHALL TAKE PRECEDENCE OVER INORGANIC MATERIALS OR VIRGIN FOREST PRODUCTS UNLESS THE RECYCLED POST-CONSUMER ORGANIC PRODUCTS ARE NOT LOCALLY AVAILABLE. ORGANIC MULCHES ARE NOT REQUIRED WHERE PROHIBITED BY LOCAL FUEL MODIFICATION PLAN GUIDELINES OR OTHER APPLICABLE LOCAL ORDINANCES.

IRRIGATION NOTES

1. THE IRRIGATION SYSTEM IS TO BE INSTALLED IN CONFORMANCE WITH ALL LOCAL CODES.

2. THIS IRRIGATION DESIGN IS DIAGRAMMATIC IN NATURE AND DOES NOT REPRESENT AN EXACT LAYOUT. THE CONTRACTOR SHALL MAKE MINOR ADJUSTMENTS IN HEAD, VALVE, AND PIPING LAYOUT. FOR GRAPHIC CLARITY, PIPING MAY BE SHOWN OUTSIDE OF PLANTING AREAS BUT SHOULD BE INSTALLED IN BEDS WHENEVER POSSIBLE.

3. REMOTE CONTROL VALVES SHALL BE INSTALLED FLUSH WITH FINISH GRADE AND SHOULD BE INSTALLED IN PLANTING AREAS ONLY. USE EXISTING VALVE BOXES WHEN POSSIBLE.

4. WHERE PIPE PASSES UNDER DRIVING SURFACES, AND WALKS PROVIDE PVC SLEEVES AS NOTED ON PLANS. CONTRACTOR TO USE EXISTING SLEEVING WHEN POSSIBLE AND IS TO LOCATE ON SITE.

5. CONTRACTOR TO CONFIRM THE LOCATION OF ALL EXISTING UTILITIES AND UNDERGROUND STRUCTURES PRIOR TO EXCAVATION OF TRENCHES. CONTRACTOR TO REPAIR ANY DAMAGES CAUSED BY, OR DURING THE PERFORMANCE OF HIS WORK AT NO EXTRA COST TO THE OWNER.

"I have complied with the criteria of the ordinance and applied them for the efficient use of water in the landscape and irrigation design plan."

"I agree to comply with the requirements of the water efficient landscape ordinance and submit a complete Landscape Documentation Package."

* NOTE: Refer to L-3 & L-4 for Water Calcs. & Irrigation Details

| IRRIGATION KEY | |
|----------------|---|
| | Hunter ICZ-101-25-LF Drip Control Zone Kit. 1" ICV Globe Valve with 1" HY100 filter system. Pressure Regulation: 25psi. Flow Range: .5-15 GPM. 150 mesh stainless steel screen. |
| | Area to Receive Dripline HDL-06-12-CV: Hunter Dripline w/ 0.6 GPH emitters at 12" O.C. Check valve, dark brown tubing with gray striping. Dripline laterals spaced at 12" apart, with emitters offset for triangular pattern. Install with Hunter PLD barbed or PLD-LOC fittings. |
| | Tree Ring Irrigation Dripline w/ 0.9 drip emitters placed every 12 in. Inner ring 12" from plant. Outer ring 30" from plant. Place tie down every 4' in loam and 5' in clay. |
| | Shut Off Valve |
| | Hunter ICV-G-BSP 1-1/2" 1", 1-1/2", 2", and 3" Plastic Electric Master Valve, Globe Configuration, with BSP Threaded Inlet/Outlet, for Commercial/Municipal Use. |
| | FEBCO 825Y 1-1/2" Reduced Pressure Backflow Preventer |
| | Hunter ACC-1200 12 Station Outdoor Modular Controller. No Module Required. High-End Commercial Use. Metal Cabinet. |
| | Hunter SOIL-CLIK The Soil-Clík probe uses proven technology to measure moisture within the root zone. When the probe senses that the soil has reached its desired moisture level, it will shut down irrigation, preventing water waste. |
| | Hunter Solar-Sync Solar, rain freeze sensor with outdoor interface, connects to Hunter PCC, Pro-C, and I-Core Controllers, install as noted. Includes 10 year lithium battery and rubber module cover, and gutter mount bracket. Wired. |
| | Hunter HFS-150 Flow Sensor for use with ACC controller, 1-1/2" Schedule 40 Sensor Body, 24 VAC, 2 amp. |
| | Water Meter 1-1/2" NEW IRRIGATION WATER METER |
| | Irrigation Lateral Line: PVC Schedule 40 |
| | Irrigation Mainline: PVC Schedule 40 |
| | Pipe Sleeve: PVC Class 200 Typical pipe sleeve for irrigation pipe. Pipe sleeve size shall allow for irrigation piping and their related couplings to easily slide through sleeving material. Extend sleeves 18 inches beyond edges of paving or construction. |

REVISIONS

BY

KAREN AITKEN & ASSOCIATES

LANDSCAPE ARCHITECTS

8262 Rancho Real Giltroy Ca. 95020

Calif. Reg. #2239 (408) 842-0245

karen@kaa.design

RAHN RESIDENCE

2355 Rockwood Ranch Rd., Morgan Hill, CA

IRRIGATION PLAN

LI CENSED LANDSCAPE ARCHITECT

KAREN JONES AITKEN

No. 2239

Exp. 8-31-23

STATE OF CALIFORNIA

DATE 09-09-22








SCALE 1"=10'-0"

DRAWN EM

JOB RAHN

L-2

* NOTES (E) = Existing



MAWA EPPT and ETWU Calculations

Project Name: Santiago Res.

Project Location: 282 Gunnera Ct., Gilroy, CA.

Total Landscape Area: 10,119.0 sq. ft.

Date: 09-09-22

MAWA CALCULATION

$$MAWA = (Eto) \cdot (.62) [(0.55 \times LA) + (1 - ETAF \times SLA)]$$

MAWA = Maximum Applied Water Allowance (gallons per year)

Eto = Reference Evapotranspiration (inches per year)

.62 = Conversion Factor (to gallons)

0.55 = Et Adjustment Factor (ETAF)

LA = Landscape Area including SLA (square feet)

0.45 = Additional Water Allowance for SLA

SLA = Special Landscape Area (square feet)

| | | | |
|------------|-----------|---------------------|--|
| Eto = | 43.6 | | |
| Conversion | 0.62 | | |
| ETAF | 0.55 | | |
| LA = | 10,119 | | |
| SLA = | 0 | | |
| MAWA = | 150,445.2 | gallons per year | |
| | 20,113.0 | cubic feet per year | |

MAWA with EPPT

$$MAWA = (Eto - Eppt) \cdot (.62) [(0.55 \times LA) + (1 - ETAF \times SLA)]$$

Eppt = 25% of Annual precipitation

| | | | |
|----------------|-----------|------------------|--|
| Eto = | 43.6 | | |
| Eppt = | 9.82 | | |
| ETAF = | 0.55 | | |
| LA = | 10,119 | | |
| SLA = | 0 | | |
| MAWA w/ EPPT = | 116,581.5 | gallons per year | |
| | 15,585.8 | cubic feet | |

ETWU CALCULATION

$$ETWU = (Eto) \cdot (.62) [(PF) \cdot (IE) \cdot (LA)]$$

ETWU = Estimated Total Water Use Per Year (gallons)

Eto = Reference Evapotranspiration

PF = Plant Factor from WUCOLS (Region 2, Water Use: H 0.7 - 0.9, M 0.4 - 0.6, L 0.1 - 0.3, VL < 0.1, All Turf 0.8)

LA = Landscape Area (High, Medium, and low water use areas) (square feet)

SLA = Special Landscape Area

.62 = Conversion Factor

IE = Irrigation Efficiency (drip spray and bubblers .81, sub surface .81, spray sprinklers .75)

ET Adjustment Factor (ETAF) .55 for Residential and .45 for Non Residential

| | | |
|------------------------------------|------|-------------|
| Reference Evapotranspiration (Eto) | 43.6 | Gilroy, CA. |
|------------------------------------|------|-------------|

REGULAR LANDSCAPE AREAS

| Hydrozone #/ Plant Description | Irrigation Method | Plant Factor (PF) | Irrigation Efficiency (IE) | ETAF (PF/IE) | Landscape Area (sq. ft) | ETAF x Area | ETWU |
|--------------------------------|-------------------|-------------------|----------------------------|-------------------|-------------------------|----------------|-----------------|
| 1.) Low Water Use - Shrubs | Drip | 0.2 | 0.81 | 0.246913580246914 | 728.0 | 179.8 | 4,859.1 |
| 2.) Low Water Use - Shrubs | Drip | 0.2 | 0.81 | 0.246913580246914 | 998.0 | 246.4 | 6,661.2 |
| 3.) Low Water Use - Shrubs | Drip | 0.2 | 0.81 | 0.246913580246914 | 824.0 | 203.5 | 5,499.8 |
| 4.) Med Water Use - Trees | Drip | 0.4 | 0.81 | 0.493827160493827 | 392.0 | 193.6 | 5,232.9 |
| 5.) Low Water Use - Shrubs | Drip | 0.2 | 0.81 | 0.246913580246914 | 976.0 | 241.0 | 6,514.4 |
| 6.) Low Water Use - Shrubs | Drip | 0.2 | 0.81 | 0.246913580246914 | 920.0 | 227.2 | 6,140.6 |
| 7.) Low Water Use - Shrubs | Drip | 0.2 | 0.81 | 0.246913580246914 | 970.0 | 239.5 | 6,474.3 |
| 8.) Low Water Use - Shrubs | Drip | 0.2 | 0.81 | 0.246913580246914 | 368.0 | 90.9 | 2,456.2 |
| 9.) Low Water Use - Shrubs | Drip | 0.2 | 0.81 | 0.246913580246914 | 495.0 | 122.2 | 3,303.9 |
| 10.) Low Water Use - Shrubs | Drip | 0.2 | 0.81 | 0.246913580246914 | 930.0 | 229.6 | 6,207.3 |
| 11.) Low Water Use - Shrubs | Drip | 0.2 | 0.81 | 0.246913580246914 | 832.0 | 205.4 | 5,553.2 |
| 12.) Med Water Use - Trees | Drip | 0.4 | 0.81 | 0.493827160493827 | 140.0 | 69.1 | 1,888.9 |
| 13.) Low Water Use - Shrubs | Drip | 0.2 | 0.81 | 0.246913580246914 | 650.0 | 160.5 | 4,338.5 |
| 14.) Low Water Use - Shrubs | Drip | 0.2 | 0.81 | 0.246913580246914 | 494.0 | 122.0 | 3,297.2 |
| 15.) Low Water Use - Shrubs | Drip | 0.2 | 0.81 | 0.246913580246914 | 402.0 | 99.3 | 2,683.2 |
| Total sf ft. | | | | | 10,119.0 | Totals 2,629.9 | Totals 71,090.8 |

SPECIAL LANDSCAPE AREAS

| Hydrozone #/ Plant Description | Irrigation Method | Plant Factor (PF) | Irrigation Efficiency (IE) | ETAF (PF/IE) | Landscape Area (sq. ft) | ETAF x Area | ETWU |
|--------------------------------|-------------------|-------------------|----------------------------|--------------|-------------------------|---------------------|------|
| | | | | 1 | 0 | 0 | 0.0 |
| Totals | | | | | 0 | 0 | 0.0 |
| | | | | | | ETWU TOTAL 71,090.8 | |
| | | | | | | MAWA 150,445.2 | |

ETAF CALCULATIONS

Regular Landscape Areas

| | |
|-------------------|----------|
| Total ETAF x Area | 2,629.9 |
| Total Area | 10,119.0 |
| Average ETAF | 0.26 |

Special Landscape Areas

| | |
|-------------------|----------|
| Total ETAF x Area | 2,629.9 |
| Total Area | 10,119.0 |
| Sitewide ETAF | 0.26 |

Average ETAF for Regular Landscape Areas must be .55 or below for residential areas, and .45 or below for non residential areas.

REVISIONS BY



KAREN AITKEN & ASSOCIATES
LANDSCAPE ARCHITECTS

8262 Rancho Real Gilroy Ca. 95020
Calif. Reg. #2239 (408) 842-0245
karen@kaa.design

RAHN RESIDENCE
2355 Rockwood Ranch Rd., Morgan Hill, CA

IRRIGATION DETAILS




DATE 09-09-22

SCALE


DRAWN EM

JOB RAHN



L-3


$$1/2'' = 1'-0''$$

328409.76-07


$$1^0 = 1^1 - 0$$

FX-IR-FX-BACK-02



| | | | |
|---|--|---|--|
| 1 | 'CINCH-TIE' TREE TIE - WRAP WIRE AROUND OUTSIDE OF STAKE. SECURE TO STAKE PER MANUFACTURER'S RECOMMENDATIONS, PLACE BELOW BRANCHING YOKE OF TREE | 5 | WATER BASIN (SHRUB AREAS ONLY) |
| 2 | LODGE POLE PINE STAKES, 3 POLES FOR 36" DIAM IN TRIANGLE ARRANGEMENT | 6 | BACKFILL MIX- 1/3 SITE SOIL, 1/3 SAND, 1/3 GROW MULCH |
| 3 | SET TOP OF ROOTBALL 2" ABOVE FINISH GRADE. | 7 | PLANTING FERTILIZER TABLETS (SEE DETAIL/CHART ON THIS SHEET) APPLICATION RATES PER MANUFACTURER SPECIFICATIONS OR SOILS REPORT RECOMMENDATIONS |
| 4 | 2" SHREDDED BARK MULCH, (APPROX. 3" DIA. RING) | 8 | NATIVE SOIL SUBGRADE EXCAVATE TO CORRECT HEIGHT FOR PLANTING, SCARIFY BOTTOM TO ENSURE ADEQUATE DRAINAGE FOR HEALTHY GROWTH OF PLANT. |