# COUNTY OF SANTA CLARA General Construction Specifications

#### GENERAL CONDITIONS

- ALL CONSTRUCTION WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE SOILS REPORT PREPARED BY AECOM USING NRCS WEB SOIL SURVEY AND DATED 3/21/2024. THIS REPORT IS SUPPLEMENTED BY: 1) THESE PLANS AND SPECIFICATIONS, 2) THE COUNTY OF SANTA CLARA STANDARD DETAILS. 3) THE COUNTY OF SANTA CLARA STANDARD SPECS, 4) STATE OF CALIFORNIA STANDARD DETAILS, 5) STATE OF CALIFORNIA STANDARD SPECIFICATIONS, IN THE EVENT OF CONFLICT THE FORMER SHALL TAKE PRECEDENCE OVER THE LATTER. THE PERFORMANCE AND COMPLETION OF ALL WORK MUST BE TO THE
- SATISFACTION OF THE COUNTY. DEVELOPER IS RESPONSIBLE FOR INSTALLATION OF THE IMPROVEMENTS SHOWN ON THESE PLANS AND HE OR HIS SUCCESSOR PROPERTY OWNERS ARE RESPONSIBLE FOR THEIR CONTINUED MAINTENANCE.
- DEVELOPER SHALL BE RESPONSIBLE FOR CORRECTION OF ANY ERRORS OR OMISSIONS IN THESE PLANS. THE COUNTY SHALL BE AUTHORIZED TO REQUIRE DISCONTINUANCE OF ANY WORK AND SUCH CORRECTION AND MODIFICATION OF PLANS AS MAY BE NECESSARY TO COMPLY WITH COUNTY STANDARDS OR CONDITIONS OF DEVELOPMENT APPROVAL
- DEVELOPER SHALL OBTAIN ENCROACHMENT PERMITS FROM THE SANTA CLARA VALLEY WATER DISTRICT AND CALIFORNIA DEPARTMENT OF TRANSPORTATION WHERE NEEDED. COPIES OF THESE PERMITS SHALL BE KEPT AT THE JOB SITE FOR REVIEW BY THE COUNTY'S INSPECTOR. DEVELOPER SHALL REMOVE OR TRIM ALL TREES TO PROVIDE AN
- UNOBSTRUCTED FIFTEEN (15) FOOT VERTICAL CLEARANCE FOR ROADWAY AREA.
- THIS PLAN AUTHORIZES THE REMOVAL OF ONLY THOSE TREES WITH TRUNK DIAMETERS GREATER THAN 12 INCHES MEASURED 4.5 FEET ABOVE THE GROUND THAT ARE SHOWN TO BE REMOVED UNLESS AN AMENDED PLAN IS APPROVED OR A SEPARATE TREE REMOVAL PERMIT IS OBTAINED FROM THE PLANNING OFFICE, IT IS THE CONTRACTOR'S RESPONSIBILITY TO ENSURE THAT REMOVAL OF ADDITIONAL TREES HAS BEEN PERMITTED. DEVELOPER SHALL PROVIDE ADEQUATE DUST CONTROL AS REQUIRED BY THE
- COUNTY INSPECTOR ALL PERSONS MUST COMPLY WITH SECTION 4442 OF THE PUBLIC RESOURCES CODE AND SECTION 13005 OF THE HEALTH AND SAFETY CODE RELATING TO
- THE USE OF SPARK ARRESTERS. UPON DISCOVERING OR UNEARTHING ANY BURIAL SITE AS EVIDENCED BY HUMAN SKELETAL REMAINS OR ARTIFACTS, THE PERSON MAKING SUCH DISCOVERY SHALL IMMEDIATELY NOTIFY THE COUNTY CORONER AT (4008) 454-2520 AND LAND DEVELOPMENT ENGINEERING OFFICE AT (408) 299-5730. NO FURTHER DISTURBANCE OF THE SITE MAY BE MADE EXCEPT AS AUTHORIZED BY THE LAND DEVELOPMENT OFFICE IN ACCORD WITH PROVISIONS
- OF THIS ORDINANCE (COUNTY ORDINANCE CODE SECTION B6-18). THESE PLANS ARE FOR THE WORK DESCRIBED IN THE SCOPE OF WORK ONLY. A SEPARATE PERMIT WILL BE REQUIRED FOR THE SEPTIC LINE CONSTRUCTION. ANY DEVIATION FROM THESE APPROVED PLANS SHALL BE RE-APPROVED IN
- WRITING BY THE COUNTY ENGINEER PRIOR TO CONSTRUCTION.

#### CONSTRUCTION STAKING

- THE DEVELOPER'S ENGINEER IS RESPONSIBLE FOR THE INITIAL PLACEMENT AND REPLACEMENT OF CONSTRUCTION GRADE STAKES. THE STAKES ARE TO BE ADEQUATELY IDENTIFIED, LOCATED, STABILIZED, ETC. FOR THE CONVENIENCE OF CONTRACTORS. LATERAL OFFSET OF STAKES SET FOR CURBS AND
- GUTTERS SHALL NOT EXCEED 2 1/2 FEET FROM BACK OF CURB. ANY PROPERTY LINE STAKES OR ROAD MONUMENTS DISTURBED DURING
- CONSTRUCTION SHALL BE REPLACED BY DEVELOPER'S ENGINEER AND LICENSED LAND SURVEYOR PROPERTY LINE STAKING MUST BE PERFORMED BY THE PROJECT ENGINEER OR LAND SURVEYOR TO ESTABLISH OR RE-ESTABLISH THE PROJECT BOUNDARY
- AND SHALL BE INSPECTED BY THE COUNTY INSPECTOR PRIOR TO THE BEGINNING OF THE WORK PROPER CONSTRUCTION STAKES SHALL BE SET IN THE FIELD BY THE PROJECT
- ENGINEER OR LAND SURVEYOR AND VERIFIED BY THE COUNTY INSPECTOR PRIOR TO THE COMMENCEMENT OF GRADING.

#### CONSTRUCTION INSPECTION

- PRIOR TO COMMENCING WORK AND FOR FINAL INSPECTION OF WORK AND SITE.
- THE COUNTY REQUIRES A MINIMUM OF 24 HOURS ADVANCE NOTICE FOR GENERAL INSPECTION, 48 HOURS FOR ASPHALT CONCRETE INSPECTION. INSPECTION BY SANTA CLARA COUNTY SHALL BE LIMITED TO INSPECTION OF
- MATERIALS AND PROCESSES OF CONSTRUCTION TO OBSERVE THEIR COMPLIANCE WITH PLANS & SPECIFICATIONS BUT DOES NOT INCLUDE RESPONSIBILITY FOR THE SUPERINTENDENT OF CONSTRUCTION, SITE CONDITIONS, EQUIPMENT OR PERSONNEL. CONTRACTOR SHALL NOTIFY THE COUNTY LAND DEVELOPMENT INSPECTOR AT PHONE (408) 299-6868 AT LEAST 24 HOURS PRIOR TO COMMENCING WORK AND FOR FINAL INSPECTION OF WORK AND SITE.
- DEVELOPER AND/OR HIS AUTHORIZED REPRESENTATIVE MUST SUBMIT WRITTEN REQUEST FOR FINAL INSPECTION AND ACCEPTANCE. SAID REQUEST SHALL BE DIRECTED TO THE INSPECTION OFFICE NOTED ON THE PERMIT FORM.
- THE CONTRACTOR SHALL PROVIDE TO THE COUNTY CONSTRUCTION INSPECTOR WITH PAD ELEVATION AND LOCATION CERTIFICATES, PREPARED BY THE PROJECT ENGINEER OR LAND SURVEYOR, PRIOR TO COMMENCEMENT OF THE BUILDING FOUNDATION.

#### SITE PREPARATION (CLEARING AND GRUBBING

- EXISTING TREES AUTHORIZED FOR REMOVAL, ROOTS, AND FOREIGN MATERIAL IN AREAS TO BE IMPROVED WILL BE REMOVED TO AN AUTHORIZED DISPOSAL SITE ACCESS ROADS AND DRIVEWAYS AS FOLLOWS:
  - PROPOSED ROADWAYS (EITHER PRIVATE OR TO BE DEDICATED TO PUBLIC USE)
- B) FROM AREAS AFFECTED BY THE PROPOSED GRADING EXCEPT WHERE NOTED ON THE PLANS. IT SHALL BE THE RESPONSIBILITY OF THE DEVELOPER TO MOVE OR RELOCATE
- UTILITY POLES AND OTHER OBSTRUCTIONS IN THE WAY OF CONSTRUCTION.
- TILITY LOCATION, TRENCHING & BACKFILI
- CONTRACTOR SHALL NOTIFY USA (UNDERGROUND SERVICE ALERT) AT 1-800-277-2600 A MINIMUM OF 24 HOURS BEFORE BEGINNING UNDERGROUND WORK FOR VERIFICATION OF THE LOCATION OF UNDERGROUND UTILITIES.
- ACCURATE VERIFICATION AS TO SIZE, LOCATION, AND DEPTH OF EXISTING UNDERGROUND CONDUITS OR FACILITIES SHALL BE THE INDIVIDUAL CONTRACTORS RESPONSIBILITY. PLAN LOCATIONS ARE APPROXIMATE AND FOR
- GENERAL INFORMATION ONLY. ALL UNDERGROUND INSTALLATIONS SHALL BE IN PLACE AND THE TRENCH BACKFILLED AND COMPACTED BEFORE PLACING AGGREGATE BASE MATERIAL OR SURFACE STRUCTURES. SURFACING MAY BE DONE IF THE UTILITY COMPANY CONCERNED INDICATES BY LETTER THAT IT WILL BORE. UNLESS SPECIFICALLY AUTHORIZED BY THE COUNTY, GAS AND WATER MAINS SHALL BE INSTALLED
- OUTSIDE THE PAVED AREAS. TRENCH BACKFILL IN EXISTING PAVEMENT AREAS SHALL BE SAND MATERIAL IN ACCORDANCE WITH THE APPLICABLE PROVISIONS OF THE STATE SPECIFICATIONS. THE STRUCTURAL SECTION FOR TRENCH REPLACEMENT SHALL CONSIST OF NOT LESS THAN 12 INCHES OF APPROVED AGGREGATE BASE MATERIAL COMPACTED TO A RELATIVE COMPACTION OF AT LEAST 95% AND 4 INCHES OF HOT ASPHALT CONCRETE PLACED IN TWO LIFTS. TRENCH RESTORATION FOR HIGHER TYPE PAVEMENTS SHALL BE MADE IN KIND OR AS
- DIRECTED BY THE COUNTY. TRENCH BACKFILL IN NEW CONSTRUCTION AREAS SHALL BE SAND MATERIAL COMPACTED TO A RELATIVE COMPACTION OF AT LEAST 90%. THE REQUIREMENT FOR SELECT MATERIAL MAY BE WAIVED BY COUNTY IF THE NATIVE SOIL IS SUITABLE FOR USE AS TRENCH BACKFILL BUT THE COMPACTION REQUIREMENTS WILL NOT BE THEREBY WAIVED.
- BACKFILL AND TRENCH RESTORATION REQUIREMENTS SHALL APPLY AS MINIMUM STANDARDS TO ALL UNDERGROUND FACILITIES INSTALLED BY OTHER FIRMS OR PUBLIC AGENCIES.

ETAINING WALLS

- REINFORCED CONCRETE AND CONCRETE MASONRY UNIT RETAINING WALLS SHALL HAVE FOUNDATION AND REINFORCEMENT INSPECTED BY THE COUNTY ENGINEERING CONTINUAL CONTROL OF THE COUNTY INSPECTOR. INSPECTOR AND ENGINEER OF RECORD PRIOR TO POURING THE FOUNDATION AND FORMING THE WALL
- SEGMENTAL BLOCK RETAINING WALLS SHALL HAVE FOUNDATION AND REINFORCEMENT INSPECTED BY THE COUNTY ENGINEERING INSPECTOR.

#### GRADING

- EXCAVATED MATERIAL SHALL BE PLACED IN THE FILL AREAS DESIGNATED OR SHALL BE HAULED AWAY FROM THE SITE TO A COUNTY APPROVED DISPOSAL SITE. WHERE FILL MATERIAL IS TO BE PLACED ON NATURAL GROUND, IS SHALL BE STRIPPED OF ALL VEGETATION. TO ACHIEVE A PROPER BOND WITH THE FILL MATERIAL, THE SURFACE OF THE GROUND SHALL BE SCARIFIED TO DEPTH OF 6" BEFORE FILL IS PLACED. WHERE NATURAL GROUND IS STEEPER THAN 5:1. IT SHALL BE BENCHED AND THE FILL KEYED IN TO ACHIEVE STABILITY. WHERE NEW FILL IS TO BE PLACED ON EXISTING FILL THE EXISTING FILL SHALL BE REMOVED UNTIL MATERIAL COMPACTED TO 90% RELATIVE COMPACTION IS EXPOSED. THEN THE NEW FILL MATERIAL SHALL BE PLACED AS PER THESE CONSTRUCTION NOTES. FILL MATERIAL SHALL BE PLACED IN UNIFORM LIFTS NOT EXCEEDING 6" IN UNCOMPACTED THICKNESS. BEFORE COMPACTION BEGINS, THE FILL SHALL BE BROUGHT TO A WATER CONTENT THAT WILL PERMIT PROPER COMPACTION BY EITHER 1) AERATING THE FILL IF IT IS TOO WET OR 2) MOISTENING THE FILL WITH WATER IF IT IS TOO DRY. EACH LIFT SHALL BE THOROUGHLY MIXED BEFORE COMPACTION TO ENSURE A UNIFORM DISTRIBUTION OF MOISTURE.
- EXCESS CUT MATERIAL SHALL NOT BE SPREAD OR STOCKPILED ON THE SITE. SURPLUS EARTH FILL MATERIAL SHALL BE PLACED IN A SINGLE (8" MAX) THICK LAYER COMPACTED TO WITHSTAND WEATHERING IN THE AREA(S) DELINEATED ON THE PLAN.
- 4. NO ORGANIC MATERIAL SHALL BE PLACED IN ANY FILL. NO TREES SHALL BE REMOVED OUTSIDE OF CUT. FILL OR ROADWAY AREAS. 5. THE UPPER 6" OF SUBGRADE BELOW DRIVEWAY ACCESS ROAD OR PARKING
- AREA SHALL BE COMPACTED TO 95% OF MAXIMUM DENSITY. 6. MAXIMUM CUT SLOPE SHALL BE 2 HORIZONTAL TO 1 VERTICAL. MAXIMUM FILL SLOPE SHALL BE 2 HORIZONTAL TO 1 VERTICAL.

Earthwork Quantities					
Cut Fill Net Max Cut Max Fill					
Driveway	600.76 CY	132.4 CY	468.36 CY (Cut)	5'	3'
Concrete Pad	0.72 CY	12.48 CY	11.76 CY (Fill)	1'	2'
Infiltration Trench	3001.55 CY	_	3001.55 CY (Cut)	5'	-
Total	3603.03 CY	144.88 CY	480.12 CY (Cut)	-	-

NOTE: FILL VOLUMES INCLUDE 10% SHRINKAGE. EXCESS MATERIAL SHALL BE OFF HAULED TO A COUNTY APPROVED DUMP

- . NOTIFY SOILS ENGINEER TWO (2) DAYS PRIOR TO COMMENCEMENT OF ANY
- GRADING WORK TO COORDINATE THE WORK IN THE FIELD. 8. ALL MATERIALS FOR FILL SHOULD BE APPROVED BY THE SOILS ENGINEER
- BEFORE IT IS BROUGHT TO THE SITE. 9. THE UPPER 6" OF THE SUBGRADE SOIL SHALL BE SCARIFIED, MOISTURE
- CONDITIONED AND COMPACTED TO A MINIMUM RELATIVE COMPACTION OF 95% 10. ALL AGGREGATE BASE MATERIAL SHALL BE COMPACTED TO A MINIMUM 95% RELATIVE COMPACTION.
- 11. THE GEOTECHNICAL PLAN REVIEW LETTER MUST BE REVIEWED AND APPROVED BY THE COUNTY GEOLOGIST PRIOR TO FINAL APPROVAL BY THE COUNTY ENGINEER FOR BUILDING OCCUPANCY. 12. THE PROJECT GEOTECHNICAL ENGINEER SHALL PERFORM COMPACTION TESTING
- AND PRESENT THE RESULTS TO THE COUNTY ENGINEERING INSPECTOR PRIOR TO THE CONSTRUCTION OF ANY PAVED AREA 13. GRADING WORK BETWEEN OCTOBER 15TH AND APRIL 15TH IS AT THE
- DISCRETION OF THE SANTA CLARA COUNTY GRADING OFFICIAL. 14. TOTAL DISTURBED AREA FOR THE PROJECT 22,674
- 15. WDID NO. <u>N/A</u>
- 16. THE INSPECTOR MAY VERIFY THAT A VALID NOTICE OF INTENT (NOI) HAS BEEN ISSUED BY THE STATE AND THAT A CURRENT AND UP TO DATE STORM WATER POLLUTION PREVENTION PLAN (SWPPP) IS AVAILABLE ON SITE.

#### TREE PROTECTION

- CONTRACTOR SHALL NOTIFY PERMIT INSPECTION UNIT, SANTA CLARA COUNTY 1. FOR ALL TREES TO BE RETAINED WITH A CANOPY IN THE DEVELOPMENT AREA OR INTERFACES WITH THE LIMITS OF GRADING FOR ALL PROPOS DEVELOPMENT ON SITE, THE TREES SHALL BE PROTECTED BY THE PLACEMENT OF RIGID TREE PROTECTIVE FENCING, CONSISTENT WITH THE COUNTY INTEGRATED LANDSCAPE GUIDELINES, AND INCLUDE THE FOLLOWING:
  - FENCING SHOULD BE PLACED ALONG THE OUTSIDE EDGE OF THE DRIPLINE OF THE TREE OR GROVE OF TREES. THE FENCING SHALL BE MAINTAINED THROUGHOUT THE SITE
  - CONSTRUCTION PERIOD AND SHALL BE INSPECTED PERIODICALLY FOR DAMAGE AND PROPER FUNCTION. FENCING SHALL BE REPAIRED, AS NECESSARY, TO PROVIDE A PHYSICAL
  - BARRIER FROM CONSTRUCTION ACTIVITIES. SIGNAGE STATING, "WARNING- THIS FENCING SHALL NOT BE REMOVED WITHOUT PERMISSION FROM THE SANTA CLARA COUNTY PLANNING OFFICE (408) 299-5770. COUNTY OF SANTA CLARA TREE PROTECTION MEASURES MAY BE FOUND AT
  - http://www.sccplanning.gov." SHALL BE PLACED ON THE TREE PROTECTIVE FENCING UNTIL FINAL OCCUPANCY.
  - 2. PRIOR TO COMMENCEMENT OF ANY CONSTRUCTION ACTIVITY, TREE PROTECTIVE FENCING SHALL BE SECURELY IN PLACED AND INSPECTED BY THE LAND DEVELOPMENT ENGINEERING INSPECTOR
  - SEE EXISTING TREE PROTECTION DETAILS FOR MORE INFORMATION.

- A) TO A MINIMUM DEPTH OF TWO FEET BELOW THE FINISHED GRADE OF 1. DRIVEWAY LOCATIONS SHALL BE AS SHOWN ON THE IMPROVEMENT PLANS WITH CENTERLINE STATIONING. THE MINIMUM CONCRETE THICKNESS SHALL BE 6 INCHES THROUGHOUT (WITH A MAXIMUM APPROACH SLOPE OF 1 1/4 INCHES PER FOOT).
  - ALL DRIVEWAY OR COMMON ACCESS ROAD SECTIONS IN EXCESS OF 15 LONGITUDINAL SLOPE MUST BE PAVED WITH A MINIMUM 2-INCH ASPHALT LIFT OR FULL DEPTH CONCRETE LIFT PRIOR TO ANY COMBUSTIBLE FRAMING.
  - 3. THE OWNER AND PRIME CONTRACTOR ARE RESPONSIBLE FOR MAINTAINING PROJECT SITE ACCESS AND NEIGHBORHOOD ACCESS FOR EMERGENCY VEHICLES AND LOCAL RESIDENTS
  - 4. ROADWAYS DESIGNATED AS NOT COUNTY MAINTAINED ROADS AS SHOWN ON THE PLAN WILL NOT BE ELIGIBLE FOR COUNTY MAINTENANCE UNTIL THE ROADWAYS ARE IMPROVED (AT NO COST TO THE COUNTY) TO THE PUBLIC MAINTENANCE ROAD STANDARDS APPROVED BY THE BOARD OF SUPERVISORS AND IN EFFECT AT SUCH TIME THAT THE ROADWAYS ARE CONSIDERED FOR ACCEPTANCE INTO THE COUNTY'S ROAD SYSTEM.
  - ALL WORK IN THE COUNTY ROAD RIGHT-OF-WAY REQUIRES AN ENCROACHMENT PERMIT FROM THE ROADS AND AIRPORTS DEPARTMENT. EACH INDIVIDUAL ACTIVITY REQUIRES A SEPARATE PERMIT - I.E. CABLE, ELECTRICAL, GAS. SEWER. WATER. RETAINING WALLS, DRIVEWAY APPROACHES, FENCES, LANDSCAPING, TREE REMOVAL, STORM DRAINAGE IMPROVEMENTS, ETC..

#### STREET LIGHTING

1. PACIFIC GAS & ELECTRIC ELECTROLIER SERVICE FEE SHALL BE PAID BY THE DEVELOPER AND/OR HIS AUTHORIZED REPRESENTATIVE.

- Sanitary sewer THE SANITARY SEWER AND WATER UTILITIES SHOWN ON THESE PLANS ARE
- NOT PART OF THIS GRADING PERMIT AND ARE SHOWN FOR REFERENCE ONLY. 2. ALL MATERIALS AND METHODS OF CONSTRUCTION OF SANITARY SEWERS SHALL THE AS-BUILT PLANS MUST BE FURNISHED TO THE COUNTY ENGINEER CONFORM TO THE SPECIFICATIONS OF THE JURISDICTION INVOLVED. INSPECTION AFTERCONSTRUCTION. OF SANITARY SEWER WORK SHALL BE DONE BY SAID JURISDICTION.

#### PORTLAND CEMENT CONCRETE

1. CONCRETE USED FOR STRUCTURAL PURPOSES SHALL BE CLASS "A" (6 SACK PER CUBIC YARD) AS SPECIFIED IN THE STATE STANDARD SPECIFICATIONS. CONCRETE PLACED MUST DEVELOP A MINIMUM STRENGTH FACTOR OF 2800 PSI IN A SEVEN-DAY PERIOD. THE CONCRETE MIX DESIGN SHALL BE UNDER THE

THIS IS A TRUE COPY OF THE AS-BUILT PLANS. THERE (\_\_\_\_ WERE) (\_\_\_\_ WERE NOT) MINOR FIELD CHANGES - MARKED WITH THE SYMBOL (^). THERE (\_\_\_WERE) WERE NOT) PLAN REVISIONS INDICATING SIGNIFICANT CHANGES REVIEWED BY THE COUNTY ENGINEER AND MARKED WITH THE SYMBOL  $\triangle$  .

SIGNATURE NOTE: THIS STATEMENT IS TO BE SIGNED BY THE PERSON AUTHORIZED BY THE COUNTY ENGINEER TO PERFORM THE INSPECTION WORK. A REPRODUCIBLE COPYOF

#### AIR QUALITY, LANDSCAPING AND EROSION CONTRO

. WATER ALL ACTIVE CONSTRUCTION AREAS AT LEAST TWICE DAILY. 2. COVER ALL TRUCKS HAULING SOIL, SAND, AND OTHER LOOSE MATERIALS OR REQUIRE ALL TRUCKS TO MAINTAIN AT LEAST TWO FEET OF FREEBOARD. 3. PAVE, APPLY WATER THREE TIMES DAILY, OR APPLY (NON-TOXIC) SOIL STABILIZERS ON ALL UNPAVED ACCESS ROADS, PARKING AREAS AND STAGING

- AREAS AT CONSTRUCTION SITES. 4. SWEEP DAILY (WITH WATER SWEEPERS) ALL PAVED ACCESS ROADS, PARKING AREAS AND STAGING AREAS AT CONSTRUCTION SITES. THE USE OF DRY POWDER SWEEPING IS PROHIBITED.
- 5. SWEEP STREETS DAILY (WITH WATER SWEEPERS) IF VISIBLE SOIL MATERIAL IS CARRIED ONTO ADJACENT PUBLIC STREETS. THE USE OF DRY POWDER SWEEPING IS PROHIBITED
- 6. ALL CONSTRUCTION VEHICLES, EQUIPMENT AND DELIVERY TRUCKS SHALL HAVE A MAXIMUM IDLING TIME OF 5 MINUTES (AS REQUIRED BY THE CALIFORNIA AIRBORNE TOXIC CONTROL MEASURE TITLE 13, SECTION 2485 OF CALIFORNIA CODE OF REGULATIONS (CCR)). ENGINES SHALL BE SHUT OFF IF CONSTRUCTION REQUIRES LONGER IDLING TIME UNLESS NECESSARY FOR PROPER OPERATION OF THE VEHICLE.
- 7. ALL VEHICLE SPEEDS ON UNPAVED ROADS SHALL BE LIMITED TO 15 MILES PFR HOUR 8. ALL CONSTRUCTION EQUIPMENT SHALL BE MAINTAINED AND PROPERLY TUNED IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS. ALL EQUIPMENT SHALL BE CHECKED BY A CERTIFIED MECHANIC AND DETERMINED TO BE
- RUNNING IN PROPER CONDITION PRIOR TO OPERATION. 9. POST A SIGN THAT IS AT LEAST 32 SQUARE FEET MINIMUM 2 INCHES LETTER HEIGHT VISIBLE NEAR THE ENTRANCE OF CONSTRUCTION SITE THAT IDENTIFIES THE FOLLOWING REQUIREMENTS. OBTAIN ENCROACHMENT PERMIT FOR SIGN FROM ROADS DEPARTMENT OR OTHER APPLICABLE AGENCY IF REQUIRED. A. 15 MILES PER HOUR (MPH) SPEED LIMIT
  - 3. 5 MINUTES MAXIMUM ÌDLING TIME OF VEHICLES
- TELEPHONE NUMBER TO CONTACT THE BAY AREA AIR QUALITY MANAGEMENT DISTRICT REGARDING DUST COMPLAINTS. NOTE PHONE NUMBER OF THE BAY AREA AIR QUALITY MANAGEMENT DISTRICT AIR POLLUTION COMPLAIN HOTLINE OF 1-800-334-6367.
- 10. ALL FILL SLOPES SHALL BE COMPACTED AND LEFT IN A SMOOTH AND FIRM CONDITION CAPABLE OF WITHSTANDING WEATHERING. 11. ALL EXPOSED DISTURBED AREAS SHALL BE SEEDED WITH BROME SEED SPREAD AT THE RATE OF 5 LB. PER 1000 SQUARE FEET (OR APPROVED EQUAL). SEEDING AND WATERING SHALL BE MAINTAINED AS REQUIRED TO ENSURE GROWTH
- 12. ALL DITCHES SHALL BE LINED PER COUNTY STANDARD SD8. 13. ALL STORM DRAINAGE STRUCTURES SHALL BE INSTALLED WITH EFFECTIVE ENTRANCE & OUTFALL EROSION CONTROLS E.G. SACKED CONCRETE RIP-RAP. ENERGY DISSIPATERS SHALL BE INSTALLED AT ALL DITCH OUTFALLS. WHERE OUTFALLS ARE NOT INTO AN EXISTING CREEK OR WATER COURSE, RUNOFF SHALL BE RELEASED TO SHEET FLOW.
- 14. PRIOR TO GRADING COMPLETION AND RELEASE OF THE BOND, ALL GRADED AREAS SHALL BE RESEEDED IN CONFORMANCE WITH THE COUNTY GRADING ORDINANCE TO MINIMIZE THE VISUAL IMPACTS OF THE GRADE SLOPES AND REDUCE THE POTENTIAL FOR EROSION OF THE SUBJECT SITE. 15. PERMANENT LANDSCAPING SHOWN ON THE ATTACHED LANDSCAPE PLAN MUST BE INSTALLED AND FIELD APPROVED BY THE COUNTY PLANNING OFFICE PRIOR TO FINAL APPROVAL BY THE COUNTY ENGINEER, AND FINAL OCCUPANCY RELEASE BY THE BUILDING INSPECTION OFFICE.
- 16. THE OWNER SHALL PREPARE AND PRESENT A WINTERIZATION REPORT TO THE COUNTY INSPECTOR FOR REVIEW PRIOR TO OCTOBER 15TH OF EVERY YEAR. 17. THE OWNER, CONTRACTOR, AND ANY PERSON PERFORMING CONSTRUCTION ACTIVITIES SHALL INSTALL AND MAINTAIN CONSTRUCTION BEST MANAGEMENT PRACTICES (BMPS) ON THE PROJECT SITE AND WITHIN THE SANTA CLARA COUNTY ROAD RIGHT-OF-WAY THROUGHOUT THE DURATION OF THE CONSTRUCTION AND UNTIL THE ESTABLISHMENT OF PERMANENT STABILIZATION AND SEDIMENT CONTROL TO PREVENT THE DISCHARGE OF POLLUTANTS INCLUDING SEDIMENT, CONSTRUCTION MATERIALS, EXCAVATED MATERIALS, AND WASTE INTO THE SANTA CLARA COUNTY RIGHT-OF-WAY. STORM SEWER WATERWAYS, ROADWAY INFRASTRUCTURE. BMPS SHALL INCLUDE, BUT NOT BE LIMITED TO THE FOLLOWING:
- A. PREVENTION OF POLLUTANTS IN STORM WATER DISCHARGES FROM THE CONSTRUCTION SITE AND THE CONTRACTOR'S MATERIAL AND EQUIPMENT LAYDOWN / STAGING AREAS. B. PREVENTION OF TRACKING OF MUD, DIRT, AND CONSTRUCTION
- MATERIALS ONTO THE PUBLIC ROAD RIGHT-OF-WAY. PREVENTION OF DISCHARGE OF WATER RUN-OFF DURING DRY AND WET WEATHER CONDITIONS ONTO THE PUBLIC ROAD RIGHT-OF-WAY. 18. THE OWNER, CONTRACTOR, AND ANY PERSON PERFORMING CONSTRUCTION

ACTIVITIES SHALL ENSURE THAT ALL TEMPORARY CONSTRUCTION FACILITIES. INCLUDING BUT NOT LIMITED TO CONSTRUCTION MATERIALS, DELIVERIES, HAZARDOUS AND NON-HAZARDOUS MATERIAL STORAGE, EQUIPMENT, TOOLS, PORTABLE TOILETS, CONCRETE WASHOUT, GARBAGE CONTAINERS, LAYDOWN YARDS, SECONDARY CONTAINMENT AREAS, ETC. ARE LOCATED OUTSIDE THE SANTA CLARA COUNTY ROAD RIGHT-OF-WAY. 19. EROSION CONTROL PLAN IS A GUIDE AND SHALL BE AMENDED AS NECESSARY TO PREVENT EROSION AND ILLICIT DISCHARGES ON A YEAR AROUND BASIS, DEPENDING ON THE SEASON, WEATHER, AND FIELD CONDITIONS. EROSION

CONTROL MEASURES IN ADDITION TO THOSE NOTED IN THE PERMITTED PLANS MAY BE NECESSARY. FAILURE TO INSTALL SITE SITE AND SITUATIONALY APPROPRIATE EROSION CONTROL MEASURES MAY RESULT IN VIOLATIONS, FINES, AND A STOPPAGE OF WORK.

### STORM DRAINAGE AND STORMWATER MANAGEMENT

. DEVELOPER IS RESPONSIBLE FOR ALL NECESSARY DRAINAGE FACILITIES WHETHER SHOWN ON THE PLANS OR NOT AND HE OR HIS SUCCESSOR PROPERTY OWNERS ARE RESPONSIBLE FOR THE ADEQUACY AND CONTINUED MAINTENANCE OF THESE FACILITIES IN A MANNER WHICH WILL PRECLUDE ANY HAZARD TO LIFE, HEALTH, OR DAMAGE TO ADJOINING PROPERTY, CONSISTENT WITH NPDES PERMIT CAS612008 / ORDER NO. R2-2009-0047 AND NPDES PERMIT CAS000004/ ORDER NO. 2013-0001-DWQ.

DROP INLETS SHALL BE COUNTY STANDARD TYPE 5 UNLESS OTHERWISE NOTED ON THE PLANS. THE DEVELOPER'S ENGINEER SHALL BE RESPONSIBLE FOR THE PROPER LOCATION OF DROP INLETS. WHERE STREET PROFILE GRADE EXCEEDS 6% DROP INLETS SHALL BE SET AT 500 ANGLE CURB LINE TO ACCEPT WATER OR AS SHOWN ON THE PLANS. WHERE CULVERTS ARE INSTALLED THE DEVELOPER SHALL BE RESPONSIBLE

FOR GRADING THE OUTLET DITCH TO DRAIN TO AN EXISTING SWALE OR TO AN OPEN AREA FOR SHEET FLOW. 4. UPON INSTALLATION OF DRIVEWAY CONNECTIONS, PROPERTY OWNERS SHALL


PROVIDE FOR THE UNINTERRUPTED FLOW OF WATER IN ROADSIDE DITCHES. THE COUNTY SHALL INSPECT UNDERGROUND DRAINAGE IMPROVEMENTS AND STORMWATER MANAGEMENT FEATURES PRIOR TO BACKFILL.


#### AS-BUILT PLANS STATEMENT

#### <u>Geotechnical engineer observation</u>

1. A CONSTRUCTION OBSERVATION LETTER FROM THE RESPONSIBLE

GEOTECHNICAL ENGINEER AND ENGINEERING GEOLOGIST DETAILING CONSTRUCTION OBSERVATIONS AND CERTIFYING THAT THE WORK WAS DONE IN ACCORDANCE WITH THE RECOMMENDATIONS IN THE GEOTECHNICAL AND GEOLOGIC REPORTS SHALL BE SUBMITTED PRIOR TO THE GRADING COMPLETION AND RELEASE OF THE BOND.





#### SURVEY MONUMENT PRESERVATION

- 1. THE LANDOWNER / CONTRACTOR MUST PROTECT AND ENSURE THE PERPETUATION OF SURVEY MONUMENTS AFFECTED BY CONSTRUCTION ACTIVITIES.
- PRIOR TO THE START OF CONSTRUCTION, THE CONTRACTOR SHALL LOCATE STAKE, AND FLAG OR OTHERWISE IDENTIFY WITH PAINT OR OTHER MARKINGS ALL PERMANENT SURVEY MONUMENTS OF RECORD AND ANY UNRECORDED MONUMENTS THAT ARE DISCOVERED THAT ARE WITHIN 50 FEET OF THE CONSTRUCTION ACTIVITY.
- 3. THE LANDOWNER, CONTRACTOR AND/OR ANY PERSON PERFORMING CONSTRUCTION ACTIVITIES THAT WILL OR MAY DISTURB AN EXISTING MONUMENT, CORNER STAKE, OR ANY OTHER PERMANENT SURVEYED MONUMENT SHALL CAUSE TO HAVE A LICENSED LAND SURVEYOR OR CIVIL ENGINEER, AUTHORIZED TO PRACTICE SURVEYING, ENSURE THAT A CORNER RECORD AND/OR RECORD OF SURVEY ARE FILED WITH THE COUNTY SURVEYOR'S OFFICE PRIOR TO DISTURBING SAID MONUMENTS AND RESET PERMANENT MONUMENT(S) IN THE SURFACE OF THE NEW CONSTRUCTION OR SET A WITNESS MONUMENT(S) TO PERPETUATE THE LOCATION IF ANY PERMANENT MONUMENT COULD BE DESTROYED, DAMAGED, COVERED, DISTURBED, OR OTHERWISE OBLITERATED. THE LICENSED LAND SURVEYOR OR CIVIL ENGINEER SHALL FILE A CORNER RECORD OR RECORD OF SURVEY WITH COUNTY SURVEYOR PRIOR TO FINAL ACCEPTANCE OF THE PROJECT BY THE LAND DEVELOPMENT ENGINEERING INSPECTOR.



PIPE 2" 0.C.

- INSPECTION.

COUNTY OF SANTA CLARA DEPT. OF ROADS AND AIRPORTS ISSUED BY: <u>DATE</u>:

ENCROACHMENT PERMIT NO.

NO WORK SHALL BE DONE IN THE COUNTY'S RIGHT-OF-WAY WITHUOT AN ENCROACHEMENT PERMIT, INCLUDING THE STAGING OF CONSTRUCTION MATERIAL AND THE PLACEMENT OF PORTABLE TOILETS.

#### ENGINEER'S STATEMENT

DATE \_\_\_\_\_




SIGNATURE




### COUNTY ENGINEER'S NOTE

ISSUANCE OF A PERMIT AUTHORIZING CONSTRUCTION DOES NOT RELEASE THE [ ENGINEER FROM RESPONSIBILITY FOR THE CORRECTION OF ERRORS OR OMISSION PLANS. IF, DURING THE COURSE OF CONSTRUCTION, THE PUBLIC INTEREST REQ (OR DEPARTURE FROM) THE SPECIFICATIONS OF THE PLANS, THE COUNTY SHAL TO REQUIRE THE SUSPENSION OF WORK, AND THE NECESSARY MODIFICATION OR SPECIFY THE MANNER IN WHICH THE SAME IS TO BE MADE.

R.C.E. NO.



# PROJECT TITLE LANDS OF DEMKOWSKI



#### EXISTING TREE PROTECTION DETAILS

1. PRIOR TO THE COMMENCEMENT OF ANY GRADING, TREE PROTECTIVE FENCING SHALL BE IN PLACE IN ACCORDANCE WITH THE TREE PRESERVATION PLAN AND INSPECTED BY A CERTIFIED ARBORIST. THE ARBORIST SHALL MONITOR CONSTRUCTION ACTIVITY TO ENSURE THAT THE TREE PROTECTION MEASURES ARE IMPLEMENTED AND ADHERED TO DURING CONSTRUCTION. THIS CONDITION

SHALL BE INCORPORATED INTO THE GRADING PLANS 2. FENCE SHALL BE MINIMUM 5 FEET TALL CONSTRUCTED OF STURDY MATERIAL (CHAIN-LINK OR EQUIVALENT STRENGTH/ DURABILITY). 3. FENCE SHALL BE SUPPORTED BY VERTICAL POSTS DRIVEN 2 FEET (MIN) INTO HE GROUND AND SPACED NOT MORE THAN 10 FEET APART 4. TREE FENCING SHALL BE MAINTAINED THROUGHOUT THE SITE DURING THE

CONSTRUCTION PERIOD, INSPECTED PERIODICALLY FOR DAMAGE AND PROPER FUNCTION, REPAIRED AS NECESSARY TO PROVIDE A PHYSICAL BARRIER FROM CONSTRUCTION ACTIVITIES, AND REMAIN IN PLACE UNTIL THE FINAL

5. A SIGN THAT INCLUDES THE WORDS, "WARNING: THIS FENCE SHALL NOT BE REMOVED WITHOUT THE EXPRESSED PERMISSION OF THE SANTA CLARA COUNTY PLANNING OFFICE." SHALL BE SECURELY ATTACHED TO THE FENCE IN A VISUALLY PROMINENT LOCATION.

COUNTY OF SAN LAND DEVELOPMENT ENGINE	
GRADING / DRAINAGE PERMIT N ISSUED BY:	
TED COUNTY STANDARDS, THE PERTAINING THERETO DATED	
R.C.E. NO.	
EXPIRATION DATE	
GINEER	
*	
ASE THE DEVELOPER, PERMITTEE OMISSIONS CONTAINED IN THE	
EREST REQUIRES A MODIFICATION	
CATION OR DEPARTURE AND TO	

EXPIRATION DATE

#### SCOPE OF WORK

1. THE DEVELOPER IS RESPONSIBLE FOR THE INSTALLATION OF THE WORK PROPOSED ON THE EROSION CONTROL PLAN. THE ENGINEER OF RECORD IS RESPONSIBLE FOR THE DESIGN OF THE EROSION CONTROL PLANS AND ANY MODIFICATIONS OF THE EROSION CONTROL PLANS TO PREVENT ILLICIT DISCHARGES FROM THE SITE DURING CONSTRUCTION.

#### **ON SITE**

- CONSTRUCTION OF A 12' DRIVEWAY
- CONSTRUCTION OF A CONCRETE PAD
- **REMOVAL OF 3 STORAGE CONTAINERS**
- NO TREES TO BE REMOVED 4
- NO PROPOSED LANDSCAPE FOR THIS PROJECT 5 OFF SITE

CONSTRUCTION OF ROADS AND AIRPORTS STD. B4 DRIVEWAY APPROACH.


#### LEGEND

EXISTING	PROPOSED	DESCRIPTION
	-	PROJECT PROPERTY LINE
	-	PROPERTY LINE
	-	CENTERLINE
	-	RIGHT-OF-WAY
-		STORMWATER DISSIPATOR
$\oplus$	-	ACTIVE EXISTING WELL

	SHEET INDEX
1	COVER SHEET
2	SITE PLAN
3	PARCEL PLAN
4	GRADING PLAN - DRIVEWAY
5	<b>GRADING PLAN - CONCRETE PAD</b>
6	GRADING PLAN - PROFILE AND
	DETAILS
BMP-1	COUNTY BMP SHEET
BMP-2	COUNTY BMP SHEET
ENGIN	IEER: CHRIS BERILLA 300 LAKESIDE DRIVE OAKLAND, CA 94612 717-422-7112 CHRIS.BERILLA@AECOM.COM
Revision	742 30 003 1
Revision	n 2 Date of

Date

Revision 3



**Coordinate System:** NAD83 CA State Planes Zone 3 is used for the coordinate system to designate northing and easting of control points.

Hillside

HS-sr

PG&E

50.681 AC

Hillside/Agricultural

Right of Way: Parcel Map and aerial imaging was used to approximate the right of way location. Right of way limits to be confirmed prior

Water: The location of the active existing wells are approximated and based on the GIS system of Santa Clara Valley District.

**Trees:** No trees to be removed during construction.

Sight Distance: Sight distance was checked on existing driveway and was determined to be adequate.

### Area of Disturbance: 22,674 SF

· · · · · · · · · · · · · · · · · · ·					
AREA TYPE	QUANTITY	UNITS			
CONTOUR INTERVAL	5	FEET			
LENGTH	810	FEET			
PROPOSED DEVELOPMENT AREA	44736.27	SQUARE FEET			
<u>Slope</u>	9.05	%			
Impervious Ar	ea Summary				
Driveway 9,893 SF					
Concrete Pad	4,608 SF				
Total Impervious Area	14,501 SF				

Earthwork Quantities					
Cut Fill Net Max Cut Max F					Max Fill
Driveway	600.76 CY	132.4 CY	468.36 CY (Cut)	5'	3'
Concrete Pad	0.72 CY	12.48 CY	11.76 CY (Fill)	1'	2'
Infiltration Trench	3001.55 CY	-	3001.55 CY (Cut)	5'	-
Total	3603.03 CY	144.88 CY	480.12 CY (Cut)	-	-


FIRE TRUCK TURNAROUND AREA

STORAGE CONTAINERS

HEAVY DUTY AC PAVEMENT AND BASE SEE DETAIL 1/C500 AND 2/C500 CONCRETE PAD

ENVIRONM CODE	ENTAL	ALTERNATIVE
drawing <b>C200</b>	NO.	
SCALE		
	AS	SHOWN
SHEET NO		
		OF

FULL SIZE MAP SCALE: 1" = 20'H: FEET 0102040



: Wheeler, Riana : Riana.wheeler Βγ: ΒΥ: C-PMT-GRD100.dwg 3/21/2024 5:04 PM 3/21/2024 5:03 PM Date: Date -ilen Plot I Save

# Applicant/Owner:

Mike Demkowski 4901 Croy Road Morgan Hill, CA 95037 408-640-1240 mdemkowski@gmail.com

# Engineer:

Chris Berilla 300 Lakeside Drive Oakland, CA 94612 717-422-7112 chris.berilla@aecom.com

# **Project Information:**

APN 742-30-003	
Present Use:	Hillside
Proposed Use:	Hillside/Agricultural
Present Zoning:	HS-sr
Gas and Electric:	PG&E
Existing Improvements:	As Shown
Area:	50.681 AC

Gas and Electric: Coast Counties Gas and Electric for the purpose of electric facilities and communication facilities to be located prior to construction. Recording No. is 447560 for Book 1433, page 288, of official records. Recording date is February 26th, 1947.

Coordinate System: NAD83 CA State Planes Zone 3 is used for the coordinate system to designate northing and easting of control points.

Right of Way: Parcel Map and aerial imaging was used to approximate the right of way location. Right of way limits to be confirmed prior to construction.

Water: The location of the active existing wells are approximated and based on the GIS system of Santa Clara Valley District.

**Trees:** No trees to be removed during construction.

Sight Distance: Sight distance was checked on existing driveway and was determined to be adequate.

# Area of Disturbance: 22,674 SF

AREA TYPE	QUANTITY	UNITS			
CONTOUR INTERVAL	5	FEET			
LENGTH	810	FEET			
PROPOSED DEVELOPMENT AREA	44736.27	SQUARE FEET			
<u>Slope</u>	9.05	%			
Impervious A	rea Summary				
Driveway	9,893 SF				
Concrete Pad	4,608 SF				
<b>Total Impervious Area</b>	Total Impervious Area14,501 SF				

Earthwork Quantities					
Cut Fill Net Max Cut Max Fill					Max Fill
Driveway	600.76 CY	132.4 CY	468.36 CY (Cut)	5'	3'
Concrete Pad	0.72 CY	12.48 CY	11.76 CY (Fill)	1'	2'
Infiltration Trench	3001.55 CY	-	3001.55 CY (Cut)	5'	-
Total	3603.03 CY	144.88 CY	480.12 CY (Cut)	_	-




\_\_\_\_\_

PROJECT PROPERTY LINE

PROPERTY LINE

CENTERLINE

**RIGHT-OF-WAY** 



# **CROY BARN** MORGAN HILL - CALIFORNIA MIKE DEMKOWSKI PROPERTY PARCEL PLAN


NVIRONMENTAL ALTERNATIVE CODE DRAWING NO. C300 SCALE AS SHOWN SHEET NO. OF

FULL SIZE MAP SCALE: 1" = 150'

3Ò0

H: FEET 0 75 150





Filename: C-PMT-GRD100.dwg Plot Date: 3/21/2024 5:05 PM By: Wheeler, R Save Date: 3/21/2024 5:03 PM BY: Riana.whee



Mike Demkowski 4901 Croy Road Morgan Hill, CA 95037 408-640-1240 mdemkowski@gmail.com

# Engineer:

Chris Berilla 300 Lakeside Drive Oakland, CA 94612 717-422-7112 chris.berilla@aecom.com

# Project Information:

APN 742-30-003	
Present Use:	Hillside
Proposed Use:	Hillside/Agricultural
Present Zoning:	HS-sr
Gas and Electric:	PG&E
Existing Improvements:	As Shown
Area:	50.681 AC

**Gas and Electric:** Coast Counties Gas and Electric for the purpose of electric facilities and communication facilities to be located prior to construction. Recording No. is 447560 for Book 1433, page 288, of official records. Recording date is February 26th, 1947.

**Coordinate System:** NAD83 CA State Planes Zone 3 is used for the coordinate system to designate northing and easting of control points.

**Right of Way:** Parcel Map and aerial imaging was used to approximate the right of way location. Right of way limits to be confirmed prior to construction.

**Water:** The location of the active existing wells are approximated and based on the GIS system of Santa Clara Valley District.

**Trees:** No trees to be removed during construction.

**Sight Distance:** Sight distance was checked on existing driveway and was determined to be adequate.

### Area of Disturbance: 22,674 SF

AREA TYPE	QUANTITY	UNITS			
CONTOUR INTERVAL	5	FEET			
LENGTH	810	FEET			
PROPOSED DEVELOPMENT AREA	44736.27	SQUARE FEET			
<u>Slope</u>	9.05	%			
Impervious Ar	ea Summary				
Driveway 9,893 SF					
Concrete Pad	Concrete Pad 4,608 SF				
Total Impervious Area	14,501 SF				

Earthwork Quantities					
	Cut	Fill	Net	Max Cut	Max Fill
Driveway	600.76 CY	132.4 CY	468.36 CY (Cut)	5'	3'
Concrete Pad	0.72 CY	12.48 CY	11.76 CY (Fill)	1'	2'
Infiltration Trench	3001.55 CY	-	3001.55 CY (Cut)	5'	-
Total	3603.03 CY	144.88 CY	480.12 CY (Cut)	_	_

# TOPOGRAPHIC LEGEND

EXISTING CONTOURS

PROPOSED CONTOURS

PROPOSED CO

H: FEET 0 10 20 4

CROY BARN MORGAN HILL - CALIFORNIA MIKE DEMKOWSKI PROPERTY GRADING PLAN DRIVEWAY

EXISTING GROUND-


DRAWING NO. **G200** SCALE AS SHOWN SHEET NO. OF


FULL SIZE MAP SCALE: 1" =

FULL SIZE MAP SCALE: 1" = 8H: FEET 0 4 8 1

FULL SIZE MAP SCALE: 1" = 20'

H: FEET 0 1 2





Filename: C-PMT-GRD100.dwg Plot Date: 3/21/2024 5:05 PM By: Wheeler, Riana Save Date: 3/21/2024 5:03 PM BY: Riana.wheeler

AECOM

**AECOM USA, Inc.** 300 Lakeside Drive, Suite 400 Oakland, CA 94612 T 510.893.3600

www.aecom.com

# Applicant/Owner:

Mike Demkowski 4901 Croy Road Morgan Hill, CA 95037 408-640-1240 mdemkowski@gmail.com

# Engineer:

Chris Berilla 300 Lakeside Drive Oakland, CA 94612 717-422-7112 chris.berilla@aecom.com

# **Project Information:**

APN 742-30-003	
Present Use:	Hillside
Proposed Use:	Hillside/Agricultural
Present Zoning:	HS-sr
Gas and Electric:	PG&E
Existing Improvements:	As Shown
Area:	50.681 AC

**Gas and Electric:** Coast Counties Gas and Electric for the purpose of electric facilities and communication facilities to be located prior to construction. Recording No. is 447560 for Book 1433, page 288, of official records. Recording date is February 26th, 1947.

**Coordinate System:** NAD83 CA State Planes Zone 3 is used for the coordinate system to designate northing and easting of control points.

**Right of Way:** Parcel Map and aerial imaging was used to approximate the right of way location. Right of way limits to be confirmed prior to construction.

**Water:** The location of the active existing wells are approximated and based on the GIS system of Santa Clara Valley District.

**Trees:** No trees to be removed during construction.

**Sight Distance:** Sight distance was checked on existing driveway and was determined to be adequate.


# Area of Disturbance: 22,674 SF


AREA TYPE	QUANTITY	UNITS			
CONTOUR INTERVAL	5	FEET			
LENGTH	810	FEET			
PROPOSED DEVELOPMENT AREA	44736.27	SQUARE FEET			
<u>Slope</u>	9.05	%			
Impervious Area Summary					
Driveway	9,893 SF				
Concrete Pad	4,608 SF				
Total Impervious Area	14,501 SF				

Earthwork Quantities					
	Cut	Fill	Net	Max Cut	Max Fill
Driveway	600.76 CY	132.4 CY	468.36 CY (Cut)	5'	3'
Concrete Pad	0.72 CY	12.48 CY	11.76 CY (Fill)	1'	2'
Infiltration Trench	3001.55 CY	_	3001.55 CY (Cut)	5'	-
Total	3603.03 CY	144.88 CY	480.12 CY (Cut)	_	-




CROY BARN MORGAN HILL - CALIFORNIA MIKE DEMKOWSKI PROPERTY GRADING PLAN CONCRETE PAD environmental alternative code drawing no. **G300** scale AS SHOWN sheet no. OF






Structural Construction Section Notes 1. All driveway approach and driveway sections shall be 4" of AC on 8" of Class II aggregate base compacted to 95% relative compaction.



Wheeler, Riana Riana.wheeler Β<u>Υ</u>: Β<u>Υ</u>: C-PMT-GRD100.dwg 3/21/2024 5:05 PM 3/21/2024 5:03 PM Date: Date olot Save

**PROFILE VIEW** SCALE H: 1"=30' SCALE V: 1"=10'



AECOM USA, Inc. 300 Lakeside Drive, Suite 400 Oakland, CA 94612 T 510.893.3600

AECOM

www.aecom.com

600 mm (2') max.

# Applicant/Owner:

Mike Demkowski 4901 Croy Road Morgan Hill, CA 95037 408-640-1240 mdemkowski@gmail.com

# Engineer:

Chris Berilla 300 Lakeside Drive Oakland, CA 94612 717-422-7112 chris.berilla@aecom.com

# **Project Information:**

APN 742-30-003	
Present Use:	Hillside
Proposed Use:	Hillside/Agricultural
Present Zoning:	HS-sr
Gas and Electric:	PG&E
Existing Improvements:	As Shown
Area:	50.681 AC

Gas and Electric: Coast Counties Gas and Electric for the purpose of electric facilities and communication facilities to be located prior to construction. Recording No. is 447560 for Book 1433, page 288, of official records. Recording date is February 26th, 1947.

**Coordinate System:** NAD83 CA State Planes Zone 3 is used for the coordinate system to designate northing and easting of control points.

Right of Way: Parcel Map and aerial imaging was used to approximate the right of way location. Right of way limits to be confirmed prior to construction.

Water: The location of the active existing wells are approximated and based on the GIS system of Santa Clara Valley District.


**Trees:** No trees to be removed during construction.

Sight Distance: Sight distance was checked on existing driveway and was determined to be adequate.

### Area of Disturbance: 22,674 SF

AREA TYPE	QUANTITY	UNITS			
CONTOUR INTERVAL	5	FEET			
LENGTH	810	FEET			
PROPOSED DEVELOPMENT AREA	44736.27	SQUARE FEET			
<u>Slope</u>	9.05	%			
Impervious Area Summary					
Driveway	9,893 SF				
Concrete Pad	4.608 SF				

Earthwork Quantities					
	Cut	Fill	Net	Max Cut	Max Fill
Driveway	600.76 CY	132.4 CY	468.36 CY (Cut)	5'	3'
Concrete Pad	0.72 CY	12.48 CY	11.76 CY (Fill)	1'	2'
Infiltration Trench	3001.55 CY	-	3001.55 CY (Cut)	5'	-
Total	3603.03 CY	144.88 CY	480.12 CY (Cut)	-	-



# **CROY BARN** MORGAN HILL - CALIFORNIA MIKE DEMKOWSKI PROPERTY **GRADING PLAN PROFILE AND DETAILS**

EN VIRONM CODE	IENTAL	ALTERNATIVE
	NO.	
G400		
SCALE		
	AS	SHOWN
SHEET NO	).	
		OF