ASA SUBMITTAL SET

DRAWING STATUS ASA SUBMITTAL ASA COMPLIANCE RE-SUBMITTAL PERMIT APPLICATION CONSTRUCTION PERMIT RECORD DRAWINGS

SUBMITTAL DATE: APPROVAL DATE: 03/18/2024 08/13/2024



VICINITY MAP

STANFORD UNIVERSITY LACROSSE PRACTICE FIELD

PROJECT 200184

(09-379, 657 MASTERS MALL)

| | DRAV | VING INDEX |
|---------------|---|--|
| | PL0.0 PL1.2 | TITLE SHEET GUP INFORMATION MAP |
| PROPOSED SITE | C-1.0 C-1.1 C-2.0 C-3.0 C-3.1 C-4.0 C-4.1 C-5.0 C-6.0 C-6.1 C-6.2 C-7.0 C-8.0 C-8.0 C-9.0 | COUNTY COVER SHEET CONSTRUCTION NOTES TOPOGRAPHIC SURVEY DEMOLITION/TREE REMOVAL PLAN DEMOLITION/TREE REMOVAL PLAN GRADING & DRAINAGE PLAN GRADING SECTIONS UTILITY PLAN EROSION CONTROL PLAN COUNTY BMP NOTES COUNTY BMP NOTES FIRE ACCESS PLAN STORMWATER MANAGEMENT PLAN CONSTRUCTION SITE/LOGISTICS SAFETY PL |
| | L-1.01 L-1.02 | LANDSCAPE PLAN LANDSCAPE NOTES |
| | E-1 E-2 E-3 E-5 E-6 E-7 E-8 E-9 E-10 | PROJECT SUMMARY ILLUMINATION SUMMARY ILLUMINATION SUMMARY ILLUMINATION SUMMARY EQUIPMENT LAYOUT POLE CONFIGURATION DRAWING EXISTING LIGHTING PLAN EXISTING LIGHTING SPECIFICATIONS |
| | | |

SITE DATA INFORMATION

GENERAL

APN: PARCEL SIZE: DEVELOPMENT DISTRICT: BUILDING/QUAD: LAND USE DESIGNATION: SITE AREA:

142-04-036 580.15 AC DAPER AND ADMINISTRATIVE 09-379 ACADEMIC CAMPUS 139,275 SF

PERCENTAGE OF SITE AREA:

LANDSCAPE: HARDSCAPE: 97.6 % 2.4 %

EXCAVATION TABLE

| LOCATION | CUT (C.Y.) | FILL (C.Y.) | VERT. DEPTH |
|--------------------------|------------|-------------|-------------|
| RESIDENCE | 0 | 0 | |
| ACCESSORY STRUCTURE | 0 | 0 | |
| POOL/HARDSCAPE | 0 | 0 | |
| LANDSCAPE | 7,618 | 1,761 | 2 |
| DRIVEWAY | 0 | 0 | |
| OFF SITE IMPROVEMENTS | 0 | 0 | |
| TOTAL | 7,618 | 1,761 | 2 |

PROJECT DESCRIPTION:

THIS PROJECT INCLUDES CONSTRUCTION OF A NEW LACROS FIELD. THE SCOPE OF WORK INCLUDES SITE GRADING, INSTALLATION OF UTILITIES, REMOVAL OF EXISTING TREES A INSTALLATION OF FENCING.

PROJECT MANAGER: Mark Bonino 560 Fremont Road Stanford, CA 94305 Telephone: (650) 723-0022 mbonino@stanford.edu

LAN

| | REVISION |
|-----|--|
| | 2TMENT OF PROJECT MANAGEMENT nair Siding Road d, CA 94304 ONE (650) 723-0022 FAX (650) 723-7444 |
| SSE | TITLE SHEET Stanf TELE |
| AND | ATE: 03/18/2024 DATE: N/A PLO.0 |





PROPOSED SITE

GUP INFORMATION MAP

| REVISION |
|---|
| GEMENT 350) 723-7444 |
| T MANA(Fax (6 |
| DEPARTMENT OF PROJEC ^r 340 Bonair Siding Road Stanford, CA 94304 TELEPHONE (650) 723-0022 |
| GUP INFORMATION MAP |
| CALE: N/A RACTICE FIELD DATE: 03/18/2024 SCALE: N/A |

COUNTY OF SANTA CLARA

<u>General Construction</u> <u>Specifications</u>

GENERAL CONDITIONS

- ALL CONSTRUCTION WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE SOILS AND/OR GEOTECHNICAL REPORT PREPARED BY SILICON VALLEY SOIL ENGINEERING AND DATED XXXX 202X. THIS REPORT IS SUPPLEMENTED BY: 1) THESE PLANS AND SPECIFICATIONS, 2) THE COUNTY OF SANTA CLARA STANDARD DETAILS. 3) THE COUNTY OF SANTA CLARA STANDARD SPECS, 4) STATE OF CALIFORNIA STANDARD DETAILS, 5) STATE OF CALIFORNIA STANDARD SPECIFICATIONS. IN THE EVENT OF CONFLICT THE FORMER SHALL TAKE PRECEDENCE OVER THE LATTER. THE PERFORMANCE AND COMPLETION
- OF ALL WORK MUST BE TO THE SATISFACTION OF THE COUNTY. DEVELOPER IS RESPONSIBLE FOR INSTALLATION OF THE IMPROVEMENTS SHOWN ON THESE PLANS AND HE OR HIS SUCCESSOR PROPERTY OWNERS ARE RESPONSIBLE FOR THEIR CONTINUED MAINTENANCE.
- DEVELOPER SHALL BE RESPONSIBLE FOR CORRECTION OF ANY ERRORS OR OMISSIONS IN THESE PLANS. THE COUNTY SHALL BE AUTHORIZED TO REQUIRE DISCONTINUANCE OF ANY WORK AND SUCH CORRECTION AND MODIFICATION OF PLANS AS MAY BE NECESSARY TO COMPLY WITH COUNTY STANDARDS OR CONDITIONS OF DEVELOPMENT APPROVAL
- DEVELOPER SHALL OBTAIN ENCROACHMENT PERMITS FROM THE SANTA CLARA VALLEY WATER DISTRICT AND CALIFORNIA DEPARTMENT OF TRANSPORTATION WHERE NEEDED. COPIES OF THESE PERMITS SHALL BE KEPT AT THE JOB SITE FOR REVIEW BY THE COUNTY'S INSPECTOR.
- DEVELOPER SHALL REMOVE OR TRIM ALL TREES TO PROVIDE AN UNOBSTRUCTED FIFTEEN (15) FOOT VERTICAL CLEARANCE FOR ROADWAY AREA. THIS PLAN AUTHORIZES THE REMOVAL OF ONLY THOSE TREES WITH TRUNK DIAMETERS GREATER THAN 12 INCHES MEASURED 4.5 FEET ABOVE THE GROUND THAT ARE SHOWN TO BE REMOVED UNLESS AN AMENDED PLAN IS APPROVED OR A SEPARATE TREE REMOVAL PERMIT IS OBTAINED FROM THE PLANNING OFFICE. IT IS THE CONTRACTOR'S RESPONSIBILITY TO ENSURE THAT REMOVAL OF ADDITIONAL TREES HAS BEEN PERMITTED. . DEVELOPER SHALL PROVIDE ADEQUATE DUST CONTROL AS REQUIRED BY THE
- COUNTY INSPECTOR 3. ALL PERSONS MUST COMPLY WITH SECTION 4442 OF THE PUBLIC RESOURCES CODE AND SECTION 13005 OF THE HEALTH AND SAFETY CODE RELATING TO
- THE USE OF SPARK ARRESTERS.). UPON DISCOVERING OR UNEARTHING ANY BURIAL SITE AS EVIDENCED BY HUMAN SKELETAL REMAINS OR ARTIFACTS, THE PERSON MAKING SUCH DISCOVERY SHALL IMMEDIATELY NOTIFY THE COUNTY CORONER AT (4008) 454-2520 AND LAND DEVELOPMENT ENGINEERING OFFICE AT (408) 299-5730. NO FURTHER DISTURBANCE OF THE SITE MAY BE MADE EXCEPT AS AUTHORIZED BY THE LAND DEVELOPMENT OFFICE IN ACCORD WITH PROVISIONS OF THIS ORDINANCE (COUNTY ORDINANCE CODE SECTION B6-18).
- 10. THESE PLANS ARE FOR THE WORK DESCRIBED IN THE SCOPE OF WORK ONLY. A SEPARATE PERMIT WILL BE REQUIRED FOR THE SEPTIC LINE CONSTRUCTION. 11. ANY DEVIATION FROM THESE APPROVED PLANS SHALL BE RE-APPROVED IN WRITING BY THE COUNTY ENGINEER PRIOR TO CONSTRUCTION.

CONSTRUCTION STAKING

- THE DEVELOPER'S ENGINEER IS RESPONSIBLE FOR THE INITIAL PLACEMENT AND REPLACEMENT OF CONSTRUCTION GRADE STAKES. THE STAKES ARE TO BE ADEQUATELY IDENTIFIED, LOCATED, STABILIZED, ETC. FOR THE CONVENIENCE OF CONTRACTORS. LATERAL OFFSET OF STAKES SET FOR CURBS AND
- GUTTERS SHALL NOT EXCEED 2 1/2 FEET FROM BACK OF CURB. ANY PROPERTY LINE STAKES OR ROAD MONUMENTS DISTURBED DURING CONSTRUCTION SHALL BE REPLACED BY DEVELOPER'S ENGINEER AND LICENSED LAND SURVEYOR.
- PROPERTY LINE STAKING MUST BE PERFORMED BY THE PROJECT ENGINEER OR LAND SURVEYOR TO ESTABLISH OR RE-ESTABLISH THE PROJECT BOUNDARY AND SHALL BE INSPECTED BY THE COUNTY INSPECTOR PRIOR TO THE
- BEGINNING OF THE WORK. PROPER CONSTRUCTION STAKES SHALL BE SET IN THE FIELD BY THE PROJECT ENGINEER OR LAND SURVEYOR AND VERIFIED BY THE COUNTY INSPECTOR PRIOR TO THE COMMENCEMENT OF GRADING

CONSTRUCTION INSPECTION

- CONTRACTOR SHALL NOTIFY PERMIT INSPECTION UNIT. SANTA CLARA COUNTY PRIOR TO COMMENCING WORK AND FOR FINAL INSPECTION OF WORK AND SITE.
- 2. THE COUNTY REQUIRES A MINIMUM OF 24 HOURS ADVANCE NOTICE FO
- GENERAL INSPECTION. 48 HOURS FOR ASPHALT CONCRETE INSPECTION. INSPECTION BY SANTA CLARA COUNTY SHALL BE LIMITED TO INSPECTION OF MATERIALS AND PROCESSES OF CONSTRUCTION TO OBSERVE THEIR COMPLIANCE WITH PLANS & SPECIFICATIONS BUT DOES NOT INCLUDE RESPONSIBILITY FOR THE SUPERINTENDENT OF CONSTRUCTION, SITE CONDITIONS. EQUIPMENT OR PERSONNEL. CONTRACTOR SHALL NOTIFY THE COUNTY LAND DEVELOPMENT INSPECTOR AT PHONE (408) 299-6868 AT LEAST 24 HOURS PRIOR TO COMMENCING WORK AND FOR FINAL INSPECTION
- OF WORK AND SITE. DEVELOPER AND/OR HIS AUTHORIZED REPRESENTATIVE MUST SUBMIT WRITTEN REQUEST FOR FINAL INSPECTION AND ACCEPTANCE. SAID REQUEST SHALL BE DIRECTED TO THE INSPECTION OFFICE NOTED ON THE PERMIT FORM.
- THE CONTRACTOR SHALL PROVIDE TO THE COUNTY CONSTRUCTION INSPECTOR WITH PAD ELEVATION AND LOCATION CERTIFICATES, PREPARED BY THE PROJECT ENGINEER OR LAND SURVEYOR, PRIOR TO COMMENCEMENT OF THE BUILDING FOUNDATION.

SITE PREPARATION (CLEARING AND GRUBBING)

- EXISTING TREES AUTHORIZED FOR REMOVAL, ROOTS, AND FOREIGN MATERIAL IN AREAS TO BE IMPROVED WILL BE REMOVED TO AN AUTHORIZED DISPOSAL SITE ACCESS ROADS AND DRIVEWAYS AS FOLLOWS:
 - PROPOSED ROADWAYS (EITHER PRIVATE OR TO BE DEDICATED TO PUBLIC USE)
 - B) FROM AREAS AFFECTED BY THE PROPOSED GRADING EXCEPT WHERE NOTED ON THE PLANS.
- 2. IT SHALL BE THE RESPONSIBILITY OF THE DEVELOPER TO MOVE OR RELOCATE UTILITY POLES AND OTHER OBSTRUCTIONS IN THE WAY OF CONSTRUCTION.

JTILITY LOCATION, TRENCHING & BACKFILI

- CONTRACTOR SHALL NOTIFY USA (UNDERGROUND SERVICE ALERT) AT 1-800-277-2600 A MINIMUM OF 24 HOURS BEFORE BEGINNING UNDERGROUND WORK FOR VERIFICATION OF THE LOCATION OF UNDERGROUND
- ACCURATE VERIFICATION AS TO SIZE, LOCATION, AND DEPTH OF EXISTING UNDERGROUND CONDUITS OR FACILITIES SHALL BE THE INDIVIDUAL CONTRACTORS RESPONSIBILITY. PLAN LOCATIONS ARE APPROXIMATE AND FOR
- GENERAL INFORMATION ONLY. ALL UNDERGROUND INSTALLATIONS SHALL BE IN PLACE AND THE TRENCH BACKFILLED AND COMPACTED BEFORE PLACING AGGREGATE BASE MATERIAL OR SURFACE STRUCTURES. SURFACING MAY BE DONE IF THE UTILITY COMPANY CONCERNED INDICATES BY LETTER THAT IT WILL BORE. UNLESS SPECIFICALLY AUTHORIZED BY THE COUNTY, GAS AND WATER MAINS SHALL BE INSTALLED
- TRENCH BACKFILL IN EXISTING PAVEMENT AREAS SHALL BE SAND MATERIAL IN 1. PACIFIC GAS & ELECTRIC ELECTROLIER SERVICE FEE SHALL BE PAID BY THE ACCORDANCE WITH THE APPLICABLE PROVISIONS OF THE STATE SPECIFICATIONS. THE STRUCTURAL SECTION FOR TRENCH REPLACEMENT SHALL CONSIST OF NOT LESS THAN 12 INCHES OF APPROVED AGGREGATE BASE MATERIAL COMPACTED TO A RELATIVE COMPACTION OF AT LEAST 95% AND 4
- INCHES OF HOT ASPHALT CONCRETE PLACED IN TWO LIFTS. TRENCH RESTORATION FOR HIGHER TYPE PAVEMENTS SHALL BE MADE IN KIND OR AS DIRECTED BY THE COUNTY. TRENCH BACKFILL IN NEW CONSTRUCTION AREAS SHALL BE SAND MATERIAL
- COMPACTED TO A RELATIVE COMPACTION OF AT LEAST 90%. THE REQUIREMENT FOR SELECT MATERIAL MAY BE WAIVED BY COUNTY IF THE NATIVE SOIL IS SUITABLE FOR USE AS TRENCH BACKFILL BUT THE COMPACTION REQUIREMENTS WILL NOT BE THEREBY WAIVED.
- BACKFILL AND TRENCH RESTORATION REQUIREMENTS SHALL APPLY AS MINIMUM STANDARDS TO ALL UNDERGROUND FACILITIES INSTALLED BY OTHER FIRMS OR PUBLIC AGENCIES.

RETAINING WALLS

- REINFORCED CONCRETE AND CONCRETE MASONRY UNIT RETAINING WALLS SHALL HAVE FOUNDATION AND REINFORCEMENT INSPECTED BY THE COUNTY ENGINEERING INSPECTOR AND ENGINEER OF RECORD PRIOR TO POURING THE FOUNDATION AND FORMING THE WALL SEGMENTAL BLOCK RETAINING WALLS SHALL HAVE FOUNDATION AND
- REINFORCEMENT INSPECTED BY THE COUNTY ENGINEERING INSPECTOR

GRADING

- WATER ALL ACTIVE CONSTRUCTION AREAS AT LEAST TWICE DAILY. EXCAVATED MATERIAL SHALL BE PLACED IN THE FILL AREAS DESIGNATED OR COVER ALL TRUCKS HAULING SOIL, SAND, AND OTHER LOOSE MATERIALS OR REQUIRE ALL TRUCKS TO MAINTAIN AT LEAST TWO FEET OF FREEBOARD. SHALL BE HAULED AWAY FROM THE SITE TO A COUNTY APPROVED DISPOSAL SITE. WHERE FILL MATERIAL IS TO BE PLACED ON NATURAL GROUND, IS SHALL BE STRIPPED OF ALL VEGETATION. TO ACHIEVE A PROPER BOND WITH THE 3. PAVE, APPLY WATER THREE TIMES DAILY, OR APPLY (NON-TOXIC) SOIL FILL MATERIAL, THE SURFACE OF THE GROUND SHALL BE SCARIFIED TO DEPTH STABILIZERS ON ALL UNPAVED ACCESS ROADS, PARKING AREAS AND STAGING OF 6" BEFORE FILL IS PLACED. WHERE NATURAL GROUND IS STEEPER THAN AREAS AT CONSTRUCTION SITES. 5:1, IT SHALL BE BENCHED AND THE FILL KEYED IN TO ACHIEVE STABILITY. SWEEP DAILY (WITH WATER SWEEPERS) ALL PAVED ACCESS ROADS, PARKING WHERE NEW FILL IS TO BE PLACED ON EXISTING FILL THE EXISTING FILL SHALL AREAS AND STAGING AREAS AT CONSTRUCTION SITES. THE USE OF DRY BE REMOVED UNTIL MATERIAL COMPACTED TO 90% RELATIVE COMPACTION IS POWDER SWEEPING IS PROHIBITED. EXPOSED. THEN THE NEW FILL MATERIAL SHALL BE PLACED AS PER THESE 5. SWEEP STREETS DAILY (WITH WATER SWEEPERS) IF VISIBLE SOIL MATERIAL IS CONSTRUCTION NOTES. FILL MATERIAL SHALL BE PLACED IN UNIFORM LIFTS CARRIED ONTO ADJACENT PUBLIC STREETS. THE USE OF DRY POWDER NOT EXCEEDING 6" IN UNCOMPACTED THICKNESS. BEFORE COMPACTION BEGINS. SWEEPING IS PROHIBITED. THE FILL SHALL BE BROUGHT TO A WATER CONTENT THAT WILL PERMIT ALL CONSTRUCTION VEHICLES, EQUIPMENT AND DELIVERY TRUCKS SHALL 6. PROPER COMPACTION BY EITHER 1) AERATING THE FILL IF IT IS TOO WET OR HAVE A MAXIMUM IDLING TIME OF 5 MINUTES (AS REQUIRED BY THE 2) MOISTENING THE FILL WITH WATER IF IT IS TOO DRY. EACH LIFT SHALL BE CALIFORNIA AIRBORNE TOXIC CONTROL MEASURE TITLE 13, SECTION 2485 OF THOROUGHLY MIXED BEFORE COMPACTION TO ENSURE A UNIFORM DISTRIBUTION CALIFORNIA CODE OF REGULATIONS (CCR)). ENGINES SHALL BE SHUT OFF IF OF MOISTURE. CONSTRUCTION REQUIRES LONGER IDLING TIME UNLESS NECESSARY FOR EXCESS CUT MATERIAL SHALL NOT BE SPREAD OR STOCKPILED ON THE SITE. PROPER OPERATION OF THE VEHICLE.
- SURPLUS EARTH FILL MATERIAL SHALL BE PLACED IN A SINGLE (8" MAX) THICK LAYER COMPACTED TO WITHSTAND WEATHERING IN THE AREA(S)
- DELINEATED ON THE PLAN. 4. NO ORGANIC MATERIAL SHALL BE PLACED IN ANY FILL. NO TREES SHALL BE
- REMOVED OUTSIDE OF CUT, FILL OR ROADWAY AREAS. THE UPPER 6" OF SUBGRADE BELOW DRIVEWAY ACCESS ROAD OR PARKING AREA SHALL BE COMPACTED TO 95% OF MAXIMUM DENSITY. 6. MAXIMUM CUT SLOPE SHALL BE 2 HORIZONTAL TO 1 VERTICAL. MAXIMUM FILL
- SLOPE SHALL BE 2 HORIZONTAL TO 1 VERTICAL.

| LOCATION | CUT (C.Y.) | FILL (C.Y.) | VERT. | DEPT |
|------------------------|------------|-------------|-------|------|
| RESIDENCE | 0 | 0 | | |
| ACCESSORY STRUCTURE | 0 | 0 | | |
| POOL/HARDSCAPE | 0 | 0 | | |
| LANDSCAPE | 7,618 | 1,761 | 2 | |
| DRIVEWAY | 0 | 0 | | |
| OFF SITE | 0 | 0 | | |
| TOTAL | 7,618 | 1,761 | 2 | |

NOTE: FILL VOLUMES INCLUDE 10% SHRINKAGE. EXCESS MATERIAL SHALL BE OFF HAULED TO A COUNTY APPROVED DUMP

- 7. NOTIFY SOILS ENGINEER TWO (2) DAYS PRIOR TO COMMENCEMENT OF ANY
- GRADING WORK TO COORDINATE THE WORK IN THE FIELD. ALL MATERIALS FOR FILL SHOULD BE APPROVED BY THE SOILS ENGINEER
- BEFORE IT IS BROUGHT TO THE SITE.
- 9. THE UPPER 6" OF THE SUBGRADE SOIL SHALL BE SCARIFIED, MOISTURE CONDITIONED AND COMPACTED TO A MINIMUM RELATIVE COMPACTION OF 95%
- 10. ALL AGGREGATE BASE MATERIAL SHALL BE COMPACTED TO A MINIMUM 95% **RELATIVE COMPACTION.** THE GEOTECHNICAL PLAN REVIEW LETTER MUST BE REVIEWED AND APPROVED BY THE COUNTY GEOLOGIST PRIOR TO FINAL APPROVAL BY THE COUNTY
- ENGINEER FOR BUILDING OCCUPANCY. 12. THE PROJECT GEOTECHNICAL ENGINEER SHALL PERFORM COMPACTION TESTING AND PRESENT THE RESULTS TO THE COUNTY ENGINEERING INSPECTOR PRIOR
- TO THE CONSTRUCTION OF ANY PAVED AREA. GRADING WORK BETWEEN OCTOBER 15TH AND APRIL 15TH IS AT THE
- DISCRETION OF THE SANTA CLARA COUNTY GRADING OFFICIAL. 14. TOTAL DISTURBED AREA FOR THE PROJECT 139,275 SF.
- WDID NO.PENDING.
- THE INSPECTOR MAY VERIFY THAT A VALID NOTICE OF INTENT (NOI) HAS BEEN ISSUED BY THE STATE AND THAT A CURRENT AND UP TO DATE STORM WATER POLLUTION PREVENTION PLAN (SWPPP) IS AVAILABLE ON SITE.

TREE PROTECTION

- 1. FOR ALL TREES TO BE RETAINED WITH A CANOPY IN THE DEVELOPMENT AREA OR INTERFACES WITH THE LIMITS OF GRADING FOR ALL PROPOSED OF RIGID TREE PROTECTIVE FENCING, CONSISTENT WITH THE COUNTY
- INTEGRATED LANDSCAPE GUIDELINES, AND INCLUDE THE FOLLOWING: FENCING SHOULD BE PLACED ALONG THE OUTSIDE EDGE OF THE DRIPLINE OF THE TREE OR GROVE OF TREES. THE FENCING SHALL BE MAINTAINED THROUGHOUT THE SITE
- CONSTRUCTION PERIOD AND SHALL BE INSPECTED PERIODICALLY FOR DAMAGE AND PROPER FUNCTION.
- FENCING SHALL BE REPAIRED, AS NECESSARY, TO PROVIDE A PHYSICAL BARRIER FROM CONSTRUCTION ACTIVITIES. SIGNAGE STATING, "WARNING- THIS FENCING SHALL NOT BE REMOVED **D**.
- WITHOUT PERMISSION FROM THE SANTA CLARA COUNTY PLANNING OFFICE (408) 299-5770. COUNTY OF SANTA CLARA TREE PROTECTION MEASURES MAY BE FOUND AT http://www.sccplanning.gov." SHALL BE PLACED ON THE TREE PROTECTIVE FENCING UNTIL FINAL OCCUPANCY.
- PRIOR TO COMMENCEMENT OF ANY CONSTRUCTION ACTIVITY. TREE PROTECTIVE FENCING SHALL BE SECURELY IN PLACED AND INSPECTED BY THE LAND
- DEVELOPMENT ENGINEERING INSPECTOR. SEE EXISTING TREE PROTECTION DETAILS FOR MORE INFORMATION.

- 1. DEVELOPER IS RESPONSIBLE FOR ALL NECESSARY DRAINAGE FACILITIES WHETHER SHOWN ON THE PLANS OR NOT AND HE OR HIS SUCCESSOR A) TO A MINIMUM DEPTH OF TWO FEET BELOW THE FINISHED GRADE OF 1. DRIVEWAY LOCATIONS SHALL BE AS SHOWN ON THE IMPROVEMENT PLANS WITH PROPERTY OWNERS ARE RESPONSIBLE FOR THE ADEQUACY AND CONTINUED CENTERLINE STATIONING. THE MINIMUM CONCRETE THICKNESS SHALL BE 6 MAINTENANCE OF THESE FACILITIES IN A MANNER WHICH WILL PRECLUDE ANY INCHES THROUGHOUT (WITH A MAXIMUM APPROACH SLOPE OF 1 1/4 INCHES HAZARD TO LIFE, HEALTH, OR DAMAGE TO ADJOINING PROPERTY, CONSISTENT WITH NPDES PERMIT CAS612008 / ORDER NO. R2-2009-0047 AND NPDES PFR FOOT) PERMIT CAS000004/ ORDER NO. 2013-0001-DWQ.
 - 2. ALL DRIVEWAY OR COMMON ACCESS ROAD SECTIONS IN EXCESS OF 15 LONGITUDINAL SLOPE MUST BE PAVED WITH A MINIMUM 2-INCH ASPHALT LIFT
 - 2. DROP INLETS SHALL BE COUNTY STANDARD TYPE 5 UNLESS OTHERWISE NOTED OR FULL DEPTH CONCRETE LIFT PRIOR TO ANY COMBUSTIBLE FRAMING. ON THE PLANS. THE DEVELOPER'S ENGINEER SHALL BE RESPONSIBLE FOR THE THE OWNER AND PRIME CONTRACTOR ARE RESPONSIBLE FOR MAINTAINING PROPER LOCATION OF DROP INLETS. WHERE STREET PROFILE GRADE EXCEEDS PROJECT SITE ACCESS AND NEIGHBORHOOD ACCESS FOR EMERGENCY VEHICLES 6% DROP INLETS SHALL BE SET AT 500 ANGLE CURB LINE TO ACCEPT WATER AND LOCAL RESIDENTS. OR AS SHOWN ON THE PLANS.
 - 4. ROADWAYS DESIGNATED AS NOT COUNTY MAINTAINED ROADS AS SHOWN ON THE PLAN WILL NOT BE ELIGIBLE FOR COUNTY MAINTENANCE UNTIL THE ROADWAYS ARE IMPROVED (AT NO COST TO THE COUNTY) TO THE PUBLIC MAINTENANCE ROAD STANDARDS APPROVED BY THE BOARD OF SUPERVISORS AND IN EFFECT AT SUCH TIME THAT THE ROADWAYS ARE CONSIDERED FOR ACCEPTANCE INTO THE COUNTY'S ROAD SYSTEM.
 - ALL WORK IN THE COUNTY ROAD RIGHT-OF-WAY REQUIRES AN ENCROACHMENT PERMIT FROM THE ROADS AND AIRPORTS DEPARTMENT. EACH INDIVIDUAL ACTIVITY REQUIRES A SEPARATE PERMIT - I.E. CABLE, ELECTRICAL, GAS. SEWER, WATER, RETAINING WALLS, DRIVEWAY APPROACHES, FENCES, LANDSCAPING, TREE REMOVAL, STORM DRAINAGE IMPROVEMENTS, ETC..
 - STREET LIGHTING
 - DEVELOPER AND/OR HIS AUTHORIZED REPRESENTATIVE.

SANITARY SEWER

- 1. THE SANITARY SEWER AND WATER UTILITIES SHOWN ON THESE PLANS ARE NOT PART OF THIS GRADING PERMIT AND ARE SHOWN FOR REFERENCE ONLY.
- ALL MATERIALS AND METHODS OF CONSTRUCTION OF SANITARY SEWERS SHALL CONFORM TO THE SPECIFICATIONS OF THE JURISDICTION INVOLVED. INSPECTION AFTERCONSTRUCTION. OF SANITARY SEWER WORK SHALL BE DONE BY SAID JURISDICTION.

PORTLAND CEMENT CONCRETE

1. CONCRETE USED FOR STRUCTURAL PURPOSES SHALL BE CLASS "A" (6 SACK PER CUBIC YARD) AS SPECIFIED IN THE STATE STANDARD SPECIFICATIONS. CONCRETE PLACED MUST DEVELOP A MINIMUM STRENGTH FACTOR OF 2800 PSI IN A SEVEN-DAY PERIOD. THE CONCRETE MIX DESIGN SHALL BE UNDER THE CONTINUAL CONTROL OF THE COUNTY INSPECTOR.

AIR QUALITY, LANDSCAPING AND EROSION CONTROL

- ALL VEHICLE SPEEDS ON UNPAVED ROADS SHALL BE LIMITED TO 15 MILES PFR HOUR. 8. ALL CONSTRUCTION EQUIPMENT SHALL BE MAINTAINED AND PROPERLY TUNED IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS. ALL EQUIPMENT SHALL BE CHECKED BY A CERTIFIED MECHANIC AND DETERMINED TO BE
- RUNNING IN PROPER CONDITION PRIOR TO OPERATION. 9. POST A SIGN THAT IS AT LEAST 32 SQUARE FEET MINIMUM 2 INCHES LETTER HEIGHT VISIBLE NEAR THE ENTRANCE OF CONSTRUCTION SITE THAT IDENTIFIES THE FOLLOWING REQUIREMENTS. OBTAIN ENCROACHMENT PERMIT FOR SIGN FROM ROADS DEPARTMENT OR OTHER APPLICABLE AGENCY IF REQUIRED.
- A. 15 MILES PER HOUR (MPH) SPEED LIMIT B. 5 MINUTES MAXIMUM IDLING TIME OF VEHICLES
- C. TELEPHONE NUMBER TO CONTACT THE BAY AREA AIR QUALITY MANAGEMENT DISTRICT REGARDING DUST COMPLAINTS. NOTE PHONE
- NUMBER OF THE BAY AREA AIR QUALITY MANAGEMENT DISTRICT AIR POLLUTION COMPLAIN HOTLINE OF 1-800-334-6367. 10. ALL FILL SLOPES SHALL BE COMPACTED AND LEFT IN A SMOOTH AND FIRM CONDITION CAPABLE OF WITHSTANDING WEATHERING.
- 11. ALL EXPOSED DISTURBED AREAS SHALL BE SEEDED WITH BROME SEED SPREAD AT THE RATE OF 5 LB. PER 1000 SQUARE FEET (OR APPROVED EQUAL). SEEDING AND WATERING SHALL BE MAINTAINED AS REQUIRED TO ENSURE GROWTH
- 12. ALL DITCHES SHALL BE LINED PER COUNTY STANDARD SD8. 13. ALL STORM DRAINAGE STRUCTURES SHALL BE INSTALLED WITH EFFECTIVE ENTRANCE & OUTFALL EROSION CONTROLS E.G. SACKED CONCRETE RIP-RAP. ENERGY DISSIPATERS SHALL BE INSTALLED AT ALL DITCH OUTFALLS. WHERE OUTFALLS ARE NOT INTO AN EXISTING CREEK OR WATER COURSE, RUNOFF SHALL BE RELEASED TO SHEET FLOW.
- 14. PRIOR TO GRADING COMPLETION AND RELEASE OF THE BOND, ALL GRADED AREAS SHALL BE RESEEDED IN CONFORMANCE WITH THE COUNTY GRADING ORDINANCE TO MINIMIZE THE VISUAL IMPACTS OF THE GRADE SLOPES AND REDUCE THE POTENTIAL FOR EROSION OF THE SUBJECT SITE. 15. PERMANENT LANDSCAPING SHOWN ON THE ATTACHED LANDSCAPE PLAN MUST BE INSTALLED AND FIELD APPROVED BY THE COUNTY PLANNING OFFICE PRIOR
- TO FINAL APPROVAL BY THE COUNTY ENGINEER, AND FINAL OCCUPANCY RELEASE BY THE BUILDING INSPECTION OFFICE. 16. THE OWNER SHALL PREPARE AND PRESENT A WINTERIZATION REPORT TO THE COUNTY INSPECTOR FOR REVIEW PRIOR TO OCTOBER 15TH OF EVERY YEAR. 17 THE OWNER. CONTRACTOR. AND ANY PERSON PERFORMING CONSTRUCTION ACTIVITIES SHALL INSTALL AND MAINTAIN CONSTRUCTION BEST MANAGEMENT PRACTICES (BMPS) ON THE PROJECT SITE AND WITHIN THE SANTA CLARA COUNTY ROAD RIGHT-OF-WAY THROUGHOUT THE DURATION OF THE CONSTRUCTION AND UNTIL THE ESTABLISHMENT OF PERMANENT STABILIZATION AND SEDIMENT CONTROL TO PREVENT THE DISCHARGE OF POLLUTANTS INCLUDING SEDIMENT, CONSTRUCTION MATERIALS, EXCAVATED MATERIALS, AND WASTE INTO THE SANTA CLARA COUNTY RIGHT-OF-WAY, STORM SEWER WATERWAYS, ROADWAY INFRASTRUCTURE, BMPS SHALL INCLUDE, BUT NOT BE
- LIMITED TO THE FOLLOWING A. PREVENTION OF POLLUTANTS IN STORM WATER DISCHARGES FROM THE CONSTRUCTION SITE AND THE CONTRACTOR'S MATERIAL AND EQUIPMENT LAYDOWN / STAGING AREAS.
- B. PREVENTION OF TRACKING OF MUD, DIRT, AND CONSTRUCTION
- MATERIALS ONTO THE PUBLIC ROAD RIGHT-OF-WAY. PREVENTION OF DISCHARGE OF WATER RUN-OFF DURING DRY AND WET WEATHER CONDITIONS ONTO THE PUBLIC ROAD RIGHT-OF-WAY.
- 18. THE OWNER, CONTRACTOR, AND ANY PERSON PERFORMING CONSTRUCTION ACTIVITIES SHALL ENSURE THAT ALL TEMPORARY CONSTRUCTION FACILITIES. INCLUDING BUT NOT LIMITED TO CONSTRUCTION MATERIALS, DELIVERIES, HAZARDOUS AND NON-HAZARDOUS MATERIAL STORAGE, EQUIPMENT, TOOLS, PORTABLE TOILETS. CONCRETE WASHOUT. GARBAGE CONTAINERS. LAYDOWN YARDS, SECONDARY CONTAINMENT AREAS, ETC. ARE LOCATED OUTSIDE THE SANTA CLARA COUNTY ROAD RIGHT-OF-WAY. EROSION CONTROL PLAN IS A GUIDE AND SHALL BE AMENDED AS NECESSARY TO PREVENT EROSION AND ILLICIT DISCHARGES ON A YEAR AROUND BASIS,
- DEPENDING ON THE SEASON, WEATHER, AND FIELD CONDITIONS. EROSION CONTROL MEASURES IN ADDITION TO THOSE NOTED IN THE PERMITTED PLANS MAY BE NECESSARY. FAILURE TO INSTALL SITE SITE AND SITUATIONALY APPROPRIATE EROSION CONTROL MEASURES MAY RESULT IN VIOLATIONS, FINES. AND A STOPPAGE OF WORK.

STORM DRAINAGE AND STORMWATER MANAGEMENT

- WHERE CULVERTS ARE INSTALLED THE DEVELOPER SHALL BE RESPONSIBLE FOR GRADING THE OUTLET DITCH TO DRAIN TO AN EXISTING SWALE OR TO AN OPEN AREA FOR SHEET FLOW.
- UPON INSTALLATION OF DRIVEWAY CONNECTIONS. PROPERTY OWNERS SHALL PROVIDE FOR THE UNINTERRUPTED FLOW OF WATER IN ROADSIDE DITCHES. 5. THE COUNTY SHALL INSPECT UNDERGROUND DRAINAGE IMPROVEMENTS AND STORMWATER MANAGEMENT FEATURES PRIOR TO BACKFILL.

AS-BUILT PLANS STATEMENT

THIS IS A TRUE COPY OF THE AS-BUILT PLANS. THERE (____ WERE) (____ WERE NOT) MINOR FIELD CHANGES - MARKED WITH THE SYMBOL (^). THERE (___WERE) WERE NOT) PLAN REVISIONS INDICATING SIGNIFICANT CHANGES REVIEWED BY THE COUNTY ENGINEER AND MARKED WITH THE SYMBOL \triangle .

NOTE: THIS STATEMENT IS TO BE SIGNED BY THE PERSON AUTHORIZED BY THE COUNTY ENGINEER TO PERFORM THE INSPECTION WORK. A REPRODUCIBLE COPYOF THE AS-BUILT PLANS MUST BE FURNISHED TO THE COUNTY ENGINEER

SIGNATURE

GEOTECHNICAL ENGINEER OBSERVATION

1. A CONSTRUCTION OBSERVATION LETTER FROM THE RESPONSIBLE GEOTECHNICAL ENGINEER AND ENGINEERING GEOLOGIST DETAILING CONSTRUCTION OBSERVATIONS AND CERTIFYING THAT THE WORK WAS DONE IN ACCORDANCE WITH THE RECOMMENDATIONS IN THE GEOTECHNICAL AND GEOLOGIC REPORTS SHALL BE SUBMITTED PRIOR TO THE GRADING COMPLETION AND RELEASE OF THE BOND.



COUNTY LOCATION MAP



EXISTING TREE PROTECTION DETAILS

- PRIOR TO THE COMMENCEMENT OF ANY GRADING, TREE PROTECTIVE FENCING SHALL BE IN PLACE IN ACCORDANCE WITH THE TREE PRESERVATION PLAN AND INSPECTED BY A CERTIFIED ARBORIST. THE ARBORIST SHALL MONITOR CONSTRUCTION ACTIVITY TO ENSURE THAT THE TREE PROTECTION MEASURES ARE IMPLEMENTED AND ADHERED TO DURING CONSTRUCTION. THIS CONDITION
- SHALL BE INCORPORATED INTO THE GRADING PLANS 2. FENCE SHALL BE MINIMUM 5 FEET TALL CONSTRUCTED OF STURDY MATERIAL
- (CHAIN-LINK OR EQUIVALENT STRENGTH/ DURABILITY). 3. FENCE SHALL BE SUPPORTED BY VERTICAL POSTS DRIVEN 2 FEET (MIN) INTO
- THE GROUND AND SPACED NOT MORE THAN 10 FEET APART. 4. TREE FENCING SHALL BE MAINTAINED THROUGHOUT THE SITE DURING THE CONSTRUCTION PERIOD. INSPECTED PERIODICALLY FOR DAMAGE AND PROPER
- FUNCTION, REPAIRED AS NECESSARY TO PROVIDE A PHYSICAL BARRIER FROM CONSTRUCTION ACTIVITIES, AND REMAIN IN PLACE UNTIL THE FINAL INSPECTION.
- 5. A SIGN THAT INCLUDES THE WORDS, "WARNING: THIS FENCE SHALL NOT BE REMOVED WITHOUT THE EXPRESSED PERMISSION OF THE SANTA CLARA COUNTY PLANNING OFFICE," SHALL BE SECURELY ATTACHED TO THE FENCE IN A VISUALLY PROMINENT LOCATION.

| COUNTY OF SANTA CLARA D | EPT. OF ROADS AND AIRPORTS |
|-------------------------|----------------------------|
| ISSUED BY: | DATE: |
| ENCROACHMENT PERMIT NO. | |

NO WORK SHALL BE DONE IN THE COUNTY'S RIGHT-OF-WAY WITHUOT AN ENCROACHEMENT PERMIT, INCLUDING THE STAGING OF CONSTRUCTION MATERIAL AND THE PLACEMENT OF PORTABLE TOILETS.

ENGINEER'S STATEMENT

I HEREBY STATE THAT THESE PLANS ARE IN COMPLIANCE WITH ADOPTED COUNTY STANDARDS. THE APPROVED TENTATIVE MAP (OR PLAN) AND CONDITIONS OF APPROVAL PERTAINING THERETO DATED FILE(S) NO.

SIGNATURE

COUNTY ENGINEER'S NOTE

ISSUANCE OF A PERMIT AUTHORIZING CONSTRUCTION DOES NOT RELEASE THE DEVELOPER. PERMITTEE OF ENGINEER FROM RESPONSIBILITY FOR THE CORRECTION OF ERRORS OR OMISSIONS CONTAINED IN THE PLANS. IF, DURING THE COURSE OF CONSTRUCTION, THE PUBLIC INTEREST REQUIRES A MODIFICATION OF (OR DEPARTURE FROM) THE SPECIFICATIONS OF THE PLANS, THE COUNTY SHALL HAVE THE AUTHORITY TO REQUIRE THE SUSPENSION OF WORK, AND THE NECESSARY MODIFICATION OR DEPARTURE AND TO SPECIFY THE MANNER IN WHICH THE SAME IS TO BE MADE.

DATE

DATE

<u>R.C.F. NO.</u>

LACROSSE PRACTICE FIELD

STANFORD UNIVERSITY STANFORD CALIFORNIA



VICINITY MAP NOT TO SCALE

| PROJECT INCLUDES CONSTRUCTION OF NEW LACROSSE FIELD. THE SCOPE OF WOR IDES SITE GRADING, INSTALLATION OF UTILITIES, AND REMOVAL OF EXISTING TREE |
|---|
| |
| |
| |
| |
| |
| |
| |
| |
| |
| |
| COUNTY OF SANTA CLARA LAND DEVELOPMENT ENGINEERING & SURVEYING |
| RADING / DRAINAGE PERMIT NO |
| SUED BY: DATE: |
| |
| |

SCOPE OF WORK

THIS

INCI

R.C.E. NO.

EXPIRATION DATE

EXPIRATION DATE

| | SHEET INDEX | | | | |
|--|---|--|--|--|--|
| C—1.0 | COUNTY COVER SHEET | | | | |
| C-1.1 | CONSTRUCTION NOTES | | | | |
| C-2.0 | TOPOGRAPHIC SURVEY | | | | |
| C-3.0 | DEMOLITION/TREE REMOVAL PLAN | | | | |
| C-3.1 | DEMOLITION/TREE REMOVAL NOTES | | | | |
| C-4.0 | GRADING AND DRAINAGE PLAN | | | | |
| C-4.1 | GRADING SECTIONS | | | | |
| C—5.0 | UTILITY PLAN | | | | |
| C-6.0 | EROSION CONTROL PLAN | | | | |
| C-6.1 - C-6.2 | COUNTY BMP NOTES | | | | |
| C-7.0 | FIRE ACCESS PLAN | | | | |
| C-8.0 | STORMWATER MANAGEMENT PLAN | | | | |
| C-9.0 | CONSTRUCTION SITE/LOGISTICS SAFETY PLAN | | | | |
| L—1.01 | LANDSCAPE PLAN | | | | |
| L-1.02 | LANDSCAPE NOTES | | | | |
| E—1 | PROJECT SUMMARY | | | | |
| E-2 - E-6 | ILLUMINATION SUMMARY | | | | |
| E-7 | EQUIPMENT LAYOUT | | | | |
| E-8 | POLE CONFIGURATION DRAWING | | | | |
| E-9 | EXISTING LIGHTING PLAN | | | | |
| E—10 | EXISTING LIGHTING SPECIFICATIONS | | | | |
| ENGINEER'S NAME: <u>NATE DICKINSON</u> | | | | | |
| ADDRESS: | 1700 S. WINCHESTER BLVD. | | | | |
| - | CAMPBELL, CA 95008 | | | | |
| PHONE NO. | PHONE NO. <u>408–636–0900</u> | | | | |
| FAX NU. | <u>408–636–0900</u> | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| levision 1 | Date APN Sheet | | | | |
| Devicier ? | | | | | |

Date

Date

Co. File

of 27

Revision 2

Revision 3

ABBREVIATIONS

| ? | _ | AGGREGATE BASE ASPHALT CONCRETE |
|--------------------|--------|--|
|) 2A | _ _ | AREA DRAIN AMERICANS WITH DISABILITIES ACT |
|) | _ | AGGREGATE SUBBASE BEGINNING OF CURVE |
| P DC DC | _ | BACK FLOW PREVENTOR BUILDING CORNER BUILDING |
| | - | BOILDING BOTTOM OF DOCK BOLLARD |
|) S W | _ | BOTTOM OF STEP FG @ BOTTOM OF WALL |
| IC V | _ | BEGIN VERTICAL CURVE BACK OF WALK |
| :G | _ | CONCRETE OR CIVIL CURB AND GUTTER CATCH BASIN |
| ס | _ | COMBINATION INLET CAST IRON PIPE |
| IP | _ | CENTER LINE OR CLASS CORRUGATED METAL PIPE |
|) // | _ | CLEANOUT CURB OPENING INLET |
| NC NST | _ | CONCRETE CONSTRUCTION OR CONSTRUCT |
| DA | _ | DOUBLE CHECK DETECTOR ASSEMBLY |
| o M | - | DUCTILE IRON PIPE DOMESTIC |
| ý VG | _ | DOMESTIC WATER DRAWING |
| | _ | EAST END OF CURVE |
| | _ | EDGE OF PAVEMENT END OF RETURN |
| C EV ' FYIST | _ | END VERTICAL CURVE ELEVATION EXISTING |
| с, <i>с</i> | - | FACE OF CURB FIRE DEPARTMENT CONNECTION |
| • | _ | FINISHED FLOOR FINISHED GRADE |
| | _ | FIRE HYDRANT FLOW LINE |
| UND | _ | FOUNDATION FINISHED SURFACE |
| / | _ | FIRE WATER GROUND FI EVATION |
|) / | _ | GRADE BREAK GATE VALVE |
| R | _ | ACCESSIBLE RAMP HIGH POINT |
| V | _ | INVERT ELEVATION JOINT POLE |
| , | _ | JOINT TRENCH LIP OF GUTTER |
| A | _ | LOW POINT LANDSCAPE ARCHITECT |
| TP | _ | MAXIMUM MECHANICAL/ELECTRICAL/PLUMBING |
| / V | _ | MANHOLE MINIMUM MIDDOINT OF VERTICAL OURVE |
| N N | _ | MIDPOINT OF VERTICAL CURVE MONUMENT NORTH |
| . <i>C</i> . | - | NORTH NOT IN CONTRACT NUMBER |
| 3 | _ | NOT TO SCALE PAVEMENT ELEVATION |
| хс | - | PORTLAND CEMENT CONCRETE / POINT OF CONTINUOUS CURVATURE |
| / | _ | POST INDICATOR VALVE PROPERTY LINE |
| IH DC | _ | POWER MANHOLE POINT ON CURVE |
| ,)C | _ | POWER POLE POINT OF REVERSE CURVATURE |
| | _ | POLIVINIL CHLORIDE PIPE RADIUS PELATIVE COMPACTION |
| , ,p ,pa | _ | RELATIVE COMPACTION REINFORCED CONCRETE PIPE REDUCED PRESSURE PRINCIPLE ASSEMBLY |
| W | _ | RIGHT OF WAY SLOPE OR SOUTH |
| 4. <i>D</i> . | _ | SEE ARCHITECTURAL DRAWINGS SEDIMENT BASIN |
|) AD | _ | STORM DRAIN STORM DRAIN AREA DRAIN |
| E. <i>D</i> . | _ _ | SEE ELECTRICAL DRAWINGS SILT FENCE |
| | _ | SUBGRADE SEE LANDSCAPE DRAWINGS |
| N.D. IH | _ | SEE MECHANICAL DRAWINGS SIGNAL MANHOLE |
| | - | SEE PLUMBING DRAWINGS SANITARY SEWER SANITARY SEWER MANHOLE |
| D D | - | STATION STANDARD |
| Ŵ | _ | SIDEWALK TOP OF CURB |
| D | _ | TRENCH DRAIN TOP OF DOCK |
| E S | _ | TOE OF SLOPE TOP OF STAIR |
| W | _ | FG @ TOP OF WALL TOP OF SLAB |
| Þ W | _ | TYPICAL UNLESS OTHERWISE NOTED |
| 6 | _ | UNDERGROUND VERTICAL CURVE |
| ! , | _ _ | WATER METER WATER VALVE |
| Æ | _ | WEST WELDED WIRE FABRIC |

– WITH

LEGEND

SAWCUT AND CONFORM LINE RETAINING WALL A.C. PAVEMENT CONC. VALLEY GUTTER CONC. SIDEWALK OR PAD 6" CURB & GUTTER EDGE OF A.C. PAVEMENT 6" VERTICAL CURB Center line SANITARY SEWER MAIN STORM DRAIN MAIN PERFORATED PIPE WATER MAIN FIRE WATER MAIN DOMESTIC WATER MAIN CHILLED WATER MAIN IRRIGATION LINE HOT WATER SUPPLY & RETURN STEAM LINE TRENCH DRAIN CONDENSATE RETURN FLOW LINE CHAIN LINK FENCE GAS MAIN ELECTRIC AND SIGNAL DUCT BANK OVERHEAD ELECTRIC LINE UNDERGROUND ELECTRIC LINE STREET LIGHT CONDUIT CONTOUR ELEVATION LINE SPOT ELEVATION DIRECTION OF SLOPE GAS METER GAS VALVE WATER METER WATER VALVE FIRE HYDRANT BACK FLOW PREVENTOR POST INDICATOR VALVE FIRE DEPARTMENT CONNECTION WATER LINE TEE CAP AND PLUG END AIR RELEASE VALVE SIGN ACCESSIBLE RAMP CONCRETE THRUST BLOCK REDUCER SANITARY SEWER MANHOLE SANITARY SEWER CLEANOUT STORM DRAIN MANHOLE STORM DRAIN AREA DRAIN STORM DRAIN CATCH BASIN STORM DRAIN CURB INLET STORM DRAIN CLEANOUT ELECTROLIER JOINT POLE OVERLAND RELEASE

CONSTRUCTION DETAIL REFERENCE



SHEET REFERENCE

(C-5.2)

SURVEY MONUMENT PRESERVATION

- 1. THE LANDOWNER / CONTRACTOR MUST PROTECT AND ENSURE THE PERPETUATION OF SURVEY MONUMENTS AFFECTED BY CONSTRUCTION ACTIVITIES.
- 2. PRIOR TO THE START OF CONSTRUCTION, THE CONTRACTOR SHALL LOCATE, STAKE, AND FLAG OR OTHERWISE IDENTIFY WITH PAINT OR OTHER MARKINGS ALL PERMANENT SURVEY MONUMENTS OF RECORD AND ANY UNRECORDED MONUMENTS THAT ARE DISCOVERED THAT ARE WITHIN 50 FEET OF THE CONSTRUCTION ACTIVITY.
- 3. THE LANDOWNER, CONTRACTOR AND/OR ANY PERSON PERFORMING CONSTRUCTION ACTIVITIES THAT WILL OR MAY DISTURB AN EXISTING MONUMENT, CORNER STAKE, OR ANY OTHER PERMANENT SURVEYED MONUMENT SHALL CAUSE TO HAVE A LICENSED LAND SURVEYOR OR CIVIL ENGINEER, AUTHORIZED TO PRACTICE SURVEYING, ENSURE THAT A CORNER RECORD AND/OR RECORD OF SURVEY ARE FILED WITH THE COUNTY SURVEYOR'S OFFICE PRIOR TO DISTURBING SAID MONUMENTS AND RESET PERMANENT MONUMENT(S) IN THE SURFACE OF THE NEW CONSTRUCTION OR SET A WITNESS MONUMENT(S) TO PERPETUATE THE LOCATION IF ANY PERMANENT MONUMENT COULD BE DESTROYED, DAMAGED, COVERED, DISTURBED, OR OTHERWISE OBLITERATED. THE LICENSED LAND SURVEYOR OR CIVIL ENGINEER SHALL FILE A CORNER RECORD OR RECORD OF SURVEY WITH COUNTY SURVEYOR PRIOR TO FINAL ACCEPTANCE OF THE PROJECT BY THE LAND DEVELOPMENT ENGINEERING INSPECTOR.

GRADING NOTES

- 1. PROVIDE POSITIVE SURFACE DRAINAGE AWAY FROM ALL STRUCTURES BY SLOPING ALL HARDSCAPE SURFACES AT 2% AND VEGETATED SURFACES AT 5% AWAY FROM STRUCTURES UNLESS OTHERWISE NOTED ON PLANS.
- 2. ROUGH GRADING TO BE WITHIN 0.1' AND FINISH GRADES ARE TO BE WITHIN 0.05', HOWEVER CONTRACTOR SHALL NOT CONSTRUCT ANY IMPROVEMENTS THAT WILL CAUSE WATER TO POND OR NOT MEET REQUIREMENTS IN GRADING NOTE #1 OR THE ADA REQUIREMENTS BELOW. DO NOT ADJUST GRADES ON THIS PLAN WITHOUT PRIOR WRITTEN APPROVAL OF THE ENGINEER/ARCHITECT.
- 3. THE CONTRACTOR SHALL EXERCISE EXTREME CARE TO CONFORM TO THE LINES, GRADES, SECTIONS, AND DIMENSIONS AS SET FORTH ON THESE PLANS. ALL GRADED AREAS SHALL CONFORM TO THE VERTICAL ELEVATIONS SHOWN WITH A TOLERANCE OF ONE-TENTH OF A FOOT. WHERE GRADED AREAS DO NOT CONFORM TO THESE TOLERANCES, THE CONTRACTORS SHALL BE REQUIRED TO DO CORRECTIVE GRADING, AT NO EXTRA COST TO THE CLIENT.
- 4. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO CONFIRM THE GROUND ELEVATIONS AND OVERALL TOPOGRAPHY OF THE SITE PRIOR TO THE START OF CONSTRUCTION AS TO THE ACCURACY BETWEEN THE WORK SET FORTH ON THESE PLANS AND THE WORK IN THE FIELD. ANY DISCREPANCIES SHALL BE IMMEDIATELY BROUGHT TO THE ATTENTION OF THE CONSTRUCTION MANAGER AND CIVIL ENGINEER IN WRITING PRIOR TO START OF CONSTRUCTION WHICH MAY REQUIRE CHANGES IN DESIGN AND/OR AFFECT THE EARTHWORK QUANTITIES.
- 5. ALL GRADING SHALL CONFORM TO APPROVED SPECIFICATIONS PRESENTED HEREON OR ATTACHED HERETO. ALL GRADING WORK SHALL BE OBSERVED AND APPROVED BY THE SOILS ENGINEER. THE SOILS ENGINEER SHALL BE NOTIFIED AT LEAST 48 HOURS BEFORE BEGINNING ANY GRADING. UNOBSERVED AND UNAPPROVED GRADING WORK SHALL BE REMOVED AND REDONE AT THE CONTRACTORS EXPENSE.
- 6. THE CONTRACTOR SHALL BE RESPONSIBLE TO REPAIR OR REPLACE ANY EXISTING IMPROVEMENTS OF UNDERGROUND FACILITIES DAMAGED DURING THE CONSTRUCTION PERIOD.
- 7. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL ENCROACHMENT, EXCAVATION, CONCRETE, ELECTRICAL, PLUMBING, ETC. PERMITS NECESSARY PRIOR TO BEGINNING CONSTRUCTION FOR ANY WORK.
- 8. AREAS LACKING TOPOGRAPHIC INFORMATION (ELEVATIONS) HAVE BEEN INTERPOLATED USING STANDARD ENGINEERING METHODS. CONTRACTOR SHALL FIELD VERIFY ALL ELEVATIONS AT CONFORMS PRIOR TO COMMENCEMENT OF CONSTRUCTION AND REPORT BACK ANY DISCREPANCIES TO THE CIVIL ENGINEER.
- 9. ADJUST ANY MANHOLE OR UTILITY STRUCTURES TO PROPOSED GRADE PRIOR TO INSTALLING FINAL LIFT OF AC OR POURING CONCRETE.
- 10. ALL EXPOSED DISTURBED AREAS SHALL HAVE 2" OF SALVAGED TOPSOIL SPREAD ACROSS TOP SURFACE TO REESTABLISH LOCAL VEGETATION. THIS PROJECT DOES NOT USE ANY PLANTING OR IRRIGATION.
- 11. SITE IS KNOWN TO HAVE NATURALLY OCCURRING ASBESTOS, CONTRACTOR TO COMPLY WITH BAAQMD REQUIREMENTS AND THE REQUIREMENTS OF THE ASBESTOS MITIGATION PLAN. CONTRACTOR SHALL ALSO INCLUDE EMPLOYEE SAFETY MITIGATION MEASURES IN BID.

ADA NOTES

- 1. ALL HARDSCAPE ALONG THE ADA PATH OF TRAVEL SHALL BE IN CONFORMANCE WITH TITLE 24 OF THE CALIFORNIA ADMINISTRATIVE CODE.
- 2. SLOPED WALKS ALONG THE DESIGNATED ADA PATH OF TRAVEL SHALL NOT EXCEED A SLOPE OF 1:20 (5%) WITHOUT HANDRAILS. THE MAXIMUM SLOPE WITH HANDRAILS OR FOR CURB RAMPS IS 1:12 (8.33%). LEVEL LANDINGS ARE REQUIRED AT THE TOP AND BOTTOM OF ALL SLOPED WALKWAYS AND RAMPS.

CONSTRUCTION GENERAL NOTES

- 1. THE BAY AREA AIR QUALITY MANAGEMENT DISTRICT (BAAQMD) HAS IDENTIFIED A SET OF FEASIBLE PM10 CONTROL MEASURES FOR ALL CONSTRUCTION ACTIVITIES. THESE CONTROL MEASURES, AS PREVIOUSLY REQUIRED IN THE PROGRAM EIR, SHALL BE ADHERED TO DURING ALL CONSTRUCTION ACTIVITIES.
- A.WATER ALL ACTIVE CONSTRUCTION AREAS AT LEAST TWICE DAILY; B.COVER ALL TRUCKS HAULING SOIL, SAND, AND OTHER LOOSE MATERIALS OR REQUIRE ALL TRUCKS TO MAINTAIN AT LEAST TWO FEET OF FREEBOARD;
- C. PAVE, APPLY WATER THREE TIMES DAILY, OR APPLY (NON-TOXIC) SOIL STABILIZERS ON ALL UNPAVED ACCESS ROADS, PARKING AREAS AND STAGING AREAS AT CONSTRUCTION SITES;
- D. SWEEP DAILY (WITH WATER SWEEPERS) ALL PAVED ACCESS ROADS, PARKING AREAS AND STAGING AREAS AT CONSTRUCTION SITES;
- E. SWEEP STREETS DAILY (WITH WATER SWEEPERS) IF VISIBLE SOIL MATERIAL IS CARRIED ONTO ADJACENT PUBLIC STREETS; E HYDROSEED OR ARDI Y (NON-TOYIC) SOIL STABILIZERS TO INACTI
- F. HYDROSEED OR APPLY (NON-TOXIC) SOIL STABILIZERS TO INACTIVE CONSTRUCTION AREAS (PREVIOUSLY GRADED AREAS INACTIVE FOR TEN DAYS OR MORE);
- G. ENCLOSE, COVER, WATER TWICE DAILY OR APPLY (NON-TOXIC) SOIL BINDERS TO EXPOSED STOCKPILES (DIRT, SAND,);
- H. LIMIT TRAFFIC SPEEDS ON UNPAVED ROADS TO 15 MPH; I. INSTALL FIBER ROLLS, SANDBAGS OR OTHER EROSION CONTROL MEASURES TO PREVENT SILT RUNOFF TO PUBLIC ROADWAYS;
- J. REPLANT VEGETATION IN DISTURBED AREAS AS QUICKLY AS POSSIBLE; K INSTALL WHEEL WASHERS FOR ALL EXISTING TRUCKS OF WAS
- K. INSTALL WHEEL WASHERS FOR ALL EXISTING TRUCKS, OR WASH OFF THE TIRES OF TRACKS OF ALL TRUCKS AND EQUIPMENT LEAVING THE SITE; AND
- L. SUSPEND EXCAVATION AND GRADING ACTIVITY WHEN WINDS (INSTANTANEOUS GUSTS) EXCEED 25 MPH."

2. ALL CONSTRUCTION CONTRACTORS SHALL PROPERLY MAINTAIN THE EQUIPMENT AND WHERE FEASIBLE, USE "CLEAN FUEL" EQUIPMENT AND EMISSIONS CONTROL TECHNOLOGY (E.G., CNG FIRED ENGINES, CATALYTIC CONVERTERS, PARTICULATE TRAPS, ETC.). MEASURES TO REDUCE DIESEL EMISSION WOULD BE CONSIDERED FEASIBLE WHEN THEY ARE CAPABLE OF BEING USED ON EQUIPMENT WITHOUT INTERFERING SUBSTANTIALLY WITH EQUIPMENT PERFORMANCE.

TREE PROTECTION NOTES

- 1. THE GENERAL CONTRACTOR SHALL TAKE THE FOLLOWING STEPS TO PRESERVE AND PROTECT ALL EXISTING TREES SHOWN TO REMAIN:
- A. PRIOR TO COMMENCEMENT OF DEMOLITION, GRADING AND CONSTRUCTION, TEMPORARY FENCING SHALL BE INSTALLED AT THE DRIP LINE OF EACH TREE TO BE PRESERVED. REFER TO DETAIL, FENCED AREAS SHALL NOT BE VIOLATED DURING CONSTRUCTION.
- B. ALL EXISTING ON SITE TREES INDICATED TO REMAIN SHALL BE TRIMMED BY A LICENSED ARBORIST FOUR WEEKS PRIOR TO COMMENCEMENT OF DEMOLITION OF GRADING OPERATIONS. ALL BROKEN OR BRUISED BRANCHES AND DEAD WOOD SHALL BE REMOVED. ALL CUTS OVER ¾" DIAMETER SHALL BE PAINTED WITH "TREE SEAL" OR APPROVED EQUAL. IN NO CASE SHALL ANY TREE BE TOPPED.
- C. ALL EXISTING ON SITE TREES INDICATED TO REMAINS SHALL BE FERTILIZED BY ROOT INJECTION BY A LICENSED ARBORIST FOUR WEEKS PRIOR TO COMMENCEMENT OF GRADING OR DEMOLITION OPERATIONS.
- 2. ALL EXISTING ON-SITE TREES INDICATED TO REMAIN SHALL BE PRESERVED AND PROTECTED DURING CONSTRUCTION. NO GRADING IS PERMITTED WITHIN THE DRIP-LINE OF ANY TREE INDICATED TO REMAIN. NO DEBRIS OR MATERIALS SHALL BE STOCKPILED AROUND THE BASE OF THE TREES. NO TRADESMAN SHALL DUMP DEBRIS OR FLUIDS WITHIN THE DRIP-LINE OF ANY TREES (PLASTER, PAINT, THINNER, ETC.). ALL TREES SHALL BE FENCED BY THE GENERAL CONTRACTOR TO AVOID COMPACTION OF THE TREE'S ROOT SYSTEM AND DAMAGE TO THE BARK. THE FENCE SHALL BE SIX FEET HIGH, AND EXTEND OUT TO THE DRIP-LINE OF THE TREE.
- 3. ALL EXISTING ON-SITE TREES INDICATED TO REMAIN SHALL BE WATERED BY THE GENERAL CONTRACTOR CONTINUOUSLY DURING THE COURSE OF CONSTRUCTION. IF POTABLE WATER IS NOT AVAILABLE ON THE SITE, A WATERING TRUCK SHALL BE EMPLOYED TO ACCOMPLISH THE WATERING.
- 4. DO NOT DISTURB SURFACE SOIL WITHIN TREE DRIP-LINE EXCEPT AS MANDATED BY CONSTRUCTION PLANS.
- 5. DURING PERIODS OF EXTENDED DROUGHT, SPRAY WOAK TREES TO REMOVE ACCUMULATED CONSTRUCTION.
- 6. GRADE IN LINES RADIAL TO THE EXISTING TREE RATHER THAN TANGENTIAL. IF ROOTS ARE ENCOUNTERED WHILE GRADING, CUT THEM CLEANLY WITH A SAW. <u>DO NOT RIP THEM WITH GRADING EQUIPMENT.</u>
- 7. DO NOT ATTEMPT DEMOLITION OF TREES WITH GRADING EQUIPMENT WHEN TREES THAT ARE TO BE PRESERVED ARE IN THE VICINITY.

TREE REMOVAL NOTES

- 1. THE LOCATION OF ALL SERVICE RUNS SUCH AS WATER SUPPLY, SEWER, ELECTRICITY, TELEPHONES, CABLE, GAS, STORM DRAIN LINES, ETC. SHALL BE ASCERTAINED BEFORE TREE REMOVAL WORK IS STARTED. WHERE SUCH LINES WILL BE AFFECTED BY TREE REMOVAL, OR WHERE TREE REMOVAL MACHINERY WILL BE WORKING NEARBY, LINES SHOULD BE CAREFULLY SEALED OFF, PROTECTED OR DIVERTED. IT IS THE CONTRACTOR'S RESPONSIBILITY TO TAKE NECESSARY PRECAUTIONARY ACTIONS.
- 2. REMOVE ONLY THOSE TREES INDICATED ON THIS PLAN TO BE REMOVED. TREES INDICATED TO BE REMOVED SHALL HAVE ALL ROOTS AND STUMP REMOVED TO A DEPTH OF 24" BELOW GRADE.

STANFORD UNIVERSITY

Project Name: Lacrosse Practice Field Project Address: 657 Masters Mall, Stanford CA. 94305 Quad/ Bldg. Number: 09-379



ISSUES AND REVISIONS

DESCRIPTION

08.13.24 ASA RESUBMITTAL

ASA SUBMITTAL

NO. DATE

03.18.24

PROJECT NUMBER

SHEET TITLE

CONSTRUCTION NOTES

SCALE

N.T.S.

SYMBOLS & ABBREVIATIONS

GAS METER GM G AD AREA DRAIN — — — — — — BUILDING OVERHANG HARDSCAPE ELEC LIGHT BAY BAY TREE -Ŵ-HE \triangleleft IRON FENCE BFP BACK FLOW PREVENTOR LANDSCAPE BLDC BUILDING CORNER L/S BLDL BUILDING LINE OVERHANG OH PAVEMENT BOL 8 BOLLARD ~~~~~ BOW WALL BOTTOM OF PEPPER TREE PEPPER BACK OF WALK BW PINE PINE TREE CATCH BASIN CB RDWD REDWOOD TREE CHKSHT CONTROL CHECKSHOT SDMH \bigcirc STORM DRAIN MANHOLE SIGN CNPT CONTROL POINT -0-SIGNS ⊿ SSCO 0 SANITARY CLEANOUT CONC CONCRETE SSMH Å. SANITARY MANHOLE DI DRAIN INLET STREET LIGHT LAMP NO ARM STL EΡ EDGE OF PAVEMENT STL-S STREET LIGHT SINGLE ARM o—☆ E EPB ELECTRIC PULLBOX STPB S STREET LIGHT PULLBOX EUC EUCALYPTUS TREE <123 J SIDEWALK SW FDCNPT \triangle FOUND CONTROL POINT ∞<u>123.45</u> <SIZE>TYPE/<TAG NUMBER> TRANS TRANSFORMER BUILDING FINISHED FLOOR FF TOP OF CURB TC FG@DOOR FINISHED GRADE AT DOOR TOW TOP OF WALL Q FH FIRE HYDRANT TREE TREE SYMBOL FLOW LINE WM . 🖾 WATER METER FNC FENCE wv 🕅 WATER VALVE GROUND WVLT WATER VAULT



UNDERGROUND UTILITY NOTE

THE TYPES, LOCATIONS, SIZES AND/OR DEPTHS OF EXISTING UNDERGROUND UTILITIES AS SHOWN ON THIS TOPOGRAPHIC SURVEY ARE APPROXIMATE AND WERE OBTAINED FROM SOURCES OF VARYING RELIABILITY. ONLY ACTUAL EXCAVATION WILL REVEAL THE TYPES, EXTENT, SIZES, LOCATIONS AND DEPTHS OF SUCH UNDERGROUND UTILITIES. A REASONABLE EFFORT HAS BEEN MADE TO LOCATE AND DELINEATE ALL KNOWN UNDERGROUND UTILITIES. HOWEVER, THE ENGINEER CAN ASSUME NO RESPONSIBILITY FOR THE COMPLETENESS OR ACCURACY OF ITS DELINEATION OF SUCH UNDERGROUND UTILITIES WHICH MAY BE ENCOUNTERED, BUT WHICH ARE NOT SHOWN ON THIS SURVEY.



30'



CHURCHILL MALL

BUILDING LINE — — — — — — APPARENT TRAVELED WAY ASPHAULT CONCRETE CURB LINE TREE DRIPLINE -DW------ DOMESTIC WATER _____ LAKE WATER ------ STREET LIGHT CONDUIT LIMIT OF WORK

POINT, ELEVATION AND DESCRIPTION

CONTOURS (1-FT INTERVALS)

TREE (DIAMETER SIZE IN INCHES) / TAG NUMBER





DEMOLITION NOTES

- 1. REMOVAL, PROTECTION, AND RELOCATION OF ELECTRICAL UTILITIES AND WATER LINES ARE SHOWN FOR REFERENCE ONLY AND ARE NOT COVERED BY THE GRADING PERMIT.
- 2. COORDINATE DEMOLITION WORK WITH STANFORD UNIVERSITY'S; ADHERE TO ALL THEIR REQUIREMENTS.
- 3. DEMOLITION AND CONSTRUCTION WORK MAY BE PERFORMED OVER THE TOP OF AND AROUND COMMUNICATION AND POWER SERVICES. CONTRACTOR SHALL WORK BY HAND IN ALL AREAS WHERE THESE SERVICES MIGHT BE HARMED BY LARGER LESS PRECISE EQUIPMENT.
- 4. THE CONTRACTOR SHALL LOCATE AND CLEARLY MARK (AND THEN PRESERVE THESE MARKERS) FOR THE DURATION OF CONSTRUCTION OF ALL UNDERGROUND UTILITIES, INCLUDING TELEPHONE, DATA, STREET LIGHT, SIGNAL LIGHT AND POWER FACILITIES, LOW TEMPERATURE HOT WATER AND CHILLED HOT WATER LINES THAT ARE IN OR NEAR THE AREA OF DEMOLITION.
- 5. CONTRACTOR'S BID IS TO INCLUDE ALL VISIBLE SURFACE AND ALL SUBSURFACE FEATURES IDENTIFIED TO BE REMOVED OR ABANDONED IN THESE DOCUMENTS.
- 6. THE CONTRACTOR SHALL BE RESPONSIBLE FOR A SITE INSPECTION TO FULLY ACKNOWLEDGE THE EXTENT OF THE DEMOLITION WORK.
- 7. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ANY AND ALL PERMITS NECESSARY FOR ENCROACHMENT, GRADING, DEMOLITION, AND DISPOSAL OF SAID MATERIALS AS REQUIRED BY PRIVATE, LOCAL AND STATE JURISDICTIONS. THE CONTRACTOR SHALL PAY ALL FEES ASSOCIATED WITH THE DEMOLITION WORK.
- 8. CONTRACTOR SHALL PAY DISPOSAL FEES.
- 9. BACKFILL ALL DEPRESSIONS AND TRENCHES FROM DEMOLITION OF FOUNDATIONS & UTILITIES TO EXISTING GRADE AND TO THE SATISFACTION OF THE GEOTECHNICAL ENGINEER, AND/OR UNIVERSITY FIELD CONSTRUCTION MANAGER (FCM).
- 10. WITHIN LIMITS OF WORK, REMOVE CURBS, GUTTERS, LANDSCAPING, SIGNAGE, TREES, SHRUBS, ASPHALT, UNDERGROUND PIPES, ETC. AS INDICATED ON THE DRAWINGS
- 11. CONTRACTOR SHALL BE RESPONSIBLE FOR DISPOSING ALL DEMOLITION MATERIALS, OR STORING SELECTED ITEMS BY UNIVERSITY'S REPRESENTATIVE AT DESIGNATED LOCATIONS.
- 12. PRIOR TO BEGINNING DEMOLITION WORK, CONTRACTOR TO NOTIFY AND COORDINATE THE REMOVAL AND/OR ABANDONMENT OF ALL AFFECTED UTILITIES WITH THE FCM.
- 13. CONTRACTOR RESPONSIBLE FOR PREPARING WASTE MANAGEMENT PLAN, TRAINING OF EMPLOYEES & SUBCONTRACTORS, AND ENSURING PROPER REMOVAL AND DISPOSAL OF ALL HAZARDOUS MATERIALS.
- 14. THESE DRAWINGS DO NOT ADDRESS CONTRACTOR MEANS, METHODS OR PROCESSES THAT MAY BE ASSOCIATED WITH ANY TOXIC SOILS IF FOUND ON SITE. THE CONTRACTOR IS RESPONSIBLE FOR COMPLYING WITH ALL UNIVERSITY AND COUNTY STANDARDS AND APPROPRIATE REGULATIONS IF TOXIC SOILS ARE ENCOUNTERED. CONTRACTOR MUST NOTIFY THE FCM IMMEDIATELY IF ANY SOILS ARE EVEN SUSPECTED OF BEING CONTAMINATED.
- 15. CONTRACTOR SHALL CONTACT UNDERGROUND SERVICE ALERT. USA. FOR LOCATION AND MARKING OF UNDERGROUND UTILITIES AT LEAST 48 HOURS PRIOR TO COMMENCEMENT OF CONSTRUCTION
- 16. CONTRACTOR SHALL MAINTAIN THE EXISTING SITE AND STREETS IN A SAFE AND USABLE MANNER SUCH THAT EMERGENCY VEHICLE ACCESS IS AVAILABLE AT ALL TIMES. CONTRACTOR TO SUPPLY, INSTALL AND MAINTAIN ALL NECESSARY FENCING. GATES. BARRICADES, SIGNAGE, AND PROVISIONS FOR ENSURING THE PROJECT'S SECURITY AND SAFE PASSAGEWAY AROUND IT.
- 17. CONTRACTOR SHALL GATHER ALL CONSTRUCTION DEBRIS ON A REGULAR BASIS AND PLACE IT IN A DUMPSTER OR OTHER CONTAINER WHICH IS EMPTIED OR REMOVED ON A REGULAR BASIS. WHEN APPROPRIATE, USE TARPS ON THE GROUND TO COLLECT FALLEN DEBRIS OR SPLATTERS THAT COULD CONTRIBUTE TO STORM WATER RUNOFF POLLUTION.
- 18. CONTRACTOR SHALL CLEAR AND GRUB WITHIN LIMIT OF WORK AS NEEDED TO PERFORM DEMOLITION ACTIVITIES.
- 19. SAWCUT & REMOVE HARDSCAPE SUCH AS, BUT NOT LIMITED TO, AC PAVEMENT, CURB, SIDEWALK, ETC.
- 20. TAKE ALL NECESSARY PRECAUTIONS NOT TO DAMAGE EXISTING UNDERGROUND UTILITY LINES TO REMAINS DURING DEMOLITION. CONTRACTOR TO HIRE AN INDEPENDENT UNDERGROUND UTILITY LOCATOR SERVICE TO LOCATE & PAINT UTILITIES IN THE FIELD PRIOR TO CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES TO REMAINS SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.
- 21. CONTRACTOR TO GRIND/ROUND CONCRETE EDGE AFTER SAWCUTTING TO MAINTAIN APPEARANCE AND SAFETY.
- 22. CONTRACTOR SHALL SCHEDULE MEETING WITH STANFORD ARBORIST AND UA/CPD FOR REVIEW OF THE TREE PROTECTION PRIOR TO START OF CONSTRUCTION.
- 23. CONTRACTOR TO SCHEDULE MEETING WITH HIGH VOLTAGE SHOP PRIOR TO REMOVING ANY EXISTING PULLBOXES.

TREE DISPOSITION TABLE

NOTES: PREVIOUS ASA.

75

76

FOR BREVITY, TREE TAGS ARE REFERRED TO IN THE WLCA ARBORIST REPORT BY THE LAST TWO DIGITS ONLY.

| SPECIES | DBH (IN.) | REMOVE/REMAIN | PROTECTED STATUS |
|--------------------------|-----------|---------------|-------------------------------------|
| EUCALYPTUS GLOBULUS | 39.1 | REMAIN | NOT PROTECTED. SEE NOTE CONDITION B |
| SHINUS MOLLE | 45.0 | REMOVE | NOT PROTECTED. SEE NOTE CONDITION B |
| EUCALYPTUS GLOBULUS | 49.5 | REMOVE | NOT PROTECTED, SEE NOTE CONDITION B |
| SCHINUS MOLLE | 34.6 | REMOVE | NOT PROTECTED, SEE NOTE CONDITION B |
| SCHINUS MOLLE | 20.0 | REMOVE | NOT PROTECTED, SEE NOTE CONDITION B |
| EUCALYPTUS GLOBULUS | 60.7 | REMOVE | NOT PROTECTED, SEE NOTE CONDITION B |
| EUCALYPTUS GLOBULUS | 41.4 | REMAIN | NOT PROTECTED, SEE NOTE CONDITION B |
| EUCALYPTUS POLYANTHEMOS | 20.2 | REMOVE | NOT PROTECTED. SEE NOTE CONDITION B |
| EUCALYPTUS SPECIES | 26.8 | REMOVE | NOT PROTECTED, SEE NOTE CONDITION B |
| EUCALYPTUS GLOBULUS | 26.0 | REMOVE | NOT PROTECTED, SEE NOTE CONDITION B |
| EUCALYPTUS GLOBULUS | 33.0 | REMOVE | NOT PROTECTED, SEE NOTE CONDITION B |
| EUCALYPTUS GLOBULUS | 32.0 | REMOVE | NOT PROTECTED, SEE NOTE CONDITION B |
| EUCALYPTUS CAMALDULENSIS | 15.3 | REMOVE | NOT PROTECTED, SEE NOTE CONDITION B |
| EUCALYPTUS CAMALDULENSIS | 29.7 | REMOVE | NOT PROTECTED, SEE NOTE CONDITION B |
| EUCALYPTUS GLOBULUS | 29.1 | REMOVE | NOT PROTECTED, SEE NOTE CONDITION B |
| EUCALYPTUS GLOBULUS | 58.0 | REMOVE | NOT PROTECTED, SEE NOTE CONDITION B |
| EUCALYPTUS GLOBULUS | 42.8 | REMOVE | NOT PROTECTED, SEE NOTE CONDITION B |
| SCHINUS MOLLE | 18.0 | REMOVE | NOT PROTECTED, SEE NOTE CONDITION B |
| SCHINUS MOLLE | 15.2 | REMOVE | NOT PROTECTED, SEE NOTE CONDITION B |
| SCHINUS MOLLE | 18.0 | REMOVE | NOT PROTECTED, SEE NOTE CONDITION B |
| PINUS RADIATA | 24.6 | REMOVE | NOT PROTECTED, SEE NOTE CONDITION B |
| SEQUOIA SEMPERVIRENS | 18.6 | REMOVE | NOT PROTECTED, SEE NOTE CONDITION B |
| SEQUOIA SEMPERVIRENS | 13.6 | REMOVE | NOT PROTECTED, SEE NOTE CONDITION B |
| SCHINUS MOLLE | 70.0 | REMOVE | NOT PROTECTED, SEE NOTE CONDITION B |
| PISTACIA CHINENSIS | 9.5 | REMOVE | NOT PROTECTED, SEE NOTE CONDITION A |
| OLEA EUROPAEA | 9.0 | REMOVE | NOT PROTECTED, SEE NOTE CONDITION A |
| EUCALYPTUS GLOBULUS | 25.0 | REMOVE | NOT PROTECTED, SEE NOTE CONDITION B |
| EUCALYPTUS GLOBULUS | 48.3 | REMOVE | NOT PROTECTED, SEE NOTE CONDITION B |
| EUCALYPTUS GLOBULUS | 63.7 | REMOVE | NOT PROTECTED, SEE NOTE CONDITION B |
| EUCALYPTUS GLOBULUS | 43.0 | REMOVE | NOT PROTECTED, SEE NOTE CONDITION B |
| SCHINUS MOLLE | 23.7 | REMOVE | NOT PROTECTED, SEE NOTE CONDITION B |
| SCHINUS MOLLE | 21.0 | REMOVE | NOT PROTECTED, SEE NOTE CONDITION B |
| EUCALYPTUS GLOBULUS | 45.7 | REMOVE | NOT PROTECTED, SEE NOTE CONDITION B |
| SCHINUS MOLLE | 11.2 | REMOVE | NOT PROTECTED, SEE NOTE CONDITION A |
| SCHINUS MOLLE | 9.5 | REMOVE | NOT PROTECTED, SEE NOTE CONDITION A |
| EUCALYPTUS GLOBULUS | 91.7 | REMOVE | NOT PROTECTED, SEE NOTE CONDITION B |
| SCHINUS MOLLE | 35.6 | REMOVE | NOT PROTECTED, SEE NOTE CONDITION B |
| EUCALYPTUS GLOBULUS | 48.8 | REMOVE | NOT PROTECTED, SEE NOTE CONDITION B |
| SCHINUS MOLLE | 11.0 | REMOVE | NOT PROTECTED, SEE NOTE CONDITION A |
| EUCALYPTUS GLOBULUS | 47.3 | REMOVE | NOT PROTECTED, SEE NOTE CONDITION B |
| EUCALYPTUS GLOBULUS | 41.5 | REMOVE | NOT PROTECTED, SEE NOTE CONDITION B |
| EUCALYPTUS GLOBULUS | 53.4 | REMOVE | NOT PROTECTED, SEE NOTE CONDITION B |
| EUCALYPTUS GLOBULUS | 53.7 | REMOVE | NOT PROTECTED, SEE NOTE CONDITION B |
| EUCALYPTUS GLOBULUS | 72.8 | REMOVE | NOT PROTECTED, SEE NOTE CONDITION B |
| EUCALYPTUS GLOBULUS | 52.2 | REMOVE | NOT PROTECTED, SEE NOTE CONDITION B |

CONDITION A: TREE IS NOT DESIGNATED AS A PROTECTED TREE DUE TO THE DBH BEING LESS THAN 12". CONDITION B: TREE IS NOT DESIGNATED AS A PROTECTED TREE DUE TO NOT BEING IDENTIFIED ON A



STANFORD UNIVERSITY

<u>NOTES:</u>

- SPECIFICATIONS GUIDELINE 01 56 39 TREE AND PLANT PROTECTION.
- 2. DEFINED AS LISTED IN DEFINITIONS 1.3B.
- PLAN SET.
- UNIVERSITY GROUNDS CERTIFIED ARBORIST.
- TREES WITHIN THE PROJECT LIMITS.
- ARFAS
- 9. 10.

- 14. ALL TRENCHING SHALL CONFORM TO THE FOLLOWING GUIDELINES.
- KIND WITHIN A TREES' ROOT ZONE. CUTTING OR REVIEW.
- C. TUNNELING OR BORING UNDER ROOTS RATHER THAN PRUNING IS PREFERRED.

GREATER THE INSTANCE OF TREE SUCCESS IN CONSTRUCTION AREAS.



| | | | | | | IIT OF WORK | | DECOMPOSI | ED GRA |
|--|--|---|--|--|--|--|---|--|--|
| | | | | * | — — — — GR | ADE BREAK | Δ Δ | | |
| | | | | 7.5' HIGH QF | 2 <i>cc</i> | DUNTOUR | | | |
| / LW LW I | _w Lw | | | | * * * * NA | TURAL TURF | | BARK MUL | CH, SLP |
| | | × 54.01 GRD | | | 53.57 G | _ <u>53.39/</u> G | | | |
| | | 2- | -1"-1-3" EL | × | | | | | |
| | (7') IRON FE | | 53.96 BW 96 | FG 53.8 | EX. 01 21 21 21 21 21 21 21 21 21 21 21 21 21 | ER WALL | (4') IRON/CHA | IN FENCE | |
| | 4' FENCE, | TYPSITE | CONCAT/FENCE | | | | | | + |
| | → + + 54.13 SW 54.18 | 284-04 | | | <u>53,728</u> + → | + + + | - SYNTHETIC TUR | <i>T</i> +/+ + + + + + + + + + + + + + + + + + + | + \ |
| | $\bigvee_{G} \underbrace{\overset{\bullet}{\overset{\bullet}}}_{G} \overset{\bullet}{\overset{\bullet}} \overset{\bullet}}_{G} \overset{\bullet}{\overset{\bullet}} \overset{\bullet}}_{G} \overset{\bullet}{\overset{\bullet}} \overset{\bullet}{\overset{\bullet}} \overset{\bullet}}_{G} \overset{\bullet}{\overset{\bullet}} \overset{\bullet}}_{G} \overset{\bullet}{\overset{\bullet}} \overset{\bullet}}_{G} \overset{\bullet}}_{G} \overset$ | | AM BENCHES | 35 .41 + + + + | + $+$ $+$ | + + + | | | ₿₽"₽ ₽ + |
| | $\begin{array}{cccc} & & & & & \\ & & & & \\ & & & & \\ & & & & \\ & & & & \\ & & & & \\ & & & & \\ & & & & \\ \end{array}$ | | | | | <u>√52.8</u> <u>√16</u> <u>√153.00</u> ↓ | | + + + + | + 、 |
| | V V WOOD ENPS | | × × × × × | | | | + + + + + + + + + + + + + + + + + + + | $\begin{array}{c} \bullet & \bullet \\ \bullet \\$ | |
| $G^{54.45}$ | $\begin{array}{cccccccccccccccccccccccccccccccccccc$ | | $\begin{array}{cccccccccccccccccccccccccccccccccccc$ | | $\begin{array}{c} & & & & & \\ & & & & \\ & & & & \\ & & & \\ & & & \\ & & & & \\ & & & \\ & & & & \\ & & & \\ & & & \\ & & & \\ & & & \\ & & & \\ & & & \\ & & & \\ & &$ | * * * * * * * | $\begin{array}{c} & & & & & & & \\ & & & & & & \\ & & & & $ | $\begin{array}{cccccccccccccccccccccccccccccccccccc$ | * * * * |
| $\begin{array}{cccccccccccccccccccccccccccccccccccc$ | $\bigvee_{\mathbf{v}}^{\mathbf{v}} \underbrace{_{54.47}^{\mathbf{v}}}_{\mathbf{G}} _{\mathbf{v}}^{\mathbf{v}} _{\mathbf{v}}^{\mathbf{v}}$ | | | | $\begin{array}{c ccccccccccccccccccccccccccccccccccc$ | $\begin{array}{c c} & & & & & \\ & & & & \\ & & & & \\ & & & \\ & & & \\ & & & \\ & & & \\ & & & \\ & & & \\ & & & \\ \end{array}$ | $\begin{array}{cccccccccccccccccccccccccccccccccccc$ | | |
| $\begin{array}{cccccccccccccccccccccccccccccccccccc$ | $\begin{array}{cccccccccccccccccccccccccccccccccccc$ | | $\begin{array}{cccccccccccccccccccccccccccccccccccc$ | $\begin{array}{cccccccccccccccccccccccccccccccccccc$ | | * * * * * * * * | $\begin{array}{cccccccccccccccccccccccccccccccccccc$ | | * * * * |
| × × × _5 45 7∠ × × × × ^G × × × | $\begin{array}{cccccccccccccccccccccccccccccccccccc$ | | | | v + + + + + + + + + + + + + + + + + + + | + + ≠ G + + + + | $\begin{array}{c} 2.75 \\ + \\ + \\ + \\ + \\ + \\ + \\ + \\ + \\ + \\ $ | | $\begin{array}{c} & & & \\ & & & \\ & & & \\ & & & \\ & & & \\ & & & \\ & & & \end{array}$ |
| | * * * * * <u>54.99</u> * * | | $\begin{array}{c} & 53.82 \\ & & & & \\ & & & \\ & & & \\ & & & \\ & & & \\ & & & \\ & & & \\ & & & \\ & &$ | | | * * * | | | |
| | | | | | * * * * | | | | * * |
| $= \frac{54.13^{4}}{6^{4}} + \frac{1}{6^{4}} + \frac{1}$ | $\begin{array}{c} \bullet & \bullet & \bullet \\ \bullet & \bullet & \bullet \\ \bullet & \bullet & \bullet \\ \bullet & \bullet &$ | | | | | * * * * 5 * * * 6 * * * | | + + + <u>52.39</u> - + | $ \begin{array}{c} $ |
| | $\begin{array}{c} & & & \\ & & & & \\ & & & & \\ & & & & \\ & & & & \\ & & & & \\ & & & & \\ & & & & \\ & & & & \\ & & & & \\ & & & & \\ & & & & \\ & & & & \\$ | | | | $\begin{array}{c} \begin{array}{c} \begin{array}{c} \begin{array}{c} \\ \\ \end{array} \\ \end{array} \\ \end{array} \\ \begin{array}{c} \\ \end{array} \\ \begin{array}{c} \\ \end{array} \\ \end{array} \\ \begin{array}{c} \\ \end{array} \\ \end{array} \\ \begin{array}{c} \\ \end{array} \\ \begin{array}{c} \\ \end{array} \\ $ | $\begin{array}{c} \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\$ | | | * * / * |
| $\begin{array}{c ccccccccccccccccccccccccccccccccccc$ | * * * * * * * * */* | | | | | * * * * * * | + + + + + + + / + + + | | * * * * |
| | | + + + + + + + + + | $\begin{array}{c} & & \\ & & \\ & & \\ & \\ & \\ & \\ & \\ & \\ $ | | | * * * * * * | $\begin{array}{cccccccccccccccccccccccccccccccccccc$ | + <u>+ 52.44</u> + + <u>G</u> + + | * |
| | + 5 ⁵ + + + + + + + + + + + + + + + + + + + | | | | | * * * * * * | | | * ~ ~ * ~ ~ |
| | * * * * * * * * | | * * * * * * * * * <u>* 53.30</u> | | | * * * | | | * 52 * * |
| * * * * <u>* 53.69</u> * | | | | | | | | | |
| × + + + + + + + + + + + + + + + + + + + | | | | | | * * * | | + + <u>52.28</u> + + + + | ·↓ ↓ ↓ ↓ |
| | | $\begin{array}{cccccccccccccccccccccccccccccccccccc$ | $\begin{array}{cccccccccccccccccccccccccccccccccccc$ | | + + + + + + + + + + + + + + + + + + + | * * * * * * * | + + + + + + + + + + | | * * * |
| · · · · · · · · · · · · · · · · · · · | | | $\begin{array}{cccccccccccccccccccccccccccccccccccc$ | | | * * * * * * * | | ↓ ↓ ↓ ↓ ↓ ↓ ↓ ↓ ↓ ↓ ↓ ↓ | |
| + + + + + + + + + + + + + + + + + + + | | | | $\begin{array}{cccccccccccccccccccccccccccccccccccc$ | | + + + + + + + + + + + + + + + + + + + | G + + + + + + + + + + | + + <u>52.42</u> + + + + | ¥ ¥ ¥ ¥ |
| $\begin{array}{cccccccccccccccccccccccccccccccccccc$ | | $\begin{array}{c ccccccccccccccccccccccccccccccccccc$ | | | | * * * * | | × × × × × × × | * * |
| × × × × | | | $\begin{array}{cccccccccccccccccccccccccccccccccccc$ | | | * * * | ↓ ↓ ↓ ↓ ↓ ↓ ↓ ↓ | | ↓ ↓ ↓ ↓ |
| ↓ ↓ G ↓ ↓ ↓ ↓ ↓ ↓ ↓ ↓ ↓ ↓ | | | $\begin{array}{cccccccccccccccccccccccccccccccccccc$ | | | | $\begin{array}{c} 52.72 \\ G \\ \end{array}$ | + + <u>52.36</u> + / + + + / | + + 7 + |
| + | | | ↓ | | | | | | |
| $\begin{array}{c} & 52.86 \\ & & G \\ & & G \\ & & & & \\ & & & & \\ & & & &$ | ψ | $\begin{array}{cccccccccccccccccccccccccccccccccccc$ | 52.67 + 52.83 + | | $\overset{\checkmark}{\models} \overset{\checkmark}{\downarrow} \overset{\checkmark}{\downarrow} \overset{\checkmark}{\downarrow} \overset{\checkmark}{\downarrow} \overset{\checkmark}{\downarrow} \overset{\checkmark}{\downarrow} \overset{\checkmark}{\downarrow} \overset{\checkmark}{\downarrow} \overset{\lor}{\downarrow} \overset{\lor}$ | $\begin{array}{cccccccccccccccccccccccccccccccccccc$ | $\begin{array}{cccccccccccccccccccccccccccccccccccc$ | $\begin{array}{cccccccccccccccccccccccccccccccccccc$ | * * * * |
| $ \begin{array}{cccccccccccccccccccccccccccccccccccc$ | $\begin{array}{cccccccccccccccccccccccccccccccccccc$ | $\begin{array}{cccccccccccccccccccccccccccccccccccc$ | ↓ ↓ ↓ ↓ G ↓ ↓ ↓ ↓ ↓ ↓ ↓ ↓ ↓ ↓ ↓ ↓ ↓ ↓ ↓ | ↓ ↓ ↓ FOR ↓MOWE | $\mathbf{R} \stackrel{}{\downarrow} }{\downarrow} \stackrel{}{\downarrow} }{\downarrow} {\downarrow} }{\downarrow} $ | $\begin{array}{cccccccccccccccccccccccccccccccccccc$ | • • • • • • • • • • • • • • • • • • • | | * * * * |
| | | | | | <u>, , , , , , , , , , , , , , , , , , , </u> | | | | |
| RELOCATED SITE | AC PAVEMENT | PH-CS | OCATED SITE | MATCH EX | | SITE - | SW 252.40 | 52.38 SW | |
| | - Y | × | CONC S/W | r6 32.3±∲´́ | UGHT, CONC | TYP. ♥ S/W | ↓ X | | ILU SITE GHT, TYP |
| 52.56 | 52.42 3W | 5 <u>2.30</u> | 52.25 BW 52.24 | (4´) IRON FENCE | BW | 52.48 BW | | | _ M |
| | | | | | ·~ | | | | • !/ |
| | | | | | - DV 1" | | | Ļ | |
| | | | | | ם - אמ | | | | |
| | | | | | ₹ | | | | |



STANFORD UNIVERSITY

Project Name: Lacrosse Practice Field Project Address: 657 Masters Mall, Stanford CA. 94305 Quad/ Bldg. Number: 09-379

NO.DATEDESCRIPTION03.18.24ASA SUBMITTAL08.13.24ASA RESUBMITTAL

PROJECT NUMBER

ISSUES AND REVISIONS

SHEET TITLE

GRADING SECTIONS

SCALE

1"=20'

SHEET NUMBER

C-4.1

- DEGREE ANGLE AND WATER LINES SHALL BE MINIMUM OF 12" ABOVE TOP OF
- APPLICABLE WATER DISTRICT STANDARDS.

- AREAS SHALL MEET ADA REQUIREMENTS. AS DIRECTED BY THE LANDSCAPE ARCHITECT. TWO (2) FEET OF COVER IN NON-TRAFFIC AREAS SHALL BE POLYVINYL CHLORIDE (PVC) SDR 35 GREEN PIPE AND SHALL CONFORM TO THE 4. ALL TRENCHES SHALL BE BACK FILLED PER THE SPECIFICATIONS WITH REQUIREMENTS OF ASTM DESIGNATION D 3034-73 WITH BELLS AND SPIGOT APPROPRIATE TESTS BY THE GEOTECHNICAL ENGINEER TO VERIFY COMPACTION CONNECTIONS. ALL DIRECTION CHANGES SHALL BE MADE WITH WYE VALUES. PLANS. CONNECTIONS, 22.5° ELBOWS, 45° ELBOWS OR LONG SWEEP ELBOWS, 90°

EROSION CONTROL NOTES:

- A. THIS PLAN IS FOR STORMWATER POLLUTION CONTROL DURING CONSTRUCTION IF NO SWPPP IS REQUIRED. IF A SWPPP FOR THE PROJECT HAS BEEN ISSUED THE PROJECT SWPPP OVERRIDES ANYTHING SHOWN ON THIS PLAN.
- B. TEMPORARY CONSTRUCTION ENTRANCE/EXIT LOCATION SHOWN IS APPROXIMATE. CONTRACTOR TO PROVIDE LOCATION WHERE APPROPRIATE.
- C. THIS PLAN REPRESENTS POSSIBLE WATER POLLUTION CONTROL MEASURES INCLUDING EROSION CONTROL AND SEDIMENT CONTROL.
- D. EXISTING SURFACES SHALL BE UNDISTURBED TO THE EXTENT PRACTICAL.
- E. GROUND WATER SHALL NOT BE DISCHARGED WITH STORM WATER. GROUND WATER DEWATERING OPERATIONS SHALL BE COORDINATED AS NEEDED WITH OWNER.
- F. CONTRACTOR SHALL PROVIDE EFFECTIVE SOIL COVER FOR AREAS OF CONSTRUCTION ACTIVITY THAT HAVE BEEN DISTURBED AND ARE NOT SCHEDULED TO BE ACTIVE FOR AT LEAST 14 DAYS.
- G. ALL EROSION CONTROL AND SEDIMENT CONTROLS TO BE OBTAINED INSTALLED AND MAINTAINED AS REQUIRED IN PROJECT SWPPP.
- H. CONTRACTOR TO INSTALL RUN-ON AND RUN-OFF CONTROL MEASURES ACCORDING TO PLANS OR AS NECESSARY TO ENSURE SEDIMENT IS NOT TRANSPORTED FROM SITE.
- I. CONTRACTOR TO PROVIDE BACK-UP EROSION PREVENTION MEASURES (SOIL STABILIZATION) WITH SEDIMENT CONTROL MEASURES SUCH AS STRAW WATTLES, SILT FENCE, GRAVEL INLET FILTERS, AND/OR SEDIMENT TRAPS OR BASINS. ENSURE CONTROL MEASURES ARE ADEQUATE, IN PLACE, AND IN OPERABLE CONDITIONS. SEDIMENT CONTROLS, INCLUDING INLET PROTECTION, ARE NECESSARY BUT SHOULD BE A SECONDARY DEFENSE BEHIND GOOD EROSION CONTROL MEASURES.
- J. STOCKPILE LOCATION(S) TO BE DETERMINED BY THE CONTRACTOR. COORDINATE WITH SITE QSP.
- K. ALL CONCRETE TRUCKS TO USE CHUTE WASH BUCKETS FOR CONCRETE RINSE, ALL CONCRETE PUMPS TO CAPTURE CONCRETE RINSE IN SECONDARY CONTAINMENT AND PROPERLY DISPOSE.
- L. STREET SWEEPING SHALL BE CHECKED DAILY TO ENSURE DEPOSITED SEDIMENT AND DEBRIS DOES NOT ENTER THE STORM DRAIN SYSTEM. USE REGENERATIVE VACUUM STREET CLEANER TO MITIGATE AIR AND WATER POLLUTION.
- M. RUNOFF THAT HAS CONTACTED AMENDED SOIL AREAS SHALL NOT BE ALLOWED TO LEAVE THE SITE OR ENTER THE STORM DRAIN SYSTEM.

STANFORD UNIVERSITY

Project Name: Lacrosse Practice Field Project Address: 657 Masters Mall, Stanford CA. 94305 Quad/ Bldg. Number: 09-379

NO. DATE 03.18.2

03.18.24 ASA SUBMITTAL 08.13.24 ASA RESUBMITTAL

DESCRIPTION

ISSUES AND REVISIONS

PROJECT NUMBER

SHEET TITLE

EROSION CONTROL PLAN

SCALE

1"=30'

STANDARD BEST MANAGEMENT PRACTICE NOTES

- Solid and Demolition Waste Management: Provide designated waste collection areas and containers on site away from streets, gutters, storm drains, and waterways, and arrange for regular disposal. Waste containers must be watertight and covered at all times except when waste is deposited. Refer to Erosion & Sediment Control Field Manual, 4th Edition (page C3) or latest.
- <u>Hazardous Waste Management</u>: Provide proper handling and disposal of hazardous wastes by a licensed hazardous waste material hauler. Hazardous wastes shall be stored and properly labeled in sealed containers constructed of suitable materials. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-5 to C-6) or latest.
- 3. <u>Spill Prevention and Control</u>: Provide proper storage areas for liquid and solid materials, including chemicals and hazardous substances, away from streets, gutters, storm drains, and waterways. Spill control materials must be kept on site where readily accessible. Spills must be cleaned up immediately and contaminated soil disposed properly. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-7 to C-8, C-13 to C-14) or latest.
- 4. <u>Vehicle and Construction Equipment Service and Storage</u>: An area shall be designated for the maintenance, where onsite maintenance is required, and storage of equipment that is protected from stormwater run-on and runoff. Measures shall be provided to capture any waste oils, lubricants, or other potential pollutants and these wastes shall be properly disposed of off site. Fueling and major maintenance/repair, and washing shall be conducted off-site whenever feasible. Refer to Erosion & Sediment Control Field Manual, 4th Edition (page C9) or latest.
- 5. <u>Material Delivery, Handling and Storage</u>: In general, materials should not be stockpiled on site. Where temporary stockpiles are necessary and approved by the County, they shall be covered with secured plastic sheeting or tarp and located in designated areas near construction entrances and away from drainage paths and waterways. Barriers shall be provided around storage areas where materials are potentially in contact with runoff. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-11 to C-12) or latest.
- 6. <u>Handling and Disposal of Concrete and Cement</u>: When concrete trucks and equipment are washed on-site, concrete wastewater shall be contained in designated containers or in a temporary lined and watertight pit where wasted concrete can harden for later removal. If possible have concrete contractor remove concrete wash water from site. In no case shall fresh concrete be washed into the road right-of-way. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-15 to C-16) or latest.
- Pavement Construction Management: Prevent or reduce the discharge of pollutants from paving operations, using measures to prevent run-on and runoff pollution and properly disposing of wastes. Avoid paving in the wet season and reschedule paving when rain is in the forecast. Residue from saw-cutting shall be vacuumed for proper disposal. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-17 to C-18) or latest.
- 8. <u>Contaminated Soil and Water Management</u>: Inspections to identify contaminated soils should occur prior to construction and at regular intervals during construction. Remediating contaminated soil should occur promptly after identification and be specific to the contaminant identified, which may include hazardous waste removal. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-19 to C-20) or latest.
- 9. Sanitary/Septic Water Management: Temporary sanitary facilities should be located away from drainage paths, waterways, and traffic areas. Only licensed sanitary and septic waste haulers should be used. Secondary containment should be provided for all sanitary facilities. Refer to Erosion & Sediment Control Field Manual, 4th Edition (page C-21) or latest.
- 10.Inspection & Maintenance: Areas of material and equipment storage sites and temporary sanitary facilities must be inspected weekly. Problem areas shall be identified and appropriate additional and/or alternative control measures implemented immediately, within 24 hours of the problem being identified.

STANDARD EROSIC

1. Sediment Control Ma

Tracking Preventic shall be organized to prevent or minin public street syster device construction all sites. Clean up provided by means approaching rain e of each workday th frequently as deter Refer to Erosion *&* 4th Edition (pages

Storm Drain Inlet a All inlets within th within the project I gravel bags placed protection. At loca present, staked fibe can be used. Inlet clogging and subse & Sediment Contr (pages B-49 to B-5

Storm Water Runc allowed to drain in underground storm ground watercours control measures a

Dust Control: The control in graded a suppression or che soils, providing fo deposited on pave road entrances and limiting the amoun and earth moving activities in phase

Stockpiling: Exca streets or on pave stockpiles shall be erosion control ma fences, ect.) to enso or enter the storm watercourse.

- 2. <u>Erosion Control</u>: D all disturbed areas n combination of eros required that tempor are applied to all dis event. During the n measures must be ap erosion at the site.
- Inspection & Maint Project's site, locati exit the site, and all that are identified as Plans must be inspe during, and after sto during seasonal wet be identified and ap or alternative contro immediately, within identified.
- 4. <u>Project Completion</u> signoff by the Coun shall be reseeded, p the potential for ero
- It shall be the Owner maintain control of and to keep the entierosion control plan
- Erosion and sedime practices shall be op vegetation is fully e surfaces.

Best Management Practices and Erosion Control Details Shee County of Santa Clara

| | | | STANFORD UNIVERSITY |
|--|--|-------|--|
| | | | |
| | | | |
| | Г | | |
| SION CONTROL NOTE | <u>S</u> | | Project Name: Lacrosse Practice Field |
| <u>I Management:</u> ention & Clean Up: Activit zed and measures taken as | ties needed | | Stanford CA. 94305 Quad/ Bldg. Number: 09-379 |
| stem. A gravel or proprieta etion entrance/exit is requir up of tracked material shal eans of a street sweeper pri in event, or at least once at ay that material is tracked, etermined by the County In | to the rry red for Il be for to an the end or, more nspector. | | |
| ges B-31 to B-33) or latest let and Catch Basin Inlet P n the vicinity of the project ect limits shall be protected ced around inlets or other i ocations where exposed so fiber roles or staked silt fer allet filters are not allowed c absequent flooding. Refer t ontrol Field Manual, 4th Ed P. 51) or latest | rotection: t and t with inlet ils are nces due to o Erosion lition | | SANDIS |
| unoff: No storm water runc n in to the existing and/or p orm drain system or other a ourses until appropriate ero es are fully installed. | off shall be proposed above sion | | |
| The contractor shall provide ed areas as required by pro- chemical stabilization of ex- g for rapid clean up of sedin aved roads, furnishing cons- and vehicle wash down are ount of areas disturbed by ng operations by schedulin ases. | e dust viding wet xposed ments struction eas, and clearing g these | | |
| xcavated soils shall not be ved areas. Borrow and ter be protected with appropr measures(tarps, straw bale ensure silt does not leave t rm drain system or neighbo | placed in mporary iate es, silt he site pring | | ISSUES AND REVISIONS NO. DATE DESCRIPTION |
| During the rainy season, as must include an effective rosion and sediment contro- porary erosion control mea disturbed soil areas prior t te non-rainy season, erosion e applied sufficient to control | e ol. It is asures to a rain n control rol wind | | 03.18.24 ASA SUBMITTAL 08.13.24 ASA RESUBMITTAL |
| e. <u>intenance</u> : Disturbed areas cations where vehicles enter all erosion and sediment con- d as part of the Erosion Con- spected by the Contractor by storm events, and at least wet periods. Problem areas appropriate additional and problem areas | a of the er or ontrols ntrol pefore, weekly shall | u | |
| hin 24 hours of the probler | a n being etion and | latic | PROJECT NUMBER |
| ounty Inspector, all disturbed l, planted, or landscaped to erosion on the subject site. vner's/Contractor's respon- of the entire construction of | ed areas minimize sibility to operation | lform | SHEET TITLE COUNTY BMP NOTES |
| ntire site in compliance wi lan. ment control best managen | th the | it Ir | SCALE |
| e operable year round or un y established on landscape | ntíl d |)jec | N.T.S. |
| | | Prc | SHEET NUMBER |
| | COUNT | | |
| eet I | | BMP-1 | |
| | TA CLAS | | C-6 1 |
| | | | U-0.1 |
| | | | |
| | | | |

| | STANFORD UNIVERSITY |
|--|--|
| fiber roll a level contour. | <text><text><text><text></text></text></text></text> |
| ment $3^{*} \underset{\text{WRE}}{\underset{\text{STAPLE DETAIL}}{}}$ | ISSUES AND REVISIONS NO. DATE DESCRIPTION 03.18.24 ASA SUBMITTAL 08.13.24 ASA RESUBMITTAL |
| AL LAYOUT DETERMINED LD. SORCETE WASHOUT SIGN BE INSTALLED WITHIN OF THE TEMPORARY RETE WASHOUT FACILITY. | <text><section-header><text><section-header><text><text><text><text></text></text></text></text></section-header></text></section-header></text> |
| et 2 BMP-2 | C-6.2 |

STANFORD UNIVERSITY

Project Name: Lacrosse Practice Field Project Address: 657 Masters Mall, Stanford CA. 94305 Quad/ Bldg. Number: 09-379

PROJECT NUMBER

ISSUES AND REVISIONS

DESCRIPTION

08.13.24 ASA RESUBMITTAL

ASA SUBMITTAL

NO. DATE

03.18.24

SHEET TITLE

FIRE ACCESS PLAN

SCALE

1"=30'

STORMWATER MANAGEMENT PLAN LEGEND

PROPOSED PERVIOUS AREA (136,886 SF)

PROPOSED IMPERVIOUS AREA (3,409 SF)

DMA BOUNDARY

STANFORD UNIVERSITY

Project Name: Lacrosse Practice Field Project Address: 657 Masters Mall, Stanford CA. 94305 Quad/ Bldg. Number: 09-379

STORMWATER MANAGEMENT NOTES:

THIS PROJECT CREATES/REPLACES LESS THAN 5,000 SF OF IMPERVIOUS SURFACE AND IS EXEMPTED FROM THE LID REQUIREMENTS OF PROVISION C.3.

DRAINAGE AREA:

0 SF

PROPOSED IMPERVIOUS PROPOSED PERMOUS EXISTING NON-VEHICULAR

3,409 SF 135,866 SF 139,275 SF

EXISTING AND PROPOSED AREA QUANTITIES

EXISTING IMPERMOUS PERMOUSE 139,275 SF TOTAL 139,275 SF PROPOSED 3,409 SF 135,866 SF 139,275 SF

NO. DATE

03.18.24 08.13.24

ASA SUBMITTAL ASA RESUBMITTAL

DESCRIPTION

ISSUES AND REVISIONS

PROJECT NUMBER

SHEET TITLE

STORMWATER MANAGEMENT PLAN SCALE

1"=30'

| LEGEND: | |
|-------------------------|--|
| \longrightarrow | CONSTRUCTION/FIRE TRUCK ACCESS ROUTES |
| —X | TEMPORARY CONSTRUCTION FENCE/ LIMIT OF WORK |
| \odot | EXISTING TREE TO REMAIN. SEE DETAIL 1, SHEET C-3.0 FOR PROTECTION REQUIREMENTS |
| Ř | EXISTING FIRE HYDRANT |
| \boxtimes | PORTABLE RESTROOM |
| s | SPILL KIT |
| CONSTRUCTION TRAILER | CONSTRUCTION TRAILER (DURATION 18 MONTHS) |
| | PEDESTRIAN CROSSING |

- STANFORD SHALL BE RESPONSIBLE FOR PRUNING AND TRIMMING THE ACCESS
- 2. CONTRACTOR TO ENSURE THAT 20' PATHWAY IS MAINTAINED AT ALL TIMES DURING CONSTRUCTION FOR FIRE ACCESS. CONSTRUCTION GATE OR ANY OTHER CONSTRUCTION ACTIVITY CANNOT ENCROACH INTO PATHWAY WITHOUT A
- THE EMERGENCY ACCESS SHALL MAINTAIN A 20 FT MIN. WIDTH UNDER ALL WEATHER CONDITIONS CAPABLE OF SUPPORTING UP TO 75,000 LBS.

- A. CONSTRUCTION MATERIALS AND FILL DIRT DELIVERED FROM OFF CAMPUS SHALL NOT BE DELIVERED BETWEEN THE HOURS OF 7:00 AM AND 9:00 AM AND 4:00
- B. TRUCKS BRINGING IN FILL DIRT AND BUILDING MATERIALS FOR THE PROJECT FROM OFF-SITE SHALL BE REQUIRED TO USE TRUCK ROUTES SHOWN ON FIGURE 3 OF THE INITIAL STUDY AS DESIGNATED BY THE CITIES OF PALO ALTO AND MENLO

CONSTRUCTION PRACTICES SHALL COMPLY WITH THE REQUIREMENTS OF THE COUNTY OF SANTA CLARA NOISE CONTROL ORDINANCE AND ARE TO BE MONITORED BY THE GENERAL CONTRACTOR THROUGHOUT THE CONSTRUCTION PROCESS. THE SUP REQUIRES THE FOLLOWING MEASURES TO REDUCE OPERATIONAL NOISE DURING

- A. MECHANICAL EQUIPMENT WITHIN 50 FEET OF A RESIDENCE SHALL BE
- B. THE BUILDING DESIGN SHALL INCORPORATE DESIGN MEASURES TO LOCATE NOISE SOURCES SUCH AS LOADING ZONES, TRASH BINS AND MECHANICAL EQUIPMENT C. ALL OPERATIONAL NOISE SOURCES SHALL COMPLY WITH THE COUNTY NOISE
- D. THE CONTRACTOR SHALL COORDINATE PLANNED CLASSROOM RELOCATIONS PRIOR
- E. FOR CONSTRUCTION ACTIVITIES THAT WOULD AFFECT SENSITIVE NOISE RECEPTORS OFF-CAMPUS OR IN AREAS DESIGNATED CAMPUS RESIDENTIAL IN THE COMMUNITY PLAN, THE CONTRACTOR SHALL GIVE ADVANCED REGULAR NOTIFICATION OF CONSTRUCTION ACTIVITY SCHEDULED TO THE POTENTIALLY AFFECTED RESIDENTS.
- EXTINGUISHER WITHIN 30 FEET OF THE LOCATION WHERE HOT WORK IS PERFORMED, IN ACCORDANCE WITH CFC 2604.2.6. ADDITIONALLY, STRUCTURES UNDER CONSTRUCTION, ALTERATION OR DEMOLITION SHALL BE PROVIDED WITH NO LESS THAN ONE APPROVED PORTABLE FIRE EXTINGUISHER SIZED FOR NOT LESS THAN ORDINARY HAZARD AT EACH STAIRWAY ON ALL FLOOR LEVELS WHERE COMBUSTIBLE MATERIALS HAVE ACCUMULATED, IN EVERY STORAGE/CONSTRUCTION SHED, AND WHERE SPECIAL HAZARDS EXIST INCLUDING, BUT NOT LIMITED TO, THE STORAGE AND USE OF FLAMMABLE AND COMBUSTIBLE LIQUIDS IN ACCORDANCE WITH CFC 1415.1.
- CONTRACTOR SHALL RESTORE ALL AREAS ADJACENT TO THE SITE THAT HAVE BEEN IMPACTED BY CONSTRUCTION OF THIS PROJECT. AREAS IMPACTED BY CONSTRUCTION MAY INCLUDE AREAS AT THE EDGE OF SITES AND BEYOND THE LIMIT OF WORK SHOWN

7. WALK TRUCKS TO AND FROM NELSON MALL TO CONSTRUCTION ENTRANCE DURING

STANFORD UNIVERSITY

Project Name: Lacrosse Practice Field Project Address: 657 Masters Mall, Stanford CA. 94305 Quad/ Bldg. Number: 09-379

DESCRIPTION

08.13.24 ASA RESUBMITTAL

ASA SUBMITTAL

NO. DATE

03.18.24

ISSUES AND REVISIONS

PROJECT NUMBER

SHEET TITLE

CONSTRUCTION SITE LOGISTICS/SAFETY PLAN SCALE

AS NOTED

LANDSCAPE DESIGN CONCEPT

THE LANDSCAPE DESIGN FOR THE PROJECT EXTENDS THE EXISTING STREETSCAPE FABRI MALL ALONG THE FRONT OF THE NEW LACROSSE FIELD. THE MALL WILL BE PLANTED W OAK TREES SET IN A BARK MULCH PLANTER. THE FIELD WILL BE FENCED WITH A 4' HIGH MATCH THE FENCING USED THROUGHOUT THE DAPER AREA.

TREE PRESERVATION NOTES

1. REFER TO THE TREE DISPOSITION TABLE ON SHEETS C-3.0 AND C-3.1 AND TO THE ARBOR PREPARED BY WALTER LEVISON, CONSULTING ARBORIST, FOR TREES TO BE SAVED AND F

2. REFER TO TREE PROTECTION AND REMOVAL NOTES ON SHEETS C-3.0 AND 3.1.

PLANTING NOTES

1. PROJECT SHALL COMPLY WITH SANTA CLARA COUNTY, AND STANFORD UNIVERSITY P REQUIREMENTS, INCLUDING:

1.1 SOIL SHALL BE CONDITIONED AND AMENDED AS PER THE RESULTS OF A SOILS TEST.

1.2 ALL SHRUB AND GROUNDCOVER AREAS SHALL BE MULCHED WITH 3" DEPTH OF BARK MULCH.

2. REFER TO CIVIL DRAWINGS FOR SITE DEMOLITION, PAVING, GRADING AND DRAINAGE . STORMWATER MANAGEMENT.

IRRIGATION NOTES

1. THE IRRIGATION SYSTEM SHALL BE DESIGNED BY A CERTIFIED IRRIGATION DESIGNER TO MEET SANTA CLARA COUNTY AND STANFORD UNIVERSITY REQUIREMENTS AND MAWA STANDARDS.

2. TREES WILL BE IRRIGATED WITH 2 PRESSURE COMPENSATING BUBBLER PER TREE.

3. SHRUBS WILL BE IRRIGATED WITH 1 PRESSURE COMPENSATING BUBBLER PER SHRUB.

4. GROUNDCOVER AREAS WILL BE WATERED WITH SUBSURFACE DRIPLINE.

5. NATIVE GRASS AREAS WILL BE WATERED WITH OVERHEAD SPRAY HEADS.

6. LAWN AREAS WILL BE WATERED WITH OVERHEAD SPRAY HEADS.

7. DEPENDING ON SITE CONDITIONS AND AVAILABLE STATIONS, THE IRRIGATION SYSTEM WILL BE EITHER CONNECTED TO AN EXISTING CONTROLLER OR FURNISHED WITH A NEW CONTROLLER WITH A FLOW MONITOR, RAIN SENSOR AND SURGE PROTECTION.

HYDROZONES BASED UPON WCOLS PLANT WATER USEAGE

| AREA | WCOLS WATER | WCOLS WATER USEAGE | | | | | |
|----------------|--------------|-----------------------|--|--|--|--|--|
| +/- 520 SF | LOW - 0.5% | NEW TREES | | | | | |
| +/- 117,145 SF | HIGH - 83.0% | SPECIAL USE LAWN AREA | | | | | |
| +/- 6,140 SF | NONE - 4.5% | SYNTHETIC TURF AREA | | | | | |
| +/- 17,110 SF | NONE - 12% | BARK MULCH AREA | | | | | |
| +/- 141,715 SF | TOTAL AREA | | | | | | |
| | | | | | | | |

| IC OF CHURCHILL TTH COAST LIVE I CORTEN FENCE TO | <u>PLANT LIST</u> KEY <u>TREES</u> | QTY SYMBOL | BOTANICAL NAME | COMMON NAME | SIZE | SPACING | WATER USAGE | |
|--|--|------------|----------------------|-------------------|------------|---------|----------------|----------|
| | e to the state state of the state | 1 LINS | LAGERSTROEMIA INDICA | CRAPE MYRTLE | 36" BOX | | L | Pr Pr |
| RIST REPORT REMOVED. | | 25 QA | QUERCUS AGRIFOLIA | COAST LIVE OAK | 36" BOX | | VL | Q |
| PLANTING | GROUNDCOVE | ER | | | | | | |
| | | - | NATURAL TURF | SOD TO MATCH STAN | NFORD STAN | NDARD | Н | |
| AND | | - | SYNTHETIC TURF | MATCH STANF | ORD STAND | ARD | NONE | |
| | ₹ | - | BARK MULCH | MATCH STANFORD S | TANDARD | | NONE | _ |
| | | | | | | | | |
| | | | | | | | | 4 |

STANFORD UNIVERSITY

Project Name: Lacrosse Practice Field Project Address: 657 Masters Mall, Stanford CA. 94305 Quad/ Bldg. Number: 09-379

Stephen Wheeler Landscape Architects 744 Alabama Street, #331 San Francisco, CA 415-252-7075

> PO Box 460116 San Francisco, CA 94146

DESCRIPTION

ISSUES AND REVISIONS

NO. DATE

03.18.24 ASA SUBMITTAL 08.01.24 ASA RESUBMITTAL

PROJECT NUMBER

SHEET TITLE

LANDSCAPE NOTES

SCALE

SHEET NUMBER

L-1.02

Stanford Practice Lacrosse

Standford, CA

Lighting System

| Pole / Fixture Summary | | | | | | | | | | | |
|------------------------|-------------|------------|-------------|----------------|----------|---------|--|--|--|--|--|
| Pole ID | Pole Height | Mtg Height | Fixture Qty | Luminaire Type | Load | Circuit | | | | | |
| F1-F4 | 80' | 80' | 2 | TLC-LED-1200 | 2.34 kW | A | | | | | |
| | | 80' | 10 | TLC-LED-1500 | 14.10 kW | A | | | | | |
| | | 16' | 2 | TLC-BT-575 | 1.15 kW | A | | | | | |
| 4 | | | 56 | | 70.36 kW | | | | | | |

| Circuit Summary | | | | | | | | | |
|-----------------|-------------|----------|-------------|--|--|--|--|--|--|
| Circuit | Description | Load | Fixture Qty | | | | | | |
| A | Lacrosse | 70.36 kW | 56 | | | | | | |

| Fixture Type Summary | | | | | | | | | | | | |
|----------------------|--------------------|---------|---------|----------|----------|----------|----------|--|--|--|--|--|
| Туре | Source | Wattage | Lumens | L90 | L80 | L70 | Quantity | | | | | |
| TLC-LED-1500 | LED 5700K - 75 CRI | 1410W | 181,000 | >120,000 | >120,000 | >120,000 | 40 | | | | | |
| TLC-LED-1200 | LED 5700K - 75 CRI | 1170W | 150,000 | >120,000 | >120,000 | >120,000 | 8 | | | | | |
| TLC-BT-575 | LED 5700K - 75 CRI | 575W | 52,000 | >120,000 | >120,000 | >120,000 | 8 | | | | | |

| Single Luminaire Amperage Draw Chart | | | | | | | | | |
|--------------------------------------|---------------------------------|-------------|-------------|-------------|-------------|-------------|-------------|--|--|
| Driver (.90 min power factor) | Max Line Amperage Per Luminaire | | | | | re | | | |
| Single Phase Voltage | 208 (60) | 220 (60) | 240 (60) | 277 (60) | 347 (60) | 380 (60) | 480 (60) | | |
| TLC-LED-1500 | 8.4 | 7.9 | 7.3 | 6.3 | 5.0 | 4.6 | 3.6 | | |
| TLC-LED-1200 | 6.9 | 6.5 | 6.0 | 5.2 | 4.2 | 3.8 | 3.0 | | |
| TLC-BT-575 | 3.4 | 3.2 | 2.9 | 2.5 | 2.0 | 1.8 | 1.5 | | |

Light Level Summary

| Calculation Grid Summary | | | | | | | | | | | |
|--------------------------|---------------------------------|------|-----|--------------|---------|---------|----------|--------------|--|--|--|
| Grid Name | Calculation Metric | | | Illumination | - | | Circuits | Fixture Otv | | | |
| Sha Name | | Ave | Min | Max | Max/Min | Ave/Min | onouno | T IXture day | | | |
| Blanket | Horizontal | 13.4 | 0 | 83 | 0.00 | | A | 56 | | | |
| El Camino Spill | Horizontal | 0 | 0 | 0.01 | 0.00 | | A | 56 | | | |
| El Camino Spill | Max Candela (by Fixture) | 232 | 0 | 882 | 0.00 | | A | 56 | | | |
| El Camino Spill | Max Vertical Illuminance Metric | 0.01 | 0 | 0.03 | 0.00 | | A | 56 | | | |
| Lacrosse | Horizontal Illuminance | 75.7 | 68 | 79 | 1.17 | 1.11 | A | 56 | | | |

Not to be reproduced in whole or part without the written consent of Musco Sports Lighting, LLC. ©1981, 2024 Musco Sports Lighting, LLC.

E-1 PROJECT SUMMARY

| EQ | EQUIPMENT LIST FOR AREAS SHOWN | | | | | | | | | | | | |
|-----|--------------------------------|------|--------------------|--------------------|-------------------|---------------|--------------|----------------|--|--|--|--|--|
| | Р | ole | | | Luminaires | | | | | | | | |
| QTY | LOCATION | SIZE | GRADE ELEVATION | Mounting Height | LUMINAIRE TYPE | QTY / POLE | THIS GRID | OTHER GRIDS | | | | | |
| 2 | F1-F2 | 80' | - | 80' | TLC-LED-1200 | 2 | 2 | 0 | | | | | |
| | | | | 15.5' | TLC-BT-575 | 2 | 2 | 0 | | | | | |
| | | | | 80' | TLC-LED-1500 | 10 | 10 | 0 | | | | | |
| 2 | F3-F4 | 80' | - | 80' | TLC-LED-1500 | 10 | 10 | 0 | | | | | |
| | | | | 15.5' | TLC-BT-575 | 2 | 2 | 0 | | | | | |
| | | | | 80' | TLC-LED-1200 | 2 | 2 | 0 | | | | | |
| 4 | 4 TOTALS | | | | | | 56 | 0 | | | | | |

Stanford Practice Lacrosse Standford, CA

| GRID SUMMARY | |
|-----------------------|------------------|
| Name: | Lacrosse |
| Size: | 360' x 195' |
| Spacing: | 30.0' x 30.0' |
| Height: | 3.0' above grade |
| | 5.6 42010 8.440 |
| ILLUMINATION S | UMMARY |
| MAINTAINED HORIZONTA | AL FOOTCANDLES |
| | Entire Grid |
| Guaranteed Average: | 75 |
| Scan Average: | 75.67 |
| Maximum: | 79 |
| Minimum: | 68 |
| Avg / Min: | 1.11 |
| Guaranteed Max / Min: | 2 |
| Max / Min: | 1.17 |
| UG (adjacent pts): | 1.10 |
| CU: | 0.65 |
| No. of Points: | 84 |
| LUMINAIRE INFORMATIO | N |
| Applied Circuits: | А |
| No. of Luminaires: | 56 |
| Total Load: | 70.36 kW |

Guaranteed Performance: The ILLUMINATION described above is guaranteed per your Musco Warranty document and includes a 0.95 dirt depreciation factor.

Field Measurements: Individual field measurements may vary from computer-calculated predictions and should be taken in accordance with IESNA RP-6-15.

Electrical System Requirements: Refer to Amperage Draw Chart and/or the "Musco Control System Summary" for electrical sizing.

Installation Requirements: Results assume ± 3% nominal voltage at line side of the driver and structures located within 3 feet (1m) of design locations.

0.0 - Green color denote the largest foot candle #.# - Black color denotes the foot candles at the marker location 0.0 - Red color denotes zero foot candles at marker location

Not to be reproduced in whole or part without the written consent of Musco Sports Lighting, LLC. ©1981, 2024 Musco Sports Lighting, LLC.

E-2 ILLUMINATION SUMMARY

| EQ | EQUIPMENT LIST FOR AREAS SHOWN | | | | | | | | | | | | |
|-----|--------------------------------|------|--------------------|--------------------|-------------------|---------------|--------------|----------------|--|--|--|--|--|
| | P | ole | | | Luminaires | | | | | | | | |
| QTY | LOCATION | SIZE | GRADE ELEVATION | MOUNTING HEIGHT | LUMINAIRE TYPE | QTY / POLE | THIS GRID | OTHER GRIDS | | | | | |
| 2 | F1-F2 | 80' | - | 80' | TLC-LED-1200 | 2 | 2 | 0 | | | | | |
| | | | | 15.5' | TLC-BT-575 | 2 | 2 | 0 | | | | | |
| | | | | 80' | TLC-LED-1500 | 10 | 10 | 0 | | | | | |
| 2 | F3-F4 | 80' | - | 80' | TLC-LED-1500 | 10 | 10 | 0 | | | | | |
| | | | | 15.5' | TLC-BT-575 | 2 | 2 | 0 | | | | | |
| | | | | 80' | TLC-LED-1200 | 2 | 2 | 0 | | | | | |
| 4 | 4 TOTALS | | | | | | 56 | 0 | | | | | |

0.0 0. 0.0 0.0 0.0 .0.1 .0.1 L 0.2 0.1 0.1 0.0 0.0 0.2 0.3 0.3 0.0 0.1 0.1 .0.Q 0.1 0.1 0.1 0.1 0.3 0.5 0.8 0.9 0.9 0.8 0.6 0.4 0.1 0.0 0.1 0.1 0.0 0.1 0.0 0.0 p.4 p.5 p.4 p.7 1.4 2.0 2.6 2.6 2.8 3.0 2.6 1.8 p.9 p.5 p.6 p.4 0.0 0.0 0.3 .0.1 0.0 0.0 0.0 D.5 1.2 2.4 2.9 4.3 J.2 9.6 8.6 8.7 9.2 10.5 13.7 8.8 5.6 4.1 .0. .0.1 .D.2 1.3 p.6 p.3 p.1 p.0 p.0 2.9 D.0 D.0 D.1 D.3 1.1 37 9.7 15.5 16.5 28.1 38.0 28.1 27.8 29.0 33.5 46.1 28.3 20.5 18.7 10.2 3.9 1.2 D.4 D.1 D.0 D.0 0.0 0.1 0.2 0.6 1.8 9.6 31.<u>2 59.2 57.6 0.6 70.6 53.0 53.7 53.6 64.7 59.8 71.6 59.8 51.0 29.7 9.6 2.1 0.5 0.2 0.1 0.0</u> 18.9 50 9 79.2 78.0 78.0 78.7 79.1 79.0 78.0 78.0 77.4 78.1 78.4 76 9 47 2 14.5 3.1 D.8 D.2 D.1 D.0 D p.0 p.1 p.3 p.9 3.2 D.0 D.1 D.3 5.1 17.5 480 74.8 75.1 75.5 76.7 77.6 76.3 75.3 74.8 76.5 76.4 76.9 714 46.0 16.9 4.7 1.1 0.3 1.3 D.1 D.0 D ρ.0 ρ.1 ρ.3 1.4 6.1 21.8 4 4 69.9 73.4 74.3 73.8 74.1 74.9 74.0 72.0 74.3 74.6 73.2 66 43.8 19.0 5.8 1.4 0.3 0.1 0.0 0 0.Q. 0.Q. .0.3 <u>1.5</u> 6.4 21 70.2 74.5 76.8 75.6 74.2 75.8 74.5 73.0 75.1 76.8 75.1 £ 43.9 19.2 5.8 1.5 D.3 D.1 D.0 J4.6 J6.7 J8.1 J8.6 J7.2 J7.6 J6.7 J6.9 J8.5 J7.1 J7.0 J1 **0.0 0.0** .1.2 <u>44.8</u> 16.8 4.9 1.2 0.3 0.1 0.0 0.0 0.0 0.2 0.8 3.4 13.5 520 78.1 76.6 77.1 78.9 78.0 77.1 76.9 76.8 45 77.8 77.2 790 48.0 12.6 3.1 0.9 0.2 0.1 0.0 D.0 D.0 D.2 D.6 1.8 90 35.7 63.3 73.9 66.4 66.9 64.5 62.4 62.2 65.3 66.5 65.1 73.9 54.6 29.1 8.1 1.7 0.6 0.2 .0.1 1.0 <mark>-3.8 10.9 20.6 34.45 28.0 26.3 29.3 28.2 28.6 30.3 25.8 23.0 32.2 17.9 8.8</mark> 2 0.9 0.3 0.1 0.0 0.0 F4 7.4 6.8 7.5 8.4 8.8 8.9 8.4 7.4 6.4 6.6 4.5 2.7 D.2 D.6 1.4 3.2 5.2 1.2 D.5 D.2 D.1 D.0 🕻 00 p.5 p.8 1.0 p.9 p.6 1.4 2.3 2.6 2.6 2.3 1.3 p.5 p.6 p.7 p.4 p.2 p.1 p.0 p.0 0.8 0.1 0.1 0.2 0.1 0.1 0.1 0.3 0.6 0.8 0.8 0.6 0.3 0.1 0.1 0.1 0.1 0.1 0.0 .0.1 0.0 0. p.0 p.0 p.0 p.0 p.0 p.0 p.0 p.1 p.2 p.3 p.3 p.2 p.1 p.0 p.0 0.0 0.0 0.0 .0.0 D.0 D.0 0.0 0.1 0.1 0.1 0.0 0.0 01 00 00

Pole location(s) \oplus dimensions are relative to 0,0 reference point(s) \otimes

ENGINEERED DESIGN By: Aaron Rose · File #232514C · 05-Mar-24

Stanford Practice Lacrosse Standford, CA

| | GRID SUMMARY | |
|------------|----------------------|------------------|
| | Name: | Blanket |
| | Spacing: | 30.0' x 30.0' |
| | Height: | 3.0' above grade |
| - | ILLUMINATION SU | UMMARY |
| 100 | MAINTAINED HORIZONTA | L FOOTCANDLES |
| a land | | Entire Grid |
| | Scan Average: | 13.44 |
| 1 | Maximum: | 79 |
| 14 | Minimum: | 0 |
| ALL STREET | Avg / Min: | - |
| 1.00 | Max / Min: | - |
| Sec. 10 | UG (adjacent pts): | 58.15 |
| 8.0-5 | CU: | 0.93 |
| 2.2 | No. of Points: | 672 |
| Sea al | LUMINAIRE INFORMATIO | N |
| 744 | Applied Circuits: | Α |
| - | No. of Luminaires: | 56 |
| | Total Load: | 70.36 kW |
| | | |

Guaranteed Performance: The ILLUMINATION described above is guaranteed per your Musco Warranty document and includes a 0.95 dirt depreciation factor.

Field Measurements: Individual field measurements may vary from computer-calculated predictions and should be taken in accordance with IESNA RP-6-15.

Electrical System Requirements: Refer to Amperage Draw Chart and/or the "Musco Control System Summary" for electrical sizing.

Installation Requirements: Results assume ± 3% nominal voltage at line side of the driver and structures located within 3 feet (1m) of design locations.

#.# - Black color denotes

the foot candles at the marker location 0.0 - Red color denotes zero foot candles at

marker location

Not to be reproduced in whole or part without the written consent of Musco Sports Lighting, LLC. ©1981, 2024 Musco Sports Lighting, LLC.

| EQ | UIPMENT LI | IST FOR | AREAS SH | IOWN | | | | |
|-----|------------|---------|--------------------|--------------------|-------------------|---------------|--------------|----------------|
| | F | Pole | | | Luminaires | | | |
| QTY | LOCATION | SIZE | GRADE ELEVATION | MOUNTING HEIGHT | LUMINAIRE TYPE | QTY / POLE | THIS GRID | OTHER GRIDS |
| 2 | F1-F2 | 80' | - | 80' | TLC-LED-1200 | 2 | 2 | 0 |
| | | | | 15.5' | TLC-BT-575 | 2 | 2 | 0 |
| | | | | 80' | TLC-LED-1500 | 10 | 10 | 0 |
| 2 | F3-F4 | 80' | - | 80' | TLC-LED-1500 | 10 | 10 | 0 |
| | | | | 15.5' | TLC-BT-575 | 2 | 2 | 0 |
| | | | | 80' | TLC-LED-1200 | 2 | 2 | 0 |
| 4 | | | TOTALS | | | 56 | 56 | 0 |

ENGINEERED DESIGN By: Aaron Rose · File #232514C · 05-Mar-24

200'

400'

Stanford Practice Lacrosse Standford, CA

| GRID SUMMARY | |
|------------------------------|--|
| Name: Spacing: Height: | El Camino Spill 30.0' 0.0' above grade |
| ILLUMINATION S | UMMARY |
| HORIZONTAL FOOTCAND | LES |
| | Entire Grid |
| Scan Average: | 0.0016 |
| Maximum: | 0.01 |
| Minimum: | 0.00 |
| No. of Points: | 46 |
| LUMINAIRE INFORMATIO | N |
| Applied Circuits: | A |
| No. of Luminaires: | 56 |
| Total Load: | 70.36 kW |

Guaranteed Performance: The ILLUMINATION described above is guaranteed per your Musco Warranty document.

Field Measurements: Individual field measurements may vary from computer-calculated predictions and should be taken in accordance with IESNA RP-6-15.

Electrical System Requirements: Refer to Amperage Draw Chart and/or the "Musco Control System Summary" for electrical sizing.

Installation Requirements: Results assume ± 3% nominal voltage at line side of the driver and structures located within 3 feet (1m) of design locations.

#.# - Black color denotes the foot candles at the marker location

0.0 - Red color denotes zero foot candles at marker location

Pole location(s) Φ dimensions are relative to 0,0 reference point(s) \otimes

Not to be reproduced in whole or part without the written consent of Musco Sports Lighting, LLC. ©1981, 2024 Musco Sports Lighting, LLC.

| EQ | UIPMENT LI | IST FOR | AREAS SH | IOWN | | | | |
|-----|------------|---------|--------------------|--------------------|-------------------|---------------|--------------|----------------|
| | F | Pole | | | Luminaires | | | |
| QTY | LOCATION | SIZE | GRADE ELEVATION | MOUNTING HEIGHT | LUMINAIRE TYPE | QTY / POLE | THIS GRID | OTHER GRIDS |
| 2 | F1-F2 | 80' | - | 80' | TLC-LED-1200 | 2 | 2 | 0 |
| | | | | 15.5' | TLC-BT-575 | 2 | 2 | 0 |
| | | | | 80' | TLC-LED-1500 | 10 | 10 | 0 |
| 2 | F3-F4 | 80' | - | 80' | TLC-LED-1500 | 10 | 10 | 0 |
| | | | | 15.5' | TLC-BT-575 | 2 | 2 | 0 |
| | | | | 80' | TLC-LED-1200 | 2 | 2 | 0 |
| 4 | | | TOTALS | 5 | | 56 | 56 | 0 |

ENGINEERED DESIGN By: Aaron Rose · File #232514C · 05-Mar-24

200'

400'

Stanford Practice Lacrosse Standford, CA

| GRID SUMMARY | |
|----------------------|------------------|
| Name: | El Camino Spill |
| Spacing: Height: | 0.0' above grade |
| 5 | C C |
| ILLUMINATION S | UMMARY |
| MAX VERTICAL FOOTCAN | IDLES |
| | Entire Grid |
| Scan Average: | 0.0062 |
| Maximum: | 0.03 |
| Minimum: | 0.00 |
| No. of Points: | 46 |
| LUMINAIRE INFORMATIO | N N |
| Applied Circuits: | A |
| No. of Luminaires: | 56 |
| Total Load: | 70.36 kW |

Guaranteed Performance: The ILLUMINATION described above is guaranteed per your Musco Warranty document.

Field Measurements: Individual field measurements may vary from computer-calculated predictions and should be taken in accordance with IESNA RP-6-15.

Electrical System Requirements: Refer to Amperage Draw Chart and/or the "Musco Control System Summary" for electrical sizing.

Installation Requirements: Results assume ± 3% nominal voltage at line side of the driver and structures located within 3 feet (1m) of design locations.

#.# - Black color denotes the foot candles at the marker location

0.0 - Red color denotes zero foot candles at marker location

Pole location(s) Φ dimensions are relative to 0,0 reference point(s) \otimes

Not to be reproduced in whole or part without the written consent of Musco Sports Lighting, LLC. ©1981, 2024 Musco Sports Lighting, LLC.

E-5 ILLUMINATION SUMMARY

| EQU | JIPMENT L | IST FOR | AREAS SH | IOWN | | | | |
|-----|-----------|---------|--------------------|--------------------|-------------------|---------------|--------------|----------------|
| | F | Pole | | | Luminaires | | | |
| QTY | LOCATION | SIZE | GRADE ELEVATION | Mounting Height | LUMINAIRE TYPE | QTY / POLE | THIS GRID | OTHER GRIDS |
| 2 | F1-F2 | 80' | - | 80' | TLC-LED-1200 | 2 | 2 | 0 |
| | | | | 15.5' | TLC-BT-575 | 2 | 2 | 0 |
| | | | | 80' | TLC-LED-1500 | 10 | 10 | 0 |
| 2 | F3-F4 | 80' | - | 80' | TLC-LED-1500 | 10 | 10 | 0 |
| | | | | 15.5' | TLC-BT-575 | 2 | 2 | 0 |
| | | | | 80' | TLC-LED-1200 | 2 | 2 | 0 |
| 4 | | | TOTALS | | | 56 | 56 | 0 |

ENGINEERED DESIGN By: Aaron Rose · File #232514C · 05-Mar-24

200'

400'

Stanford Practice Lacrosse Standford, CA

| GRID SUMMARY | |
|-----------------------|------------------|
| Name: | El Camino Spill |
| Spacing: | 30.0' |
| Height: | 0.0' above grade |
| | |
| ILLUMINATION S | UNINARY |
| CANDELA (PER FIXTURE) | |
| | Entire Grid |
| Scan Average: | 231.8350 |
| Maximum: | 882.38 |
| Minimum: | 0.00 |
| No. of Points: | 46 |
| LUMINAIRE INFORMATIO | N |
| Applied Circuits: | A |
| No. of Luminaires: | 56 |
| Total Load: | 70.36 kW |

Guaranteed Performance: The ILLUMINATION described above is guaranteed per your Musco Warranty document.

Field Measurements: Individual field measurements may vary from computer-calculated predictions and should be taken in accordance with IESNA RP-6-15.

Electrical System Requirements: Refer to Amperage Draw Chart and/or the "Musco Control System Summary" for electrical sizing.

Installation Requirements: Results assume ± 3% nominal voltage at line side of the driver and structures located within 3 feet (1m) of design locations.

#.# - Black color denotes the foot candles at the marker location

0.0 - Red color denotes zero foot candles at marker location

Pole location(s) Φ dimensions are relative to 0,0 reference point(s) \otimes

Not to be reproduced in whole or part without the written consent of Musco Sports Lighting, LLC. ©1981, 2024 Musco Sports Lighting, LLC.

E-6 ILLUMINATION SUMMARY

Pole location(s) \oplus dimensions are relative to 0,0 reference point(s) 🚫

Stanford Practice Lacrosse Standford, CA

Equipment Layout

INCLUDES: · Lacrosse

Electrical System Requirements: Refer to Amperage Draw Chart and/or the "**Musco Control System Summary**" for electrical sizing.

Installation Requirements: Results assume ± 3% nominal voltage at line side of the driver and structures located within 3 feet (1m) of design locations.

| Eq | uipmen | t List Fo | or Areas | s Shown | 1 | |
|-----|----------|-----------|--------------------|----------------------|----------------|----------|
| | | Pole | | | Luminaires | |
| QTY | LOCATION | SIZE | GRADE ELEVATION | ABOVE GRADE LEVEL | LUMINAIRE TYPE | QTY/POLE |
| 4 | F1-F4 | 80' | - | 80' | TLC-LED-1200 | 2 |
| | | | | 80' | TLC-LED-1500 | 10 |
| | | | | 15.5' | TLC-BT-575 | 2 |
| 4 | | | Totals | 5 | | 56 |

| Single Luminaire Amp | era | ge Di | raw | Char | t | | |
|------------------------|------|--------|------|--------|--------|--------|------|
| Driver Specifications | | Line A | mper | age Pe | er Lum | inaire | |
| (.90 min power factor) | | | (m | ax dra | w) | | |
| Single Dhase Veltage | 208 | 220 | 240 | 277 | 347 | 380 | 480 |
| Single Phase voltage | (60) | (60) | (60) | (60) | (60) | (60) | (60) |
| TLC-BT-575 | 3.3 | 3.2 | 2.9 | 2.5 | 2.0 | 1.8 | 1.5 |
| TLC-LED-1200 | 6.9 | 6.5 | 6.0 | 5.2 | 4.2 | 3.8 | 3.0 |
| TLC-LED-1500 | 8.4 | 7.9 | 7.3 | 6.3 | 5.0 | 4.6 | 3.6 |
| | | | | | | | |

Note:

Н

3

The beams displayed on this sheet represent the precise targeting of the light fixtures. Each individual beam corresponds to a specific luminaire, and the points where the lines terminate indicate the exact locations where the light hits the ground.

Not to be reproduced in whole or part without the written consent of Musco Sports Lighting, LLC. ©1981, 2023 Musco Sports Lighting, LLC.

POLE(S): F1-F4

Musco 80FT Light-Structure System[™] pole TLC for LED[™] luminaires (10) TLC-LED-1500 (2) TLC-LED-1200

| PROJECT 2 DRAWN E 2 DRAWN E 3 SCALE: 2 DATE: 08/ 08/ 08/ 08/ | DATE: BY: R.L. | REVISIONS: | | Stanford Practice Lacrosse |
|--|----------------|------------|---|------------------------------|
| NUMBER: 37: A.Rose NTS NUMBER: E-8 | | | HUSCO. P.O. Box 808 100 1st Avenue West Oskaloosa, Iowa 52577 | Standford CA |
| <u> </u> | | | +1-800-825-6020 +1-641-673-0411 | Pole Configuration Drawing B |

| <section-header><section-header><section-header><section-header><section-header><section-header><text><list-item><list-item><section-header><list-item></list-item></section-header></list-item></list-item></text></section-header></section-header></section-header></section-header></section-header></section-header> | Applications The product family car be effectively used in outdoor wall mount locations, packing it, cargo door, high wall, areae, security, etc.) One cardination is used in a static on a static in a static on a static | <section-header><section-header><section-header><section-header><section-header><section-header><text><list-item><list-item><list-item><list-item><section-header><list-item><list-item></list-item></list-item></section-header></list-item></list-item></list-item></list-item></text></section-header></section-header></section-header></section-header></section-header></section-header> | <section-header><section-header><section-header><section-header><section-header><section-header><section-header><text><list-item><list-item><list-item><list-item><section-header><text><list-item><list-item><list-item><section-header><section-header></section-header></section-header></list-item></list-item></list-item></text></section-header></list-item></list-item></list-item></list-item></text></section-header></section-header></section-header></section-header></section-header></section-header></section-header> | b | 11 3 Øtcp | | |) Wall Pa |
|---|---|---|---|---|--|---|---|--|
| The product family can be effectively used in outdoor wall moute factors is privately develop if plang (i.e., privately develop (i.e., privately (i.e., privately (i.e | This product family can be effectively used in outdoor wall mourt locations in commanded, induiting interal and institutional eventor lighting it is, papily lack, space (and lamba the locations in the lamba the locations is a setting HD well pack is the lamba powhercom | <section-header><section-header><text><section-header></section-header></text></section-header></section-header> | <section-header><text><text><list-item><list-item><section-header><section-header></section-header></section-header></list-item></list-item></text></text></section-header> | Applications | | | | |
| parking bit, congo door, high wall, area, security, etc.). Construction 1 Octo a duminim houting 1 Importivational polycatic onde lens 3 Organing Temperature: 20 C to 40 C Electrical 2 Octoand Teleng S0,000 hour life 3 Organic Materia eskithing H10 wall pocks 3 Organic Materia | parking bit, corgo door, high woll, oneo, security, iste). Construction I one cost duminum housing I one cost duminum housing I one cost duminum housing I operating Temperature: 20 C to 40 C Electrical I operating Temperature: 20 C Electrical I opera | <section-header><section-header><section-header><section-header><section-header></section-header></section-header></section-header></section-header></section-header> | | This product family car in commercial, industrial | be effectively used in outdoor w I, retail and institutional exterior | all mount locations lighting (i.e., | Item Number | |
| Colspan="2">Colspan="2"Colspan="2"Colspan="2"Colspan=""2"Colspan=""2"Colspan=""2"Colspan=""2"Colspan=""2"Colspan=""2"Colspan=""2"Cols | Construction Description 10 procession 1 | <section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><complex-block><section-header></section-header></complex-block></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header> | <section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header> | parking lot, cargo door, | high wall, area, security, etc). | ata: 0 5 84 K | Notes | Туре |
| <section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header> | <section-header><section-header><section-header><section-header><section-header><section-header></section-header></section-header></section-header></section-header></section-header></section-header> | <section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><text></text></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header> | <section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header> | Die-cast aluminum hoi Impactresistant polya | using arbonate lens | | | |
| <section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><list-item><list-item><text></text></list-item></list-item></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header> | <section-header><section-header><section-header><section-header><section-header><section-header><text><list-item><list-item></list-item></list-item></text></section-header></section-header></section-header></section-header></section-header></section-header> | <section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header> | <section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header> | Durable dark bronze Same footprint as exist | powdercoat sting HID wall packs | | | |
| Encircul 6. Upwel doe not and B 6. Spectra mode for long 50,000 hour life 6. Spectra mode for long 50,000 hour life (Depend Microwsey Motion Sensor (MS) Optional Microwsey Motion Sensor (MS) Point Microwsey Motion Sensor (M | Electrical 0:Use we location noted 0:Spear noted for long 50,000 hour life 0:Spear noted for long 50,000 hour life 0:Dirional Microwave Mation Sensor (MS) Optional Microwave Mation Sensor (MS) 0:Dirional Microwave Mation Sensor (MC) 0:Dirional Microwave Mation Sensor (MC) <tr< td=""><td><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><text></text></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></td><td><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></td><td>Operating Temperatur</td><td>re: -20 C to 40 C</td><td></td><td>A</td><td>and the second s</td></tr<> | <section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><text></text></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header> | <section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header> | Operating Temperatur | re: -20 C to 40 C | | A | and the second s |
| Lesty-baccess wing compartment System inder for long 50,000 hour life Efficiently delivers up to 105 IPW Optional Microwave Motion Sensor (MS) Optional Microwave Motion Sensor (MS) Prismatic polycathonate lens Delivers bright, white light and excellent uniformity Catalog Ordering Matrix Example: WP5500140K Color Color Example: WP5500140K Color Example: WP5500140K Color Example: WP5500140K Color Example: WP5500140K Example: WP5500140K Color Example: WP5500140K Example: WP5500140K Find Installed Accessories: Field Installed Accessories: Color Example: W0 00 min. waterproof emergency battery backup For the most uplotdate specs and warranty information, please visit www.tcpi.com So = 5000 (15 M) 00 min. waterproof emergency battery backup For the most uplotdate specs and warranty information, please visit www.tcpi.com Color Example: Motor One Matrix Defined Matrix Def | Early-foractions wring comparison for log 50,000 hour life Efficiently delivers up to 105 IPW Optional Photocell IPC Optional Photocell IPC Politoral Photocell IPC Politoratic polycorbonote lens Politoratic | a. b. sydaen costs wring comparison b. Sydaen costs (brong SO, COS More Mile) c. Sydaen costs (brong SO, COS More Mile) c. Optical Photocolf (PC) | 10. objects one of long 30,000 huits 10. objects one of long 30,000 h | cULus wet location ra | ted | | Listings | |
| Chicken Monice of Mon | • Diricult Vacasce (FC) • Optional Microwove Motion Sensor (VS) Optional Microwove Motion Sensor (VS) • Delivers bright, white light and excellent uniformity • Delivers bright, white light and excellent uniformity • Delivers bright, white light and excellent uniformity • Catalog Ordering Matrix • Catalog Ordering Matrix • Warrange • Mainty | <section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header> | • Discusping burnessel (FG) • Optional Microweek Medican Sensor (MS) • Discusping • Ninnetic polycarborate lens • Biblens tright, white light and excellent uniformity • Cacloog Ordering Matrix Example: WP5500140K • Marcing < | Easy-to-access wiring System rated for long Efficiently delivers up | 50,000 hour life | | RoHS Compliant DLC v5.1 Standard | 1 |
| Prismatic polycarbonate lans Delivers bright, while light and excellent uniformity Prismatic polycarbonate lans Delivers bright, while light and excellent uniformity Prevent limited warranty against defects in manufacturing: Prevent limited warranty against defects in manufacturing Prevent limited warranty against defects in m | For the most upstockeds express for the first series and warranty information, please visit www.tpi.com To the most upstockeds specs and warranty information, please visit www.tpi.com To the most upstockeds specs and warranty information, please visit www.tpi.com To the most upstockeds specs and warranty information, please visit www.tpi.com To the most upstockeds specs and warranty information, please visit www.tpi.com To the most upstockeds specs and warranty information, please visit www.tpi.com To the most upstockeds specs and warranty information, please visit www.tpi.com To the most upstockeds specs and warranty information, please visit www.tpi.com To the most upstockeds specs and warranty information, please visit www.tpi.com To the most upstocked specs and warranty information, please visit www.tpi.com To the most upstocked specs and warranty information, please visit www.tpi.com To the most upstocked specs and warranty information, please visit www.tpi.com To the most upstocked specs and warranty information, please visit www.tpi.com To the most upstocked specs and warranty information, please visit www.tpi.com To appear the most upstocked specs and warranty information, please visit www.tpi.com To appear the most upstocked specs and warranty information, please visit www.tpi.com To appear the most upstocked specs and warranty information, please visit www.tpi.com To appear the most upstocked specs and warranty information, please visit www.tpi.com To appear the most upstocked specs and warranty information, please visit www.tpi.com To appear the most upstocked specs and warranty information, please visit www.tpi.com To appear the most upstocked specs and warranty information, please visit www.tpi.com To appear the most upstocked specs and warranty information, please visit www.tpi.com To appear the most upstocked specs and warranty information, please visit www.tpi.com To appear the most upstocked by the to the tothere wareated by the to the to the tothere warrant warrant warr | Correst Potencie Case van inneted vararry against defects in marufacturing 9 betwees bright, while light and excellent uniformity Image: Correst of the second secon | Cores Cale was bright, while light and excellent uniformity Fer year linked warrang against defects in nonulcuture Very weight while light and excellent uniformity warrang year of the polycarbon was and the polycarbon was apain with the light and excellent uniformity warrang year of the polycarbon was apain | Optional Photocell (PC Optional Microwave | C) Mation Sensar (MS) | | Warranty | |
| Pismotic polycarbonate lens Delwers bright, white light and excellent uniformity Terr Wer Wer Wer Street Constraints Terr Wer Wer Wer Wer Wer Wer Wer Wer Wer | Pismatic polycarbonate lans Delivers bright, white light and excellent uniformity Tor View U U U U U U U U U U U U U U U U U U U | Pismatic polycarbonate lens Delvass bright, while light and excellent unformity: The War Strange of the first of the polycarbonate lens The War Strange of the polycarbonate lens The Manue of the polycarbonate lenses and warranty information, please visit www.tcpi.com The monat uptoclate specs and warranty information, please visit www.tcpi.com The monat uptoclate specs and warranty information, please visit www.tcpi.com The monat uptoclate specs and warranty information, please visit www.tcpi.com The monat uptoclate specs and warranty information, please visit www.tcpi.com The monat uptoclate specs and warranty information, please visit www.tcpi.com The monat uptoclate specs and warranty information, please visit www.tcpi.com The monat uptoclate specs and warranty information, please visit www.tcpi.com The monat uptoclate specs and warranty information, please visit www.tcpi.com The monat uptoclate specs and warranty information, please visit www.tcpi.com The monat uptoclate specs and warranty information, please visit www.tcpi.com The monat uptoclate specs and warranty information, please visit www.tcpi.com The monate uptoclate specs and warranty information, please visit www.tcpi.com The monate uptoclate spece and warranty information, please visit www.tcpi.com The monate uptoclate spece and warranty information, please visit www.tcpi.com The mon | Plakes bight, while light and excellent uniformity: We we were bight, while light and excellent uniformity: Catalog Ordering Matrix Example: WP5500140K <u>AMMEY ALMARE MACKAGE VOLTAGE VOLTAGE ACCOUNT ACCOUNT OF THE PERMIT ACCOUNT INSTALLED ATTAGE</u> <u>AMMEY LUMER MACKAGE VOLTAGE VOLTAGE ACCOUNT AC</u> | Optics | 20 /2 | | Five year limited warranty | against defects in manufacturing. |
| For the most upboddle specs and warranty information, please visit www.tcpi.com The most upboddle specs and warranty information, please visit www.tcpi.com The most upboddle specs and warranty information, please visit www.tcpi.com The most upboddle specs and warranty information, please visit www.tcpi.com The most upboddle specs and warranty information, please visit www.tcpi.com The most upboddle specs and warranty information, please visit www.tcpi.com The most upboddle specs and warranty information, please visit www.tcpi.com The most upboddle specs and warranty information, please visit www.tcpi.com Ter 25 Gmps Dr. Aurorg, 0hio 44702 P.800-374-1496 tqt.com ext attagramma W attagramma | Intermediate speces and warranty information, please visit www.tcpi.com ION Control Marrial Reserves and warranty information, please visit www.tcpi.com ION Control Marrial Reserves and warranty information, please visit www.tcpi.com ION Control Marrial Reserves and warranty information, please visit www.tcpi.com ION Control Marrial Reserves and warranty information, please visit www.tcpi.com ION Control Reserves and warranty information, please visit www.tcpi.com ION Control Reserves and warranty information, please visit www.tcpi.com ION Control Reserves and warranty information, please visit www.tcpi.com ION Control Reserves and warranty information, please visit www.tcpi.com ION Control Reserves and warranty information, please visit www.tcpi.com ION Control Reserves and warranty information, please visit www.tcpi.com ION Control Reserves and warranty information, please visit www.tcpi.com ION Control Reserves and warranty information, please visit www.tcpi.com ION Control Reserves and warranty information, please visit www.tcpi.com ION Control Reserves and warranty information, please visit www.tcpi.com ION Control Reserves and warranty information, please visit www.tcpi.com ION Control Reserves and warranty information, please visit wwww.tcp | Image: Control of Contro | <image/> Image: Control of the control of t | Prismatic polycarboneDelivers bright, white | ate lens light and excellent uniformity | | Front View | Side View |
| For the most up-to-date specs and warranty information, please visit www.tcpi.com. Image: Construction of the most up-to-date specs and warranty information, please visit www.tcpi.com. For the most up-to-date specs and warranty information, please visit www.tcpi.com. Image: Construction of the most up-to-date specs and warranty information, please visit www.tcpi.com. Image: Construction of the most up-to-date specs and warranty information, please visit www.tcpi.com. Image: Construction of the most up-to-date specs and warranty information, please visit www.tcpi.com. Image: Construction of the most up-to-date specs and warranty information, please visit www.tcpi.com. Image: Construction of the most up-to-date specs and warranty information, please visit www.tcpi.com. Image: Construction of the most up-to-date specs and warranty information, please visit www.tcpi.com. Image: Construction of the most up-to-date specs and warranty information, please visit www.tcpi.com. Image: Construction of the most up-to-date specs and warranty information, please visit www.tcpi.com. Image: Construction of the most up-to-date specs and warranty information, please visit www.tcpi.com. Image: Construction of the most up-to-date specs and warranty information, please visit www.tcpi.com. Image: Construction of the most up-to-date specs and warranty information, please visit www.tcpi.com. Image: Construction of the most up-to-date spece | Events Color Example: WP5500140K Multy UMEN PACKAGE VOLTAGE COLOR WP - Wall Pack 55 - 5800L (55W) 001 - 120:277V 30K - 4000K Blank - No Addon WP - Wall Pack 55 - 5800L (55W) 001 - 120:277V 30K - 4000K Blank - No Addon Field Installed Accessories: Image: State of the most uptodate specs and warranty information, please visit www.tcpi.com MS - Microwave Bi-level Dimini For the most uptodate specs and warranty information, please visit www.tcpi.com Image: State of the most uptodate specs and warranty information, please visit www.tcpi.com Image: State of the most uptodate specs and warranty information, please visit www.tcpi.com Tor 305 (ampsp. br. [Auron, 0bio 44202] P. 800:324:1496 [tpi.com Image: State of the UCC PL to State of the | Image: contrast of the second seco | <image/> AMARY CALL ALMEN PACKAGE NULLAGE ACCOUNT MERNAULE MAINING MARKANAUE NULLAGE NULLAGE ACCOUNT MERNAULE MAINING MARKANE NULLAGE NULLAGE ACCOUNT MERNAULE Maining Markane NULLAGE NULLAGE ACCOUNT MERNAULE Maining Markane NULLAGE NULLAGE Markane Nullage | | | | | |
| For the most uptodate specs and warranty information, please visit www.tcpi.com For the most uptodate specs and warranty information, please visit www.tcpi.com For the most uptodate specs and warranty information, please visit www.tcpi.com For the most uptodate specs and warranty information, please visit www.tcpi.com For the most uptodate specs and warranty information, please visit www.tcpi.com For the most uptodate specs and warranty information, please visit www.tcpi.com For the most uptodate specs and warranty information, please visit www.tcpi.com For the most uptodate specs and warranty information, please visit www.tcpi.com For the most uptodate specs and warranty information, please visit www.tcpi.com For the most uptodate specs and warranty information, please visit www.tcpi.com For the most uptodate specs and warranty information, please visit www.tcpi.com For the most uptodate specs and warranty information, please visit www.tcpi.com For the most uptodate specs and warranty information, please visit www.tcpi.com For the most uptodate spece and warranty information, please visit www.tcpi.com For the most uptodate spece and warranty information, please visit www.tcpi.com For the most uptodate spece and warranty information, please visit www.tcpi.com For the most uptodate spece and warranty information, please visit www.tcpi.com For the most uptodate spece and warranty information, please visit www.tcpi.c | Events Cotalog Ordering Matrix Example: WP5500140K | Line code of the state of t | <section-header></section-header> | | | | | • <u>3</u> ⊕ |
| For the most upfordate specs and warranty information, please visit www.tcpi.com Image: Color to account of the product regulated on the DCC QPL to warrant of the product regulated on the DCC QPL to warrant of the product regulated on the DCC QPL to warrant | Catalog Ordering Matrix Example: WP5500140K FAMILY LUMEN PACKAGE VOLTAGE COLOR FACTORY INSTALLED OPTIO WP - Woil Pack 55 - 5800L (55W) 001 - 120:277V 40K - 4000K Blank - No Addon WP - Woil Pack 55 - 5800L (120W) 001 - 120:277V 40K - 4000K Blank - No Addon Field Installed Accessories: WS - Microwave Bi-level Dimmir MS - Microwave Bi-level Dimmir For the most up-to-date specs and warranty information, please visit www.tcpi.com: V V W 90 min. waterproof emergency battery backup For the most up-to-date specs and warranty information, please visit www.tcpi.com: V V V V V V V V V Soft - Soft | Catalog Ordering Matrix Example: WP5500140K <u>inverse verse ve</u> | Example website Color | | | | | |
| Catalog Ordering Matrix Example: WP5500140K FAMILY LUMEN PACKAGE VOLTAGE COLOR FACTORY INSTALLED OPTION WP - Wall Pack 55 - 5800L (55W) 001 - 120:277V 40K - 4000K Blonk - No Addon KP - Wall Pack 120 - 12600L (120W) 001 - 120:277V 40K - 4000K Blonk - No Addon Field Installed Accessories: Exempter value MS - Microwave Bi-level Dimming For the most up-to-date specs and warranty information, please visit www.tcpi.com. Image: Color of the product as packs and warranty information, please visit www.tcpi.com. CP - 323 Compus Dr. Auroro, Ohio 44202 P: 800-324-1496 tipi.com ettr 00.222/911870 | Catalog Ordering Matrix Example: WP5500140K FAMILY LUMEN PACKAGE VOLTAGE COLOR FACTORY INSTALLED OPTIO WP - Wall Pack 55 - 5800L (55W) 001 - 120-277V 40K - 4000K Blank - No Add on 120 - 12600L (120W) 001 - 120-277V 40K - 4000K Blank - No Add on Field Installed Accessories: MS - Microwave Bilevel Dimmir Field Installed Accessories: MS - Microwave Bilevel Dimmir CPEBATTERY 8WV 90 min. waterproof emergency battery backup State Sta | Catalog Ordering Matrix Example: WP5500140K Image: State of the stat | Catalog Ordering Matrix Example: WP5500140K Image: State of the most upfordate specs and warranty information, please visit www.tcpi.com Image: State of the Matrix State o | | an sugar | | 12 | م.9° |
| FAMILY LUMEN PACKAGE VOLTAGE COLOR TEMPERATURE FACTORY INSTALLED OPTION WP - Wall Pack 55 - 5800L (55W) 120 - 12600L (120W) 001 - 120:277V 40K - 4000K 50K - 5000K Blank - No Addon PC - Button Photocell MS - Microwave Bi-level Dimming Field Installed Accessories: Image: CPEBATTERY BWV 90 min, waterproof emergency battery backup For the most up-to-date specs and warranty information, please visit www.tcpi.com Image: CPEBATTERY Ima | FAMILY LUMEN PACKAGE VOLTAGE COLOR TEMPERATURE FACTORY INSTALLED OPTIO WP - Wall Pack 55 - 5800L (55W) 120 - 12600L (120W) 001 - 120:277V 40K - 4000K S0K - 5000K Blank - No Addon PC - Bution Photocell MS - Microwave Bi-level Dimmir Field Installed Accessories: Item Number Description MS - Microwave Bi-level Dimmir For the most up-to-date specs and warranty information, please visit www.tcpi.com TCP* 325 Compus Dr. Auroro, Ohio 44202 P: 800-324-1496 tpi.com Image: State of the product are updited on the DCC OPC. Is to product, please could the DCC Owalled Poduct Lip or www.state 5 % LED WALL PACK LIGHT SPECIFICATION LED WALL PACK LIGHT SPECIFICATION 5 % | FAMILY LUMEN PACKAGE VOLTAGE COLOR FACTORY INSTALLED OPTION WP - Wail Pack 55 - 5800L (55W) 001 - 120:277V 40K - 4000K Blonk - No Addon Field Installed Accessories: SK - 5000K Blonk - No Addon PC - button Photocell MS - Microwave Bilevel Dimming Field Installed Accessories: Item Number Description MS - Microwave Bilevel Dimming For the most up-to-date specs and warranty information, please visit www.tcpi.com Item State and addition of the 44202 [P: 800:324-1496 tpi.com Item company Br. [Arrong, 0hio 44202] P: 800:324-1496 tpi.com S Gmps Br. [Arrong, 0hio 44202] P: 800:324-1496 tpi.com S S 33 LED WALL PACK LIGHT SPECIFICATION | EAMILY LUMEN PACKAGE VOLTAGE COOR TEMPERATURE EMPERATURE FACTORY INSTALLED OPTION (WP - Woll Pack S5 - 5800L (SSW) 120 - 12600L (120W) 001 - 120-277V GOK = 4000C SSK = 5000C Blank - No Addon PC - Buton Photocell MS - Microwove Bi-level Dimmin Field Installed Accessories: Imm Number Description MS - Microwove Bi-level Dimmin CPEBATTERY BW 90 min. waterproof emergency battery backup MS - Microwove Bi-level Dimmin For the most uprocedule specs and warranty information, please visit www.tcpit.com ICP* 232 Sompto FL Javero, Ohio 44202 P. 800-324-1496 tepi.com COURT OF Store Structure of the product are apalled on the DIC OFL is to product, please one of the product are apalled on the DIC OFL is or product, please count the UC Challed Photech Lie or wave 3 A LED WALL PACK LIGHT SPECIFICATION 3 | Catalog O | rdering Matrix | Example: WP55001 | 40K | |
| WP - Wait Pack SS - SBUDE (SSW) 001 - 120-277V 40K - 4000K Blank - No Addion Field Installed Accessories: Item Number Description MS - Microwave Bi-level Dimmin CPEBATTERY 8W 90 min. waterproof emergency battery backup So K - So W - Microwave Bi-level Dimmin For the most up-to-date specs and warranty information, please visit www.tcpi.com Exercise of the most up-to-date specs and warranty information, please visit www.tcpi.com TCP* 325 Campus Dr. Aurora, Ohio 44202 P: 800-324-1496 tqi.com 5 ¥ Store of the product are qualified on the DIC OPL To ve product, please consult the DIC QPL To ve product, please consult the DIC QPL To ve product, please consult the DIC QPL To ve product are www.de 5 ¥ | WP - Wall Pack 35 - 3800(.053W) 120 - 126001 (120W) WI - 120-277V Mick - 4000K 50K - 5000K Blank - No Addon PC - Button Photocell MS - Microwave Bi-level Dimmir Field Installed Accessories: Item Number Description CPEBATTERY BW 90 min. waterproof emergency battery backup For the most up-to-date specs and warranty information, please visit www.tcpi.com. Image: CP* 225 Compus Dr. Aurore, Ohio 44202 P: 800-324-1496 tqi.com 5 St TCP* 225 Compus Dr. Aurore, Ohio 44202 P: 800-324-1496 tqi.com Image: CP* Product, please consulting Photocell Up of the product are qualified on the DIC OPL to v product, please consulting Photocel Up of www.de 5 St Total Westows of the product are qualified on the DIC OPL to v product, please consulting Photocel Up of www.de 5 St Total Westows of the product are qualified on the DIC OPL to v product, please consulting Photocel Up of www.de 5 St | WP- Weil Pack 35-38000 [35W] WI = 120-277V Addx = 4000K Bink = No Adda in RC = Buttom Photocoling MS = Microwave Bilevel Dimming Field Installed Accessories: <u>Intern Number</u> <u>Description</u> CPEBATTERY <u>Description</u> CPEBATTERY BW 90 min. waterproof emergency battery backup For the most up-to-date specs and warranty information, please visit www.tcpi.com <u>TCP* 232 Gmpus Dr. Aurorg, 0hio 44202 P. 800-324-1496 tgi.com estr of 322/misroe <u>ED WALL PACK LIGHT SPECIFICATION </u> <u>ST % </u> <u>Description for the DC CAddied Products is a wave determined <u>3 LED WALL PACK LIGHT SPECIFICATION </u></u></u> | WP - Weil Pack 33 - 36000 (25 W) W0 - 120-277V RWK - 4000K Billion, * OA dad only Field Installed Accessories: <u>intern Number</u> <u>Description</u> <u>CPEBATTERY</u> 8W 90 min, waterproof emergency battery backup For the most up-to-date specs and warranty information, please visit www.tcpi.com: <u>MC</u> - 4000K <u>TCP</u> <u>355 Compute file velocities <u>255 Compus Dr. Auron, 0hio 44202 P. 800-324-1496 trpi.com <u>MC</u> - 4000K <u>310 Compute file velocities <u>NC</u> - 5000K <u>255 Compus Dr. Auron, 0hio 44202 P. 800-324-1496 trpi.com <u>MC</u> - 4000K <u>310 Compute file <u>MC</u> <u>MC</u> - 4000K <u>310 Compute file <u>MC</u> </u></u></u></u></u></u> | FAMILY | | VOLTAGE | COLOR TEMPERATURE | FACTORY INSTALLED OPTION |
| Field Installed Accessories: Item Number Description CPEBATTERY 8W 90 min. waterproof emergency battery backup For the most up-to-date specs and warranty information, please visit www.tcpi.com Image: Compus Up to-date specs and warranty information, please visit www.tcpi.com TCP* 325 Compus Dr. Aurora, Ohio 44202 P: 800-324-1496 tpi.com Image: Compus Dr. Aurora, Ohio 44202 P: 800-324-1496 tpi.com | Field Installed Accessories: Item Number Description CPEBATTERY 8W 90 min. waterproof emergency battery backup For the most up-to-date specs and warranty information, please visit www.tcpi.com Image: Colspanse Dr. Aurora, Ohio 44202 P: 800-324-1496 tpi.com 5 min. 25 Gampus Dr. Aurora, Ohio 44202 P: 800-324-1496 tpi.com Source of this product are qualified on the DIC OPI. For products, please consult file DIC Qualified Products Library www.de Source of this product are qualified on the DIC OPI. For products, please consult file DIC Qualified Products Library www.de LED WALL PACK LIGHT SPECIFICATION | Field Installed Accessories: Image: Description CPEBATTERY Description (CPEBATTERY) Description (SW) 90 min. waterproof emergency battery backup For the most up-to-date specs and warranty information, please visit www.icpi.com. Image: CPC SUSCENT CPC | Field Installed Accessories: <u>Imm Number</u> <u>Description</u> <u>CPEBATTERY</u> 8/W 90 min, waterproof emergency battery backup For the most up-to-date specs and warranty information, please visit www.tcpi.com: <u>TCP*</u> 225 Gamps Dr. Aurora, Ohio 44202 P: 800-324-1496 tpi.com ettr d3222/941876 <u>TCP*</u> <u>325 Camps Dr. Aurora, Ohio 44202 P: 800-324-1496 tpi.com <u>ettr d3222/941876 <u>CED WALL PACK LIGHT SPECIFICATION</u> </u></u> | WF - Wall Pack | 120 - 12600L (120W) | 001-120-2774 | 50K – 5000K | PC – Button Photocell MS – Microwave Bi-level Dimming |
| Trem Number Description CPEBATTERY 8WV 90 min. waterproof emergency battery backup For the most up-to-date specs and warranty information, please visit www.tcpi.com TCP° 325 Campus Dr. Aurora, Ohio 44202 P: 800-324-1496 tcpi.com ettr or 2002/w169700 | Item Number Description CPEBATTERY 8W 90 min. waterproof emergency battery backup For the most up-to-date specs and warranty information, please visit www.tcpi.com Image: Compus Dr. Aurora, Ohio 44202 P: 800-324-1496 tqi.com 225 Campus Dr. Aurora, Ohio 44202 P: 800-324-1496 tqi.com Image: Computer of this product are qualified on the DIC OPL. To v product, please consult the DIC Qualified Products List at www.dd Image: Computer of the product of the DIC Qualified Products List at www.dd Image: Computer of the product of the DIC Qualified Products List at www.dd Image: Computer of the DIC Qualified Products List at www.dd Image: Computer of the DIC Qualified Products List at www.dd Image: Computer of the DIC Qualified Products List at www.dd Image: Computer of the DIC Qualified Products List at www.dd Image: Computer of the DIC Qualified Products List at www.dd Image: Computer of the DIC Qualified Products List at www.dd Image: Computer of the DIC Qualified Products List at www.dd Image: Computer of the DIC Qualified Products List at www.dd Image: Computer of the DIC Qualified Products List at www.dd Image: Computer of the DIC Qualified Products List at www.dd Image: Computer of the DIC Qualified Products List at www.dd Image: Computer of the DIC Qualified Products List at www.dd Image: Computer of the DIC Qual | Item Number Description CPEBATTERY 8VV 90 min. waterproof emergency battery backup For the most updo-date specs and warranty information, please visit www.tcpi.com Image: Computer State | Item Number Description CPEBATTERY 8/W 90 min. waterproof emergency battery backup For the most up-to-date specs and warranty information, please visit www.tcpi.com Image: Computer Special S | | ries: | | | |
| For the most up-to-date specs and warranty information, please visit www.tcpi.com TCP® 325 Campus Dr. Aurora, Ohio 44202 P: 800-324-1496 tcpi.com ettr og 2022/W16700 Not all versions of this product are qualified on the DLC OPL To vie products, please consult the DLC Qualified Products Ust at www.de | For the most up-to-date specs and warranty information, please visit www.tcpi.com TCP* 325 Campus Dr. Aurora, Ohio 44202 P: 800-324-1496 tqpi.com ettP 00 2022/W14970 Not all versions of this product are qualified on the DEC QPL To v products, please consult the DEC Qualified Products List at www.de | For the most upto-date specs and warranty information, please visit www.tcpi.com TCP 325 Gampus Dr. Aurore, Ohio 44202 P: 800-324-1496 tpi.com etr or 2022/wite/room LED WALL PACK LIGHT SPECIFICATION | For the most up-to-date specs and warranty information, please visit www.tcpi.com 232 Sompts Dr. Aurore, Ohio 44202 P: 800-324-1496 tpi.com entra 2022/WILEPTO 3 LED WALL PACK LIGHT SPECIFICATION | Field Installed Accesso | essistion | | | |
| For the most up-to-date specs and warranty information, please visit www.tcpi.com TCP* 325 Campus Dr. Aurora, Ohio 44202 P: 800-324-1496 tcpi.com ett 0:03 2022/Will/2010 Not all versions of this product are qualified on the DLC OPL. To vie products, please consult the DLC Qualified Product. List at www.det | For the most up-to-date specs and warranty information, please visit www.tcpi.com TCP* 325 Campus Dr. Aurora, Ohio 44202 P: 800-324-1496 tcpi.com ettr og 2022/WI19700 T LED WALL PACK LIGHT SPECIFICATION | For the most up-to-date specs and worranty information, please visit www.tcpi.com 235 Gampus Dr. Aurora, Ohio 44202 P. 800-324-1496 tpi.com etr on 2022/W18970 LED WALL PACK LIGHT SPECIFICATION | For the most up to date specs and warranty information, please visit www.tcpi.com TCP 325 Campus Dr. Auroro, Ohio 44202 P: 800-324-1496 tpi.com err on 1202/Witerion LED WALL PACK LIGHT SPECIFICATION | Field Installed Accesso Item Number De CPEBATTERY 8* | escription W 90 min. waterproof emerger | ncy battery backup | | |
| 325 Campus Dr. Aurora, Ohio 44202 P: 800-324-1496 tcpi.com Chi O 2022/WI 14770 Not all versions of this product are qualified on the DLC QPL. To vie products, please consult the DLC Qualified Products List at www.dee | 325 Campus Dr. Aurora, Ohio 44202 P: 800-324-1496 tqi.com etch od 2002/Wills700 LED WALL PACK LIGHT SPECIFICATION | 325 Campus Dr. Aurora, Ohio 44202 P: 800-324-1496 tpi.com entr 012022/W11970 LED WALL PACK LIGHT SPECIFICATION | Autora, Ohio 44202 P: 800-324-1496 trpi.com entr of 2022/wi16770 LED WALL PACK LIGHT SPECIFICATION 3 | Item Number Dot CPEBATTERY 8 ¹⁰ | escription W 90 min. waterproof emerger | ncy battery backup | | |
| products, please consult the DLC Qualified Products List at www.de | LED WALL PACK LIGHT SPECIFICATION | 3 LED WALL PACK LIGHT SPECIFICATION | 3 LED WALL PACK LIGHT SPECIFICATION | Field Installed Accesso Item Number Do CPEBATTERY 81 | escription W 90 min. waterproof emerger pecs and warranty information, pla | ncy battery backup ease visit www.tcpi.com | |) |
| | Z LED WALL PACK LIGHT SPECIFICATION | 3 LED WALL PACK LIGHT SPECIFICATION | 3 LED WALL PACK LIGHT SPECIFICATION | Field Installed Accesso Item Number Dr CPEBATTERY 81 For the most up-to-date sy TCP* 325 Campus Dr. Aurora, Ohio 4 extr od 2022/W169700 | escription W 90 min. waterproof emerger pecs and warranty information, pla 4202 P: 800-324-1496 typi.com | ncy battery backup ease visit www.tcpi.com | c (U | US LISTED TO STATE |
| | | | | Field Installed Accesso Item Number Do CPEBATTERY 81 For the most up-to-date sy TCP® 325 Campus Dr. Aurora, Ohio 4 entr oct 2022/W169700 | escription W 90 min. waterproof emerger becs and warranty information, pl 4202 P: 800-324-1496 tcpi.com | ncy battery backup ease visit www.tcpi.com | | US LISTED TO STORE 5 THE STORE |
| 3 LLD WALL FACK LIGHT SFLUITCATION | | | | Field Installed Accesso Item Number Da CPEBATTERY 81 For the most up-to-clate sy TCP* 325 Campus Dr. Aurora, Ohio 4 ettr od 2022/W16970 | escription W 90 min. waterproof emerger pecs and warranty information, pl 4202 P: 800-324-1496 tcpi.com | ncy battery backup ease visit www.tcpi.com | Constant Con | US LISTED IN STREED STR |
| 3 LLD WALL FACK LIGHT SFLUITCATION | | | | Field Installed Accesso Item Number Da CPEBATTERY 81 For the most up-to-date sy TCP* 325 Campus Dr. Aurora, Ohio 4 entr oct 2022/W169709 | escription W 90 min. waterproof emerger pecs and warranty information, pla 4202 P: 800-324-1496 tcpi.com | ncy battery backup ease visit www.tcpi.com | Not of Very Products, | US LISTED TO 5 THE rations of this product are qualified on the DLC OPL To view please consult the DLC Qualified Products List at www.desi CIFICATION |
| 3 LLD WALL FACK LIGHT SFLUITICATION | | | | Field Installed Accesso Item Number Da CPEBATTERY 8' For the most up-to-date sp TCP ^e 325 Campus Dr. Aurora, Ohio 4 entr oct 2022/W169700 | escription W 90 min, waterproof emerger pecs and warranty information, pla 4202 P: 800-324-1496 tcpi.com | ease visit www.tcpi.com | Constant BIGHT SPEC | US LISTED IN SUCCESSION STATES |
| 3 LLD WALL PACK LIGHT SPLCIFICATION | | | | Field Installed Accesso Item Number Da CPEBATTERY 81 For the most up-to-date sy TCP* 325 Campus Dr. Aurora, Ohio 4 entr oct 2022/W169200 | escription W 90 min. waterproof emerger pecs and warranty information, pl 4202 P: 800-324-1496 tcpi.com | ease visit www.tcpi.com | Constant Con | bus LISTED |
| 3 LLD WALL FACK LIGHT SFLOINCATION | | | | Field Installed Accesso Item Number Da CPEBATTERY 8 ¹ For the most up-to-date sy TCP ^e 325 Campus Dr. Aurora, Ohio 4 entr od 2022/W169709 | escription W 90 min, waterproof emerger pecs and warranty information, pla 4202 P: 800-324-1496 tqpi.com | ease visit www.tcpi.com | Contraction of the second seco | () US LISTED USE 5 ± 100 |
| 3 LLD WALL FACK LIGHT SPLCIFICATION | | | | Field Installed Accesso Tem Number Da CPEBATTERY 81 For the most up-to-date sy TCP* 325 Campus Dr. Aurora, Ohio 4 entr od 2022/W169700 | escription W 90 min. waterproof emerger pecs and warranty information, pla 4202 P: 800-324-1496 tcpi.com | ease visit www.tcpi.com | Contractions of the end of the en | Jus uster \tilde{b} 5 $\frac{1}{2}$ risens of this preduct are qualified on the DCC OPL. To the phene consult the DCC Qualified Products List at www.det |
| 3 LLD WALL FACK LIGHT SFLOIDCATION | | | | Field Installed Accesso Tem Number Da CPEBATTERY 81 For the most up-to-date sp TCP ^a 325 Compus Dr. Aurora, Ohio 4 entr or 2022/W169700 | escription W 90 min, waterproof emerger peets and warranty information, pla 4202 P: 800-324-1496 topi.com | ease visit www.tcpi.com | Contraction of the second seco | US LISTED USE SUBJECT |
| 3 LLD WALL PACK LIGHT SPLOINCATION | | | | Field Installed Accesso Item Number Da CPEBATTERY 81 For the most up-to-date sy TCP* 325 Campus Dr. Aurora, Ohio 4 entr od 2022/W16970 | escription W 90 min. waterproof emerger pecs and warranty information, pla 4202 P: 800-324-1496 tcpi.com | ease visit www.tcpi.com | Contractions | US LISTED |
| 3 LLD WALL PACK LIGHT SPLCIFICATION | | | | Field Installed Accesso Tem Number Da CPEBATTERY 81 For the most up-to-date sy TCP* 325 Compus Dr. Aurora, Ohio 4 entr or 2022/W16970 | escription W 90 min, waterproof emerger peecs and warranty information, pla 4202 P: 800-324-1496 tcpi.com | ease visit www.tcpi.com | Contraction of the second seco | In the product are qualified Products List of www.deta DIFFICATION |
| 3 LLD WALL FACK LIGHT SPLCIFICATION | | | | Field Installed Accesso Tem Number Da CPEBATTERY 81 For the most up-to-date sy TCP* 325 Campus Dr. Aurora, Ohio 4 entr ord 2022/W16970 | escription W 90 min. waterproof emerger pecs and warranty information, pla 4202 P: 800-324-1496 topi.com | ease visit www.tcpi.com | Contractors | () US LISTED |
| 3 LLD WALL FACK LIGHT SFLOIDCATION | | | | Field Installed Accesso Tem Number Dr CPEBATTERY 8 For the most up-to-date sy TCP* 325 Compus Dr. Aurora, Ohio 4 entr ord 2022/W16970 | escription W 90 min, waterproof emerger peecs and warranty information, pla 4202 P: 800-324-1496 tcpi.com | ease visit www.tcpi.com | Contractor Contractor Contractor | US LISTED |

E-10