

COUNTY OF SANTA CLARA

General Construction Specifications

GENERAL CONDITIONS

- 1. ALL CONSTRUCTION WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE SOILS AND/OR GEOTECHNICAL REPORT PREPARED BY REDWOOD GEOTECHNICAL ENGINEERING, INC. PO BOX 53058, SAN JOSE, CA 95153, TEL 408-227-5168...

GRADING

- 1. EXCAVATED MATERIAL SHALL BE PLACED IN THE FILL AREAS DESIGNATED OR SHALL BE HAULED AWAY FROM THE SITE TO A COUNTY APPROVED DISPOSAL SITE...

Table with columns: EARTHWORK QUANTITIES, MAXIMUM DEPTHS. Rows include Building Footprints & 5' Within, Site Work, Totals Raw, 10% Shrinkage Factor, Total Adjusted, Net Import = Fill - Cut.

- NOTE: FILL VOLUMES INCLUDE 20% SHRINKAGE. EXCESS MATERIAL SHALL BE OFF HAULED TO A COUNTY APPROVED DUMP SITE.

CONSTRUCTION STAKING

- 1. THE DEVELOPER'S ENGINEER IS RESPONSIBLE FOR THE INITIAL PLACEMENT AND REPLACEMENT OF CONSTRUCTION GRADE STAKES. THE STAKES ARE TO BE ADEQUATELY IDENTIFIED, LOCATED, STABILIZED, ETC. FOR THE CONVENIENCE OF CONTRACTORS...

CONSTRUCTION INSPECTION

- 1. CONTRACTOR SHALL NOTIFY PERMIT INSPECTION UNIT, SANTA CLARA COUNTY PRIOR TO COMMENCING WORK AND FOR FINAL INSPECTION OF WORK AND SITE.

SITE PREPARATION (CLEARING AND GRUBBING)

- 1. EXISTING TREES AUTHORIZED FOR REMOVAL, ROOTS, AND FOREIGN MATERIAL IN AREAS TO BE IMPROVED WILL BE REMOVED TO AN AUTHORIZED DISPOSAL SITE AS FOLLOWS:

UTILITY LOCATION, TRENCHING & BACKFILL


- 1. CONTRACTOR SHALL NOTIFY USA (UNDERGROUND SERVICE ALERT) AT 1-800-277-2600 A MINIMUM OF 24 HOURS BEFORE BEGINNING UNDERGROUND WORK FOR VERIFICATION OF THE LOCATION OF UNDERGROUND UTILITIES.

RETAINING WALLS

- 1. REINFORCED CONCRETE AND CONCRETE MASONRY UNIT RETAINING WALLS SHALL HAVE FOUNDATION AND REINFORCEMENT INSPECTED BY THE COUNTY ENGINEERING INSPECTOR AND ENGINEER OF RECORD PRIOR TO POURING THE FOUNDATION AND FORMING THE WALL.

AIR QUALITY, LANDSCAPING AND EROSION CONTROL

- 1. WATER ALL ACTIVE CONSTRUCTION AREAS AT LEAST TWICE DAILY. 2. COVER ALL TRUCKS HAULING SOIL, SAND, AND OTHER LOOSE MATERIALS OR REQUIRE ALL TRUCKS TO MAINTAIN AT LEAST TWO FEET OF FREEBOARD.



COUNTY LOCATION MAP



SURVEY MONUMENT PRESERVATION

- 1. THE LANDOWNER / CONTRACTOR MUST PROTECT AND ENSURE THE PERPETUATION OF SURVEY MONUMENTS AFFECTED BY CONSTRUCTION ACTIVITIES.

BASIS OF BEARINGS

THE BEARING NORTH 66°11'00" EAST OF THE LOT 167 AS SHOWN ON THAT PARCEL MAP FILED FOR RECORD IN BOOK 587 OF MAPS PAGES 13, SANTA CLARA COUNTY RECORDS, AND AS FOUND MONUMENTED, WAS TAKEN AS THE BASIS OF BEARING FOR THIS SURVEY.


BENCH MARK

DESCRIPTION: ASSUMED BENCHMARK, 1/2 REBAR IN THE LOT, NEAR THE SOUTHERLY EASTERLY CORNER OF LOT AS SHOWN: ELEV.: 100.00'

ABBREVIATIONS

- AC = ASPHALT CONCRETE AD = AREA DRAIN BC = BEGIN CURVE BS = BOTTOM OF STAIR BU = BUBBLE UP BVC = BEGIN VERTICAL CURVE BRW = BOTTOM OF RETAINING WALL CB = CURB BEGIN CL = CENTERLINE CO = CLEANOUT DS = DOWNSPOUT WITH SPLASH BOX EC = END CURVE ELEV. = ELEVATION EVO = END VERTICAL CURVE EX = EXISTING F/C = FACE OF CURB FF = FINISHED FLOOR ELEVATION FH = FIRE HYDRANT FL = FLOW LINE GB = GRADE BREAK GFF = GARAGE FINISH FLOOR HP = HIGH POINT HC = HANDICAP UNIT HW = INVERT LP = LOW POINT PAD = PAD ELEVATION PCC = PORTLAND CEMENT CONCRETE PL = PROPERTY LINE PV = PAVEMENT GRADE PVC = POLYVINYL CHLORIDE PIPE PVI = POINT OF VERTICAL INTERSECTION RCB = REINFORCED CONCRETE PIPE ROW = RIGHT OF WAY S=004> SLOPE SD = STORM DRAIN SDMH = STORM DRAIN MANHOLE SG = SUBGRADE ELEVATION SS = SANITARY SEWER SSMH = SANITARY SEWER MANHOLE STA = STATION TC = TOP OF CURB TF = TOP OF FENCE TRW = TOP OF RETAINING WALL TS = TOP OF STAIR TW = TOP OF WALL VCP = VITRIFIED CLAY PIPE WM = WATER METER WV = WATER VALVE

VICINITY MAP



EXISTING TREE PROTECTION DETAILS

- 1. PRIOR TO THE COMMENCEMENT OF ANY GRADING, TREE PROTECTIVE FENCING SHALL BE IN PLACE IN ACCORDANCE WITH THE TREE PRESERVATION PLAN AND INSPECTED BY A CERTIFIED ARBORIST.

FOOTHILL AVENUE PUBLIC IMPROVEMENTS AND GRADING & DRAINAGE PLAN LANDS OF CHEN

SCOPE OF WORK

- 1. THE DEVELOPER IS RESPONSIBLE FOR THE INSTALLATION OF THE WORK PROPOSED ON THE EROSION CONTROL PLAN. THE ENGINEER OF RECORD IS RESPONSIBLE FOR THE DESIGN OF THE EROSION CONTROL PLANS AND ANY MODIFICATIONS OF THE EROSION CONTROL PLANS TO PREVENT ILLICIT DISCHARGES FROM THE SITE DURING CONSTRUCTION.

LEGEND

Legend table with columns: DESCRIPTION, SYMBOL. Lists various symbols for Boundary Line, Lot Line, Easement Line, Side Walk, Wood Fence, Chain Link Fence, Retaining Wall, Driveway Drain Inlet, Area Drain, Drop Inlet, Monument, Fire Hydrant, Electrode, Water Meter, AC Unit, Sanitary Sewer Lateral, Storm Drain, Sanitary Sewer, Street Light Conduits, Water, Joint Trench, House Service, Slope Arrow, Existing Contour, Proposed Contour, Overland Release, Direction of Surface Drainage, SE Slope Arrow from Building.

SHEET INDEX

Sheet Index table with columns: Sheet No., Title. Lists sheets C0 to C7.2 including Title Sheet, Boundary and Topographic Map, Site Plan, Grading and Drainage Plan, Stormwater Control Plan, Construction Details & Sections, County Standard Details, Erosion Control Plan, Construction Sections & Details.

COUNTY OF SANTA CLARA DEPT. OF ROADS AND AIRPORTS ISSUED BY: DATE: ENCROACHMENT PERMIT NO.

COUNTY OF SANTA CLARA LAND DEVELOPMENT ENGINEERING & SURVEYING GRADING / DRAINAGE PERMIT NO. ISSUED BY: DATE:

NO WORK SHALL BE DONE IN THE COUNTY'S RIGHT-OF-WAY WITHOUT AN ENCROACHMENT PERMIT, INCLUDING THE STAGING OF CONSTRUCTION MATERIAL AND THE PLACEMENT OF PORTABLE TOILETS.

ENGINEER'S STATEMENT

I HEREBY STATE THAT THESE PLANS ARE IN COMPLIANCE WITH ADOPTED COUNTY STANDARDS, THE APPROVED TENTATIVE MAP (OR PLAN) AND CONDITIONS OF APPROVAL PERTAINING THERETO DATED FILE(S) NO.

Date 11/8/24, Signature P. Oscar Osuna, No. 70829, R.C.E. No. 6-30-25, Expiration Date.



COUNTY ENGINEER'S NOTE

ISSUANCE OF A PERMIT AUTHORIZING CONSTRUCTION DOES NOT RELEASE THE DEVELOPER, PERMITEE OF ENGINEER FROM RESPONSIBILITY FOR THE CORRECTION OF ERRORS OR OMISSIONS CONTAINED IN THE PLANS. IF, DURING THE COURSE OF CONSTRUCTION, THE PUBLIC INTEREST REQUIRES A MODIFICATION OF (OR DEPARTURE FROM) THE SPECIFICATIONS OF THE PLANS, THE COUNTY SHALL HAVE THE AUTHORITY TO REQUIRE THE SUSPENSION OF WORK, AND THE NECESSARY MODIFICATION OR DEPARTURE AND TO SPECIFY THE MANNER IN WHICH THE SAME IS TO BE MADE.

Date, Signature Darrell K.H. Wong, No. 63958, Expiration Date 9/30/2024.

AS-BUILT PLANS STATEMENT

THIS IS A TRUE COPY OF THE AS-BUILT PLANS, THERE () WERE () WERE NOT) MINOR FIELD CHANGES - MARKED WITH THE SYMBOL (). THERE () WERE () WERE NOT) PLAN REVISIONS INDICATING SIGNIFICANT CHANGES REVIEWED BY THE COUNTY ENGINEER AND MARKED WITH THE SYMBOL ().

DATE SIGNATURE

NOTE: THIS STATEMENT IS TO BE SIGNED BY THE PERSON AUTHORIZED BY THE COUNTY ENGINEER TO PERFORM THE INSPECTION WORK. A REPRODUCIBLE COPY OF THE AS-BUILT PLANS MUST BE FURNISHED TO THE COUNTY ENGINEER AFTER CONSTRUCTION.

GEOTECHNICAL ENGINEER OBSERVATION

- 1. A CONSTRUCTION OBSERVATION LETTER FROM THE RESPONSIBLE GEOTECHNICAL AND ENGINEERING GEOLOGIST DETAILING CONSTRUCTION OBSERVATIONS AND CERTIFYING THAT THE WORK WAS DONE IN ACCORDANCE WITH THE RECOMMENDATIONS IN THE GEOTECHNICAL AND GEOLOGIC REPORTS SHALL BE SUBMITTED PRIOR TO THE GRADING COMPLETION AND RELEASE OF THE BOND.

Date, Signature Darrell K.H. Wong, No. 63958, Expiration Date 9/30/2024.

ACCESS ROADS AND DRIVEWAYS

- 1. DRIVEWAY LOCATIONS SHALL BE AS SHOWN ON THE IMPROVEMENT PLANS WITH CENTERLINE STATIONING. THE MINIMUM CONCRETE THICKNESS SHALL BE 6 INCHES THROUGHOUT (WITH A MAXIMUM APPROACH SLOPE OF 1 1/4 INCHES PER FOOT).

STREET LIGHTING

- 1. PACIFIC GAS & ELECTRIC ELECTROLETRIER SERVICE FEE SHALL BE PAID BY THE DEVELOPER AND/OR HIS AUTHORIZED REPRESENTATIVE.

SANITARY SEWER

- 1. THE SANITARY SEWER AND WATER UTILITIES SHOWN ON THESE PLANS ARE NOT PART OF THIS GRADING PERMIT AND ARE SHOWN FOR REFERENCE ONLY.

PORTLAND CEMENT CONCRETE

- 1. CONCRETE USED FOR STRUCTURAL PURPOSES SHALL BE CLASS "A" (6 SACK PER CUBIC YARD) AS SPECIFIED IN THE STATE STANDARD SPECIFICATIONS. CONCRETE PLACED MUST DEVELOP A MINIMUM STRENGTH FACTOR OF 2800 PSI IN A SEVEN-DAY PERIOD. THE CONCRETE MIX DESIGN SHALL BE UNDER THE CONTINUAL CONTROL OF THE COUNTY INSPECTOR.

APPLICANT: CHEN



ROAD: FOOTHILL AVE

FILE NO.: LDE17-10900 G

FOOTHILL AVENUE

LEGEND

- 200--- EXISTING CONTOUR LINE
- 200--- NATURAL GRADE CONTOUR LINE
- ⊙ FOUND CITY MONUMENT BOX, OR AS NOTED
- BOUNDARY OF PROPERTY SURVEYED
- () RECORD INFORMATION
- CENTERLINE
- △ CURB INLET
- CURB LINE
- DRIVEWAY APRON
- ELECTROLUER
- x-x-x- FENCE
- ⊕ FIRE HYDRANT
- FLAT GRATE INLET
- O.H. PWR OVERHEAD POWER LINE
- O.H. TEL OVERHEAD TELEPHONE LINE
- SS SANITARY SEWER LINE
- SANITARY SEWER MANHOLE
- ⊙ SANITARY SEWER CLEANOUT
- SIGN
- SD STORM DRAIN LINE
- ⊙ STORM DRAIN MANHOLE
- UTILITY BOX
- UTILITY POLE
- W WATER LINE
- ⊕ WATER METER
- ⊕ WATER VALVE
- ⊕ ELECTRIC METER
- ⊕ WATER HEATER
- ⊕ GAS
- ⊕ WELL



BASIS OF BEARINGS
 THE BEARING NORTH 66°11'00" EAST OF THE LOT 167 AS SHOWN ON THAT PARCEL MAP FILED FOR RECORD IN BOOK 587 OF MAPS PAGES 13, SANTA CLARA COUNTY RECORDS, AND AS FOUND MONUMENTED, WAS TAKEN AS THE BASIS OF BEARING FOR THIS SURVEY.

REFERENCES:
 R1 DEED # 22828129 115-M-46&47
 R2 RECORD OF SURVEY 215-M-15
 R3 PARCEL MAP 587-M-13

BENCH MARK
 DESCRIPTION: ASSUMED BENCHMARK, 1/2 REBAR IN THE LOT, NEAR THE SOUTHERLY EASTERLY CORNER OF LOT AS SHOWN: ELEV.: 100.00'

ABBREVIATIONS

APN	ASSESSOR'S PARCEL NUMBER
BM	BENCH MARK
CATV	CABLE TELEVISION OVERHEAD
D	CURVE DELTA
DRWY	DRIVEWAY
DS	DOWNSPOUT
FL	FLOW LINE ELEVATION
IP	IRON PIPE
L	CURVE LENGTH
R#	REFERENCE DOCUMENT
M-M	MONUMENT TO MONUMENT
O.H. PWR	OVERHEAD POWER LINE
O.H. TEL	OVERHEAD TELEPHONE LINE
PCL	PARCEL
P.M.	PARCEL MAP
PTN	PORTION
R	RADIUS
SD	STORM DRAIN
SS	SANITARY SEWER
TC	TOP OF CURB ELEVATION
TEMP.	TEMPORARY
PUE	PUBLIC UTILITY EASEMENT
WLE	WATER LINE EASEMENT

- NOTES:**
- DISTANCES AND DIMENSIONS ARE SHOWN IN FEET AND DECIMALS THEREOF.
 - THE DISTINCTIVE BORDER LINE DENOTES THE BOUNDARY.
 - TREES SPECIES NAMES ARE APPROXIMATE, AND LABELED BY THEIR COMMON NAME TO THE BEST OF OUR KNOWLEDGE. IT IS NOT BASED ON AN ARBORIST REPORT.
 - THIS MAP REPRESENTS TOPOGRAPHY OF THE SURFACE FEATURES ONLY.
 - UNLESS SPECIFIED ON THIS MAP, LOCATIONS OF THE UNDERGROUND AND OVERHEAD UTILITIES ARE NEITHER INTENDED NOR IMPLIED. FOR THE LOCATIONS OF UNDERGROUND UTILITIES CALL "USA" (1-800-642-2440).
 - A TITLE REPORT FOR THE SUBJECT PROPERTY HAS NOT BEEN EXAMINED BY GREENBLUEARTH, INC. OTHER EASEMENTS OF RECORD MAY EXIST THAT ARE NOT SHOWN ON THIS MAP.

RECORD OF SURVEY NOTE:
 THIS PRELIMINARY SITE SURVEY BOUNDARY IS INTENDED FOR INITIAL STUDIES OR PLANNING DESIGN. TO FINALIZE THIS BOUNDARY SURVEY A RECORD OF SURVEY MUST BE FILED PER THE MANDATORY FILING PROVISIONS OF SECTION 8762(B) OF THE PROFESSIONAL LAND SURVEYORS' ACT. THE RECORD OF SURVEY IS BEING FILED CONCURRENTLY WITH THESE PLANS

APPROVED FOR ISSUANCE
 REFER TO ENCROACHMENT AND/OR
 CONSTRUCTION PERMIT AND PLAN
 COVER SHEET FOR SPECIAL
 CONDITIONS AND PERMIT NUMBERING



DATE	7-02-18	REVISIONS	AS SHOWN
SCALE	1" = 40'	DRAWN BY	O.OSUNA
CHECKED BY			O.O.
SUPERVISED BY PROFESSIONAL LAND SURVEYOR NO. 8921 EXPIRES 9/30/26 STATE OF CALIFORNIA			
PRELIMINARY BOUNDARY AND TOPOGRAPHIC MAP LANDS OF CHEN 11655 FOOTHILL AVE - APN 830-29-003 GILROY, CALIFORNIA			
JOB NO.	1393		
SHEET	BT1		
OF	13		

ABBREVIATIONS

- AC = ASPHALT CONCRETE
- AD = AREA DRAIN
- BC = BEGIN CURVE
- BS = BOTTOM OF STAIR
- BU = BUBBLE UP
- BVC = BEGIN VERTICAL CURVE
- BRW = BOTTOM OF RETAINING WALL
- CB = CATCH BASIN
- CL = CENTERLINE
- CO = CLEANOUT
- DS = DOWNSPOUT WITH SPLASH BOX
- EC = END CURVE
- ELEV. = ELEVATION
- EVC = END VERTICAL CURVE
- EX. = EXISTING
- F/C = FACE OF CURB
- FF = FINISHED FLOOR ELEVATION
- FH = FIRE HYDRANT
- FL = FLOW LINE
- GB = GRADE BREAK
- GFF = GARAGE FINISH FLOOR
- HP = HIGH POINT
- HC = HANDICAP UNIT
- INV = INVERT
- LP = LOW POINT
- PAD = PAD ELEVATION
- PCC = PORTLAND CEMENT CONCRETE
- PL = PROPERTY LINE
- PV = PAVEMENT GRADE
- PVC = POLYVINYL CHLORIDE PIPE
- PVI = POINT OF VERTICAL INTERSECTION
- RCP = REINFORCED CONCRETE PIPE
- ROW = RIGHT OF WAY
- S=004> SLOPE
- SD = STORM DRAIN
- SDMH = STORM DRAIN MANHOLE
- SG = SUBGRADE ELEVATION
- SS = SANITARY SEWER
- SSMH = SANITARY SEWER MANHOLE
- STA = STATION
- TC = TOP OF CURB
- TF = TOP OF FENCE
- TRW = TOP OF RETAINING WALL
- TS = TOP OF STAIR
- TW = TOP OF WALL
- VCP = VITRIFIED CLAY PIPE
- WM = WATER METER
- WV = WATER VALVE



BENCH MARK
 DESCRIPTION: ASSUMED BENCHMARK, 1/2 REBAR IN THE LOT, NEAR THE SOUTHERLY EASTERLY CORNER OF LOT AS SHOWN: ELEV.: 100.00'

a. Total Site Area: 304,920 (ft ²)		b. Total Land Area Disturbed During Construction: 42,576 (ft ²) (including clearing, grading, stockpiling, or excavating)			
Project Totals	Total Existing (Pre-project) Area (ft ²)	Existing Area Retained ¹ (ft ²)	Existing Area Replaced ² (ft ²)	New Area Created ³ (ft ²)	Total Post-Project Area (ft ²)
Impervious Area (IA)					
c. Total on-site IA	0	0	0	32,006	32,006
d. Total off-site IA ³	0	0	0	0	0
e. Total project IA	0	0	0	32,006	32,006
f. Total new and replaced IA				32,006	
Pervious Area (PA)⁴					
g. Total on-site PA	42,576				10,570
h. Total off-site PA ³	0				0
i. Total project PA	42,576				10,570
j. Total Project Area (2.e.+2.i.)	42,576				42,576

CONTRACTOR AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING THE SAFETY OF ALL PERSONS AND PROPERTY THAT THIS REQUIREMENT SHALL BE LIMITED TO NORMAL WORKING HOURS; AND THAT THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM ALL AGENCIES AND AGENCIES INVOLVED IN THE PROJECT, INCLUDING THE CITY OF GILROY, AND THAT THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM ALL AGENCIES AND AGENCIES INVOLVED IN THE PROJECT, INCLUDING THE CITY OF GILROY.

LEGEND

- | DESCRIPTION | SYMBOL |
|-------------------------------|-----------|
| BOUNDARY LINE | --- |
| LOT LINE | --- |
| EASEMENT LINE | --- |
| SIDEWALK | --- |
| WOOD FENCE | x-x |
| CHAIN LINK FENCE | o-o |
| RETAINING WALL | |
| DRIVEWAY DRAIN INLET | ⊕ |
| AREA DRAIN | ⊕ |
| DROP INLET | ⊕ |
| MONUMENT | ⊙ |
| FIRE HYDRANT | ⊕ |
| ELECTROLYSER | ⊕ |
| WATER METER | ⊕ |
| AC UNIT | ⊕ |
| SANITARY SEWER LATERAL | — |
| STORM DRAIN | — |
| SANITARY SEWER | — |
| STREET LIGHT CONDUITS | — |
| WATER | — |
| JOINT TRENCH | — |
| HOUSE SERVICE | — |
| SLOPE ARROW | → |
| EXISTING CONTOUR | ---100--- |
| PROPOSED CONTOUR | ---100--- |
| OVERLAND RELEASE | → |
| DIRECTION OF SURFACE DRAINAGE | → |
| SEE SLOPE AWAY FROM BUILDING | >> |



APPROVED FOR ISSUANCE
 REFER TO ENCROACHMENT AND/OR
 CONSTRUCTION PERMIT AND PLAN
 COVER SHEET FOR SPECIAL
 CONDITIONS AND PERMIT NUMBERING

	REVISIONS
	DATE
	BY
	CITY
	DATE

OSUNA ENGINEERING INC.
 Planning | Surveying | Civil Engineering
 CONSULTING CIVIL ENGINEERS & LAND SURVEYORS
 1949 O' TOOLE WAY
 SAN JOSE, CA 95131
 TEL: (408) 721-2100
 info@osunaengineering.com

PUBLIC IMPROVEMENTS AND GRADING & DRAINAGE PLAN

SITE PLAN



11655 FOOHILL AVE

CITY OF GILROY, CALIFORNIA
 Project No.: 1383 | Design: J0/00 | Check: O.O. | Date: 11/6/24

SHEET **C1**


OF 13 SHEETS

CONTRACTOR AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING BUT NOT LIMITED TO THE SAFETY OF ALL PERSONS AND PROPERTY. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND SHALL BE RESPONSIBLE FOR THE SAFETY OF ALL PERSONS AND PROPERTY. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE SAFETY OF ALL PERSONS AND PROPERTY. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE SAFETY OF ALL PERSONS AND PROPERTY.



TREE #	TREE SIZE AND OBSERVED TYPE*	COMMENTS
1	12" TREE (PER OWNER, TREE FELL BY STORM)	REMOVED
2	10" OAK TREE	TO REMAIN
3	13" OAK TREE	TO REMAIN
4	20" OAK TREE	TO REMAIN
5	9" OAK TREE	TO REMAIN
6	4" OAK TREE	TO REMAIN
7	7" OAK TREE	TO REMAIN
8	9, 6" TREE	TO REMAIN
9	12, 12" OAK TREE	TO REMAIN
10	10" OAK TREE	TO REMAIN
11	7" OAK TREE	TO REMAIN
12	10" OAK TREE	TO REMAIN

* TREES SIZE AND TYPE ARE APPROXIMATE BY FIELD SURVEYOR OBSERVATION. IF REQUIRED FURTHER DETAIL REFER TO ARBORIST



GENERAL RIGHT OF WAY (ROW) NOTES:


- ALL SAWCUT SPOILS SHALL BE VACUUMED
- SAWCUT AND REPAVE A MINIMUM 1 FOOT OF FOOTHILL AVE/PROPERTY FRONTAGE IMPROVEMENTS LIMITS. MATCH PAVEMENT SECTION IN KIND AND TO COUNTY STANDARD
- RESTRIPE FOG LINE IN SAWCUT AREA IN KIND WITH 4-INCH WHITE REFLECTIVE PAVEMENT MARKINGS AND AS REQUESTED BY COUNTY INSPECTOR AND/OR ENGINEER
- OFF HAUL ALL CONSTRUCTION SPOILS AND DEBRIS TO AN APPROPRIATE DUMP FACILITY
- INSTALL AND MAINTAIN PROPER BMPs THROUGHOUT THE DURATION OF CONSTRUCTION
- INSTALL AND MAINTAIN TRAFFIC CONTROL IN ACCORDANCE WITH THE MUTCD

APPROVED FOR ISSUANCE
REFER TO ENCROACHMENT AND/OR
CONSTRUCTION PERMIT AND PLAN
COVER SHEET FOR SPECIAL
CONDITIONS AND PERMIT NUMBERING



	<p>OSUNA ENGINEERING INC. Planning Surveying Civil Engineering</p> <p>CONSULTING CIVIL ENGINEERS & LAND SURVEYORS TEL: (408) 721-2100 info@osunaengineering.com</p> <p>1949 O' TOOLE WAY SAN JOSE, CA 95131</p>																				
<p>PUBLIC IMPROVEMENTS AND GRADING & DRAINAGE PLAN</p> <p>11655 FOOTHILL AVE CITY OF GALEROY, CALIFORNIA Project No.: 1383 Design: J0/00 Check: 0.0 Date: 11/8/24</p>	<p>REVISIONS</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>NO.</th> <th>DATE</th> <th>BY</th> <th>CITY</th> </tr> </thead> <tbody> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> </tbody> </table>	NO.	DATE	BY	CITY																
NO.	DATE	BY	CITY																		
<p>SHEET C2.1 OF 13 SHEETS</p>																					

TREE #	TREE SIZE AND OBSERVED TYPE*	COMMENTS
1	12" TREE (PER OWNER, TREE FELL BY STORM)	REMOVED
2	10" OAK TREE	TO REMAIN
3	13" OAK TREE	TO REMAIN
4	20" OAK TREE	TO REMAIN
5	9" OAK TREE	TO REMAIN
6	4" OAK TREE	TO REMAIN
7	7" OAK TREE	TO REMAIN
8	9, 6" TREE	TO REMAIN
9	12, 12" OAK TREE	TO REMAIN
10	10" OAK TREE	TO REMAIN
11	7" OAK TREE	TO REMAIN
12	10" OAK TREE	TO REMAIN

* TREES SIZE AND TYPE ARE APPROXIMATE BY FIELD SURVEYOR OBSERVATION.
IF REQUIRED FURTHER DETAIL REFER TO ARBORIST



CONTRACTOR AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING BUT NOT LIMITED TO NORMAL WORKING HOURS; AND THAT THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL UTILITIES AND ADJACENT PROPERTY. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL UTILITIES AND ADJACENT PROPERTY. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL UTILITIES AND ADJACENT PROPERTY.



APPROVED FOR ISSUANCE
REFER TO ENCROACHMENT AND/OR
CONSTRUCTION PERMIT AND PLAN
COVER SHEET FOR SPECIAL
CONDITIONS AND PERMIT NUMBERING

REVISIONS	DATE	BY	CITY

OSUNA ENGINEERING INC.
Planning | Surveying | Civil Engineering
CONSULTING CIVIL ENGINEERS & LAND SURVEYORS
1949 O' TOOLE WAY
SAN JOSE, CA 95131
TEL: (408) 721-2100
info@osunaengineering.com

PUBLIC IMPROVEMENTS AND GRADING & DRAINAGE PLAN



11655 FOOTHILL AVE
CITY OF GILROY, CALIFORNIA
Project No.: 1383 | Design: J0/00 | Check: 0.0 | Date: 11/8/24

SHEET C2.2
OF 13 SHEETS

STORMWATER CONTROL PLAN

11655 FOOTHILL AVE 11655 FOOTHILL AVE, GILROY, CA 95020 APN NO.: 830-29-003

NEW RESIDENTIAL HOUSE WITH ATTACHED GARAGE & DRIVEWAY



AC = ASPHALT CONCRETE	LP = LOW POINT
AD = AREA DRAIN	PAD = PAD ELEVATION
BC = BEGIN CURVE	PCC = PORTLAND CEMENT CONCRETE
BS = BOTTOM OF STAIR	PL = PROPERTY LINE
BU = BUBBLE UP	PV = PAVEMENT GRADE
BVC = BEGIN VERTICAL CURVE	PVC = POLYVINYL CHLORIDE PIPE
BRW = BOTTOM OF RETAINING WALL	PVI = POINT OF VERTICAL INTERSECTION
CB = CATCH BASIN	RCR = REINFORCED CONCRETE PIPE
CL = CENTERLINE	ROW = RIGHT OF WAY
CO = CLEANOUT	S=.004> SLOPE
DS = DOWNSPOUT WITH SPLASH BOX	SD = STORM DRAIN
EC = END CURVE	SDMH = STORM DRAIN MANHOLE
ELEV. = ELEVATION	SG = SUBGRADE ELEVATION
EVC = END VERTICAL CURVE	SS = SANITARY SEWER
EX. = EXISTING	SSMH = SANITARY SEWER MANHOLE
F/C = FACE OF CURB	STA = STATION
FF = FINISHED FLOOR ELEVATION	TC = TOP OF CURB
FI = FIRE HYDRANT	TF = TOP OF FENCE
FL = FLOW LINE	TRW = TOP OF RETAINING WALL
GB = GRADE BREAK	TS = TOP OF STAIR
GFF = GARAGE FINISH FLOOR	TW = TOP OF WALL
HP = HIGH POINT	VCP = VITRIFIED CLAY PIPE
HC = HANDICAP UNIT	WM = WATER METER
INV = INVERT	WV = WATER VALVE

LEGEND

DESCRIPTION	SYMBOL
BOUNDARY LINE	---
LOT LINE	---
EASEMENT LINE	---
SIDEWALK	---
WOOD FENCE	X X
CHAIN LINK FENCE	---
RETAINING WALL	---
DRIVEWAY DRAIN INLET	---
AREA DRAIN	---
DROP INLET	---
MONUMENT	---
FIRE HYDRANT	---
ELECTROVALVE	---
WATER METER	---
AC UNIT	---
SANITARY SEWER LATERAL	---
STORM DRAIN	SD
SANITARY SEWER	SS
STREET LIGHT CONDUITS	SL
WATER	W
JOINT TRENCH	JT
HOUSE SERVICE	SVC
SLOPE ARROW	---
EXISTING CONTOUR	100
PROPOSED CONTOUR	100
OVERLAND RELEASE	---
DIRECTION OF SURFACE DRAINAGE	---
SEE SLOPE AWAY FROM BUILDING	>>

Operation and Maintenance Information

- a) Property Owner's Name: Mingwei Chen
- b) Responsible Party for Stormwater Treatment/Hydromodification Control O&M:
- Name: Mingwei Chen
 - Address: 11655 Foothill Ave
 - Phone/E-mail: (909) 860-8216 / fny9@hotmail.com



APPROVED FOR ISSUANCE
REFER TO ENCROACHMENT AND/OR
CONSTRUCTION PERMIT AND PLAN
COVER SHEET FOR SPECIAL
CONDITIONS AND PERMIT NUMBERING

POLLUTANTS AND POLLUTANT SOURCE AREAS:
SEDIMENT: roads, parking lots and roofs
The main component of total suspended solids (TSS), and is detrimental to aquatic life. They also transport pollutants such as trace metal, nutrients, and hydrocarbons that attach to each particle.

ORGANIC COMPOUNDS: automotive fluids, pesticides and fertilizers
Organic compounds often attach to soil particles

NUTRIENTS: organic litter, fertilizers, food waste, sewage and sediment.
Nutrients include nitrogen, phosphorus and other organic compounds. Excess nutrients impact creek health and impair use of water in water supply sources by promoting excessive growth of algae or vegetation.

METALS: motor vehicles, roofing and construction materials and chemicals.
Trace metals such as copper, lead, cadmium, chromium, nickel and zinc can be toxic to aquatic organisms and, in accumulated quantities, can contaminate drinking water supplies.

BACTERIA & VIRUSES: animal excrement (areas where pets are often walked), sanitary overflow, and trash handling areas (dumpsters).
Bacteria & viruses may pose public health and safety concerns if they are present in drinking water sources.

OIL & GREASE: motor vehicles, food service establishments and fueling stations.
Oil & grease act as carriers for heavy metals and contain hydrocarbon compounds, which even at low concentrations may be toxic to aquatic organisms.

STORMWATER TREATMENT SUMMARY

The infill site will be designed to Minimize the Directly Connected Impervious Area (DCIA). The downspouts will not be directly connected to the storm sewer system and will be directed into the landscape areas.


The site will use Bioretention to treat impervious areas. A range of treatment measures may be utilized for this infill site, including but not limited to infiltration, concrete pervious pavers, and bioretentions.
This will maximize the opportunity for the runoff to be cleaned before it enters the collection system.
These measures will be maintained by the home owner.

BIORETENTION AREA MAINTENANCE PLAN

- OBJECTIVES**
THE PRINCIPAL MAINTENANCE OBJECTIVE IS TO PREVENT SEDIMENT BUILDUP AND CLOGGING, WHICH REDUCES POLLUTANT REMOVAL EFFICIENCY AND MAY LEAD TO BIORETENTION AREA FAILURE.
- ROUTINE MAINTENANCE ACTIVITIES**
ROUTINE MAINTENANCE ACTIVITIES, AND THE FREQUENCY AT WHICH THEY WILL BE CONDUCTED:
2.1 REMOVE OBSTRUCTIONS, DEBRIS AND TRASH FROM BIORETENTION AREA AND DISPOSE OF PROPERLY. MONTHLY, OR AS NEEDED AFTER STORM EVENTS.
2.2 INSPECT BIORETENTION AREA TO ENSURE THAT IT DRAINS BETWEEN STORMS AND WITHIN FIVE DAYS AFTER RAINFALL. MONTHLY, OR AS NEEDED AFTER STORM EVENTS.
2.3 INSPECT INLETS FOR CHANNELS, SOIL EXPOSURE OR OTHER EVIDENCE OF EROSION. CLEAR OBSTRUCTIONS AND REMOVE SEDIMENT. MONTHLY, OR AS NEEDED AFTER STORM EVENTS.
2.4 REMOVE AND REPLACE ALL DEAD AND DISEASED VEGETATION. TWICE A YEAR.
2.5 MAINTAIN VEGETATION AND THE IRRIGATION SYSTEM. PRUNE AND WEED TO KEEP BIORETENTION AREA NEAT AND ORDERLY IN APPEARANCE. BEFORE WET SEASON BEGINS, OR AS NEEDED.
2.6 CHECK THAT MULCH IS AT APPROPRIATE DEPTH (3 INCHES PER SOIL SPECIFICATIONS) AND REPLENISH AS NECESSARY BEFORE WET SEASON BEGINS. MONTHLY.
2.7 INSPECT BIORETENTION AREA USING THE ATTACHED INSPECTION CHECKLIST. MONTHLY, OR AFTER LARGE STORM EVENTS, AND AFTER REMOVAL OF ACCUMULATED DEBRIS OR MATERIAL.
- PROHIBITIONS**
THE USE OF PESTICIDES AND QUICK RELEASE FERTILIZERS SHALL BE MINIMIZED, AND THE PRINCIPLES OF INTEGRATED PEST MANAGEMENT (IPM) FOLLOWED:
3.1 EMPLOY NON-CHEMICAL CONTROLS (BIOLOGICAL, PHYSICAL AND CULTURAL CONTROLS) BEFORE USING CHEMICALS TO TREAT A PEST PROBLEM.
3.2 PRUNE PLANTS PROPERLY AND AT THE APPROPRIATE TIME OF YEAR.
3.3 PROVIDE ADEQUATE IRRIGATION FOR LANDSCAPE PLANTS. DO NOT OVER WATER.
3.4 LIMIT FERTILIZER USE UNLESS SOIL TESTING INDICATES A DEFICIENCY. SLOW-RELEASE OR ORGANIC FERTILIZER IS PREFERABLE. CHECK WITH MUNICIPALITY FOR SPECIFIC REQUIREMENTS.
3.5 PEST CONTROL SHOULD AVOID HARMING NON-TARGET ORGANISMS, OR NEGATIVELY AFFECTING AIR AND WATER QUALITY AND PUBLIC HEALTH. APPLY CHEMICAL CONTROLS ONLY WHEN MONITORING INDICATES THAT PREVENTATIVE AND NON-CHEMICAL METHODS ARE NOT KEEPING PESTS BELOW ACCEPTABLE LEVELS. WHEN PESTICIDES ARE REQUIRED, APPLY THE LEAST TOXIC AND THE LEAST PERSISTENT PESTICIDE THAT WILL PROVIDE ADEQUATE PEST CONTROL. DO NOT APPLY PESTICIDES ON A PRESCHEDULED BASIS.
3.6 SWEEP UP SPILLED FERTILIZER AND PESTICIDES. DO NOT WASH AWAY OR BURY SUCH SPILLS.
3.7 DO NOT OVER APPLY PESTICIDE. SPRAY ONLY WHERE THE INFESTATION EXISTS. FOLLOW THE MANUFACTURER'S INSTRUCTIONS FOR MIXING AND APPLYING MATERIALS.
3.8 ONLY LICENSED, TRAINED PESTICIDE APPLICATORS SHALL APPLY PESTICIDES.
3.9 APPLY PESTICIDES AT THE APPROPRIATE TIME TO MAXIMIZE THEIR EFFECTIVENESS AND MINIMIZE THE LIKELIHOOD OF DISCHARGING PESTICIDES INTO RUNOFF. WITH THE EXCEPTION OF PRE-EMERGENT PESTICIDES, AVOID APPLICATION IF RAIN IS EXPECTED.
3.10 UNWANTED/UNUSED PESTICIDES SHALL BE DISPOSED AS HAZARDOUS WASTE.
- VECTOR CONTROL**
4.1 OBJECTIVE: TO PREVENT CONDITIONS WITHIN SWALES THAT ATTRACT AND/OR PROMOTE THE GROWTH OF DISEASE VECTORS, INCLUDING BUT NOT LIMITED TO MOSQUITOS, RODENTS, AND FLIES.
4.2 MAINTENANCE ACTIVITIES FOR VECTOR CONTROL
4.2.1 INSPECTIONS: REGULAR INSPECTIONS WILL DETERMINE IF SWALES HAVE POOLS OF STANDING WATER OR DEBRIS ACCUMULATION. INSPECTIONS WILL BE CONDUCTED PRIOR TO THE RAINY SEASON, AFTER MAJOR STORM EVENTS, AND AT LEAST ONCE DURING THE DRY SEASON TO ASCERTAIN THAT STANDING WATER DRAINS FROM THE SWALE WITHIN 5 DAYS.
4.2.2 HOLES IN GROUND: ABATE POTENTIAL VECTORS BY FILLING HOLES IN THE GROUND IN AND AROUND THE SWALE AND BY INSURING THAT THERE ARE NO AREAS WHERE WATER STANDS LONGER THAN 5 DAYS FOLLOWING A STORM.
4.2.3 OTHER MAINTENANCE ACTIVITIES: IF ANY OBSTRUCTIONS DEVELOP (E.G. DEBRIS ACCUMULATION, INVASIVE VEGETATION, CLOGGING OF OUTLETS AND/OR UNDER DRAINS) WITHIN THE SWALE, APPROPRIATE MAINTENANCE ACTIVITIES SHALL BE IMPLEMENTED TO CORRECT THE OBSTRUCTION. REFER TO SECTION 3 FOR DETAILS ON SPECIFIC MAINTENANCE ACTIVITIES.
4.3 MOSQUITO ABATEMENT: THE AUTHORITY IN SANTA CLARA COUNTY IN CHARGE OF MOSQUITO ABATEMENT SHALL BE CONTACTED AS NEEDED FOR ASSISTANCE SHOULD ANY MOSQUITO ISSUES ARISE. MOSQUITO LARVICIDES SHOULD BE APPLIED ONLY WHEN ABSOLUTELY NECESSARY AND THEN ONLY BY A LICENSED PROFESSIONAL OR CONTRACTOR.
- CORRESPONDENCE**
CORRESPONDENCE REGARDING OPERATIONS, INSPECTIONS AND MAINTENANCE OF THE STORM WATER TREATMENT MEASURES WILL BE PROVIDED TO THE COUNTY OF SANTA CLARA ENVIRONMENTAL SERVICES DIVISION AS REQUIRED AND ACCORDING TO THE SCHEDULE OUTLINED IN THE OPERATIONS AND MAINTENANCE AGREEMENT.

CONTRACTOR AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING BUT NOT LIMITED TO THE SAFETY OF ALL PERSONS AND PROPERTY FROM THE PROJECT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN AND CONSTRUCTION OF ALL WORK AND SHALL BE RESPONSIBLE FOR THE PERFORMANCE OF THE WORK.

NO.	DATE	CITY	BY	REVISIONS



OSUNA ENGINEERING INC.
Planning | Surveying | Civil Engineering
CONSULTING CIVIL ENGINEERS & LAND SURVEYORS
1949 O' TOOLE WAY
SAN JOSE, CA 95131
TEL: (408) 721-2100
info@osunaengineering.com

OSUNA ENGINEERING INC.
CONSULTING CIVIL ENGINEERS & LAND SURVEYORS
1949 O' TOOLE WAY
SAN JOSE, CA 95131
TEL: (408) 721-2100
info@osunaengineering.com

PUBLIC IMPROVEMENTS AND GRADING & DRAINAGE PLAN
STORMWATER CONTROL PLAN
11655 FOOTHILL AVE
CITY OF GILROY, CALIFORNIA
Project No.: 1383 | Design: T.M.N. | Check: D.C. | Date: 11/8/24

SHEET
C3.1
OF 13 SHEETS

CONTRACTOR AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING THE SAFETY OF ALL PERSONS AND PROPERTY THAT IS IN THE VICINITY OF THE PROJECT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL UTILITIES AND STRUCTURES ON THIS PROJECT, EXCEPTING FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR THE ENGINEER.



TREATMENT CONTROL MEASURE SUMMARY TABLE													
DMA #	TCM #	Location ¹	Treatment Type ²	LID or Non-LID	Sizing Method	Drainage Area (s.f.)	Impervious Area ³ (s.f.)	Pervious Area (Permeable Pavement) (s.f.)	Pervious Area (Other) (s.f.)	% Onsite Area Treated by LID or Non-LID TCM	Bioretention		Overflow Riser Height (in)
											Bioretention Area Required (s.f.)	Bioretention Area Provided (s.f.)	
1	1	Onsite	Bioretention unlined w/ underdrain	LID	2C. Flow. 4% Method **	158,416	32,006	0	126,410	53.17%	1,279	1,300	6
2	2	Onsite	Self-treating areas (landscaped)	LID	N/A	139,534	0	0	139,534	46.83%			
Totals:						297,950	32,006	0	265,944	100.00%			

Footnotes:

- "Lined" refers to an impermeable liner placed on the bottom of a Bioretention basin or a concrete Flow-Through Planter, such that no infiltration into native soil occurs.
- Sizing for Bioretention Area Required calculated using the 4% Method (Impervious Area x 0.04)
- Gravel is considered as an impervious surface unless it is part of an infiltration trench.

Project Watershed/Receiving Water (creek, river): **Church Creek**

1. Total Project Area	42,576	ft ²
2. Pre-Project		
(a) Impervious Area	0	ft ²
(b) Pervious Area	42,576	ft ²
3. Post-Project		
(a) Replaced Impervious Area	0	ft ²
(b) New Impervious Area	32,006	ft ²
(c) Total Post-Project Impervious Area (sum of Line 3a and Line 3b)	32,006	ft ²
(d) Post-Project Pervious Area	10,570	ft ²
Net Impervious Area		
4. Reduced Impervious Area Credit (Line 2a minus Line 3c)	0	ft ²
5. Net Impervious Area (Line 3c minus Line 4)	32,006	ft ²



STORMWATER LEGEND

- LANDSCAPE - SELF TREATING AREAS
- IMPERVIOUS SURFACES
- BIORETENTION
- POND
- LANDSCAPE - SELF TREATING AREAS

BIORETENTION, SEE DETAIL E SHEET C4.1

TCM: 1
1,300 SF

earthen swale. See detail G sheet C5

PROPOSED POND FOR STORING EXCESS RUNOFF BY POST-DEVELOPMENT. SEE DETAIL G SHEET C4.1

APPROVED FOR ISSUANCE
REFER TO ENCROACHMENT AND/OR CONSTRUCTION PERMIT AND PLAN COVER SHEET FOR SPECIAL CONDITIONS AND PERMIT NUMBERING

NO.	DATE	BY	CITY	REVISIONS

REGISTERED PROFESSIONAL ENGINEER
PORFIRIO OSCAR OSUNA
No. 70829
Exp. 6-30-25
CIVIL
STATE OF CALIFORNIA


P. Oscar Osuna
PORFIRIO OSCAR OSUNA
RCE 70829 EXP. 6-30-25

OSUNA ENGINEERING INC.
Planning | Surveying | Civil Engineering

CONSULTING CIVIL ENGINEERS & LAND SURVEYORS
1949 O' TOOLE WAY
SAN JOSE, CA 95131
TEL: (408) 721-2100
Info@osunaengineering.com


PUBLIC IMPROVEMENTS AND GRADING & DRAINAGE PLAN
STORMWATER CONTROL PLAN
11655 FOOTHILL AVE
CITY OF GALTOS, CALIFORNIA
Project No.: 1383 | Designed: T.M.N. | Checked: D.C. | Date: 11/8/24

SHEET
C3.2
OF 13 SHEETS




- NOTE:
1. CONCRETE STRENGTH: 3,500 PSI IN 28 DAYS
 2. PAVEMENT SHOULD BE LATERALLY CONSTRAINED WITH CONCRETE VERTICAL CURBS OR 1.5' DEEPENED SHOULDERS
 3. INSTALL SUFFICIENT CONTROL JOINTS TO LIMIT AND CONTROL CRACKING
 4. REFER TO LANDSCAPE PLANS FOR PATTERN AND COLOR.

CONCRETE PAVEMENT SECTION
N.T.S.



LANDSCAPE DRAIN DETAIL
N.T.S.


NOTE: ALL GRADING IS BASED OFF OF THIS ARCHITECTURAL SECTION. THE ADJACENT GRADE AND GFF DIMENSIONS SHOWN HERE MUST BE KEPT. NOTIFY THE ENGINEER BEFORE MAKING ANY CHANGES.



N.T.S.


A CONCRETE DRIVEWAY DETAIL

NOTE: ALL GRADING IS BASED OFF OF THIS ARCHITECTURAL SECTION. THE ADJACENT GRADE AND GFF DIMENSIONS SHOWN HERE MUST BE KEPT. NOTIFY THE ENGINEER BEFORE MAKING ANY CHANGES.



N.T.S.


B AREA DRAIN DETAIL



CROSS SECTION OF BIORETENTION AREA (SIDE VIEW)
PER FIGURE 6-3 OF C3 HANDBOOK
N.T.S.

N.T.S.

C TYPICAL FOUNDATION/FF/GROUND SECTION




N.T.S.

D TYPICAL FOUNDATION/GFF/GROUND SECTION


E BIORETENTION DETAIL

F EARTHEN SWALE DETAIL




SECTION A'-A'
N.T.S.

G POND RETENTION DETAIL



SECTION POND PROFILE

H POND SECTION



SPLASH BLOCK/DOWNSPOUT DETAIL
N.T.S.

I SPLASH BLOCK/DOWNSPOUT DETAIL

NO.	REVISIONS	DATE	BY	CITY



Porfirio Oscar Osuna
PORFIRIO OSCAR OSUNA
RCE 70829 EXP. 6-30-25






OSUNA ENGINEERING INC.
Planning / Surveying / Civil Engineering
CONSULTING CIVIL ENGINEERS & LAND SURVEYORS
1949 O' TOOLE WAY
SAN JOSE, CA 95131
TEL: (408) 721-2100
Info@osunaengineering.com

PUBLIC IMPROVEMENTS AND GRADING & DRAINAGE PLAN DETAILS AND SECTIONS
11655 FOOTHILL AVE
CITY OF GILROY
Project No.: 1383
Design: J0/00
Check: O.C.
Date: 11/8/24

SHEET C4.1
OF 13 SHEETS

CONTRACTOR AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING THE SAFETY OF ALL PERSONS AND PROPERTY THAT IS IN THE VICINITY OF THE PROJECT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND SHALL BE RESPONSIBLE FOR THE PERFORMANCE OF THE WORK ON THIS PROJECT, EXCEPTING FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR THE ENGINEER.

CONTRACTOR AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING THE SAFETY OF ALL PERSONS AND PROPERTY. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND SHALL BE RESPONSIBLE FOR THE PERFORMANCE OF ALL WORK ON THIS PROJECT, EXCEPTING FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR THE ENGINEER.



NO.	DATE	BY	CITY	REVISIONS

REGISTERED PROFESSIONAL ENGINEER
 PORFIRIO OSCAR OSUNA
 No. 70829
 Exp. 6-30-25
 CIVIL
 STATE OF CALIFORNIA
P. Oscar Osuna
 PORFIRIO OSCAR OSUNA
 RCE 70829 EXP. 6-30-25

OSUNA ENGINEERING INC.
 Planning | Surveying | Civil Engineering
 CONSULTING CIVIL ENGINEERS & LAND SURVEYORS
 TEL: (408) 721-2100
 info@osunaengineering.com
 1949 O' TOOLE WAY
 SAN JOSE, CA 95131



PUBLIC IMPROVEMENTS AND
 GRADING & DRAINAGE PLAN
 DETAILS AND SECTIONS
 11655 FOOTHILL AVE
 CITY OF GALTOS CALIFORNIA
 Project No.: 1383 Designed: J0/00 Checked: O.O. Date: 11/8/24

SHEET
C4.2
 OF 13 SHEETS

SECTIONS

H: SCALE: 1"=20' ; V: SCALE: 1"=10'

CONTRACTOR AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING THE SAFETY OF ALL PERSONS AND PROPERTY FROM THE PROJECT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND FOR OBTAINING ALL NECESSARY INSURANCE COVERAGE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND FOR OBTAINING ALL NECESSARY INSURANCE COVERAGE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND FOR OBTAINING ALL NECESSARY INSURANCE COVERAGE.



NOTES:
 1. PROTECT ALL INLETS IN THE PUBLIC STREETS SURROUNDING THE SITE.
 2. ALL ON-SITE LANDSCAPE AREA DRAINS TO BE CAPPED OR PROTECTED UNTIL LANDSCAPING IS FINISHED.

EROSION & SEDIMENT CONTROL NOTES

1. NOT USED
2. THE DEVELOPER IS RESPONSIBLE FOR ENSURING THAT ALL CONTRACTORS AND SUBCONTRACTORS ARE AWARE OF ALL STORM WATER QUALITY MEASURES AND IMPLEMENT SUCH MEASURES. FAILURE TO COMPLY WITH THE APPROVED CONSTRUCTION BEST MANAGEMENT PRACTICES WILL RESULT IN THE ISSUANCE OF CORRECTION NOTICES, CITATIONS, AND/OR STOP ORDERS.
3. ANY VEHICLE OR EQUIPMENT WASHING/STEAM CLEANING MUST BE DONE AT AN APPROPRIATELY EQUIPPED FACILITY WHICH DRAINS TO THE SANITARY SEWER. OUTDOOR WASHING MUST BE MANAGED IN SUCH A WAY THAT THERE IS NO DISCHARGE OF SOAPS, SOLVENTS, CLEANING AGENTS OR OTHER POLLUTANTS TO THE STORM DRAINS. WASH WATER SHALL DISCHARGE TO THE SANITARY SEWER, SUBJECT TO REVIEW AND APPROVAL OF UNION SANITARY DISTRICT.
4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR LITTER CONTROL AND SWEEPING OF ALL PAVED SURFACES DURING CONSTRUCTION.
5. THE FACILITIES SHOWN ON THIS PLAN ARE DESIGNED TO CONTROL EROSION AND SEDIMENT DURING THE RAINY SEASON, OCTOBER 1 TO APRIL 15. EROSION CONTROL MEASURES ARE TO BE FUNCTIONAL PRIOR TO OCTOBER 1ST OF ANY YEAR GRADING OPERATIONS HAVE LEFT AREAS UNPROTECTED FROM EROSION.
6. ALL ON-SITE STORM DRAINS SHALL BE CLEANED IMMEDIATELY BEFORE THE START OF THE RAINY SEASON BEGINNING ON OCTOBER 1ST EACH YEAR, SUBJECT TO THE REVIEW OF THE BUILDING/ENGINEERING INSPECTOR.
7. IF RAINY WEATHER BECOMES IMMINENT, GRADING OPERATIONS SHALL BE STOPPED AND EROSION CONTROL MEASURES SHALL BE IMPLEMENTED TO PROTECT DISTURBED AREAS.
8. DURING THE RAINY SEASON, ALL PAVED AREAS SHALL BE KEPT CLEAR OF EARTH MATERIAL AND DEBRIS. THE SITE SHALL BE MAINTAINED SO AS TO MINIMIZE SEDIMENT LADEN RUNOFF TO ANY STORM DRAIN SYSTEM.
9. CONSTRUCTION ENTRANCES SHALL CONSIST OF A MINIMUM 8" THICK LAYER OF 3"-4" FRACTURED STONE AGGREGATE UNLAI D WITH GEOTEXTILE LINER FOR A MINIMUM DISTANCE OF 50 FEET, AND IS TO BE PROVIDED AT EACH VEHICLE ACCESS POINT TO EXISTING PAVED STREETS. THE DEPTH AND LENGTH OF AGGREGATE MAY NEED TO BE ADJUSTED IN THE FIELD TO ENSURE NO TRACKING OF SEDIMENT ONTO EXISTING PAVED STREETS. CONSTRUCTION ENTRANCES SHALL SLOPE AWAY FROM EXISTING PAVED STREETS.
10. INLETS NOT USED IN CONJUNCTION WITH EROSION CONTROL MEASURES ARE TO BE BLOCKED UNLESS THE AREA DRAINED IS UNDISTURBED OR STABILIZED.
11. BORROW AREAS AND TEMPORARY STOCKPILES SHALL BE PROTECTED WITH APPROPRIATE EROSION CONTROL MEASURES TO THE SATISFACTION OF THE CITY ENGINEER.
12. NO STRAW BALES OR SILT FENCES SHALL BE USED AS EROSION CONTROL MEASURES. SILT FENCES MAY ONLY BE USED AS A PHYSICAL BARRIER TO PREVENT VEHICULAR AND PEDESTRIAN TRAFFIC FROM USING NON-APPROVED ACCESS POINTS (E.G. - ALONG RIGHT-OF-WAY).
13. ALL DISTURBED AREAS INCLUDING FLAT PADS ARE TO BE TREATED WITH STRAW AND TACKIFIER AT A RATE OF 2 TONS PER ACRE APPROXIMATELY 3 INCHES THICK.

SUPPLEMENTAL EROSION & SEDIMENT CONTROL NOTES

1. SEE STANDARD EROSION & SEDIMENT CONTROL NOTES ABOVE.
2. THE FACILITIES SHOWN ON THIS PLAN ARE DESIGNED TO CONTROL EROSION AND SEDIMENT DURING THE RAINY SEASON, OCTOBER 1 TO APRIL 15. FACILITIES ARE TO BE OPERABLE PRIOR TO OCTOBER 1 OF ANY YEAR. GRADING OPERATIONS DURING THE RAINY SEASON WHICH LEAVE DENUDED SLOPES SHALL BE PROTECTED WITH EROSION CONTROL MEASURES IMMEDIATELY FOLLOWING GRADING ON THE SLOPES.
3. CONSTRUCTION ENTRANCES SHALL BE INSTALLED PRIOR TO COMMENCEMENT OF GRADING. ALL CONSTRUCTION TRAFFIC ENTERING ONTO THE PAVED ROADS MUST CROSS THE STABILIZED CONSTRUCTION ENTRANCE WAYS.
4. CONTRACTOR SHALL MAINTAIN STABILIZED ENTRANCE AT EACH VEHICLE ACCESS POINT TO EXISTING PAVED STREETS. ANY MUD OR DEBRIS TRACKED ONTO PUBLIC STREETS SHALL BE REMOVED DAILY AND AS REQUIRED BY THE COUNTY.
5. INLET PROTECTION SHALL BE INSTALLED AT OPEN INLETS TO PREVENT SEDIMENT FROM ENTERING THE STORM DRAIN SYSTEM. INLETS NOT USED IN CONJUNCTION WITH EROSION CONTROL ARE TO BE BLOCKED TO PREVENT ENTRY OF SEDIMENT.
6. THIS EROSION AND SEDIMENT CONTROL PLAN MAY NOT COVER ALL THE SITUATIONS THAT MAY ARISE DURING CONSTRUCTION DUE TO UNANTICIPATED FIELD CONDITIONS. VARIATIONS AND ADDITIONS MAY BE MADE TO THIS PLAN IN THE FIELD. NOTIFY THE COUNTY REPRESENTATIVE OF ANY FIELD CHANGES.


LEGEND

PROPOSED	DESCRIPTION
---	SITE BOUNDARY
[Pattern of circles]	STABILIZED CONSTRUCTION ENTRANCE 4"-6" ROCK (MIN)
[Line with cross-hatch]	FIBER ROLL

MAINTENANCE NOTES

- MAINTENANCE IS TO BE PERFORMED AS FOLLOWS:
1. REPAIR DAMAGES CAUSED BY SOIL EROSION OR CONSTRUCTION AT THE END OF EACH WORKING DAY.
 2. SWALES SHALL BE INSPECTED PERIODICALLY AND MAINTAINED AS NEEDED.
 3. SEDIMENT TRAPS, BERMS, AND SWALES ARE TO BE INSPECTED AFTER EACH STORM AND REPAIRS MADE AS NEEDED.
 4. SEDIMENT SHALL BE REMOVED AND SEDIMENT TRAP RESTORED TO ITS ORIGINAL DIMENSIONS WHEN SEDIMENT HAS ACCUMULATED TO A DEPTH OF 1 FOOT.
 5. SEDIMENT REMOVED FROM TRAP SHALL BE DEPOSITED IN A SUITABLE AREA AND IN SUCH A MANNER THAT IT WILL NOT ERODE.
 6. RILLS AND GULLIES MUST BE REPAIRED.

APPROVED FOR ISSUANCE
 REFER TO ENCROACHMENT AND/OR
 CONSTRUCTION PERMIT AND PLAN
 COVER SHEET FOR SPECIAL
 CONDITIONS AND PERMIT NUMBERING



OSUNA ENGINEERING INC.
 Planning | Surveying | Civil Engineering


CONSULTING CIVIL ENGINEERS & LAND SURVEYORS
 1949 O' TOOLE WAY
 SAN JOSE, CA 95131
 TEL: (408) 721-2100
 info@osunaengineering.com

PUBLIC IMPROVEMENTS AND GRADING & DRAINAGE PLAN
EROSION CONTROL PLAN
 11655 FOOTHILL AVE
 CITY OF GILROY, CALIFORNIA
 Project No.: 1383 Design: J07/MW Check: D.C. Date: 11/8/24


NO.	REVISIONS	DATE	CITY	BY

CONTRACTOR AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING THE SAFETY OF ALL PERSONS AND PROPERTY FROM HAZARDOUS AND UNUSUAL WORKING CONDITIONS AND THAT THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM THE CITY OF GILROY AND THE COUNTY OF SANTA CLARA. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM THE CITY OF GILROY AND THE COUNTY OF SANTA CLARA. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM THE CITY OF GILROY AND THE COUNTY OF SANTA CLARA.

3 Stabilized Construction Entrance/Exit
CASQA Detail TC-1




4 Velocity Dissipation Devices
CASQA Detail EC-10




Source for Graphics: California Stormwater BMP Handbook, California Stormwater Quality Association, January 2003. Available from www.cabmphandbooks.com.

1 Silt Fence
CASQA Detail SE-1



2 Silt Fence
CASQA Detail SE-1



STANDARD BEST MANAGEMENT PRACTICE NOTES

- Solid and Demolition Waste Management:** Provide designated waste collection areas and containers on site away from streets, gutters, storm drains, and waterways, and arrange for regular disposal. Waste containers must be watertight and covered at all times except when waste is deposited. Refer to Erosion & Sediment Control Field Manual, 4th Edition (page C3) or latest.
- Hazardous Waste Management:** Provide proper handling and disposal of hazardous wastes by a licensed hazardous waste material hauler. Hazardous wastes shall be stored and properly labeled in sealed containers constructed of suitable materials. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-5 to C-6) or latest.
- Spill Prevention and Control:** Provide proper storage areas for liquid and solid materials, including chemicals and hazardous substances, away from streets, gutters, storm drains, and waterways. Spill control materials must be kept on site where readily accessible. Spills must be cleaned up immediately and contaminated soil disposed properly. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-7 to C-8, C-13 to C-14) or latest.
- Vehicle and Construction Equipment Service and Storage:** An area shall be designated for the maintenance, where on-site maintenance is required, and storage of equipment that is protected from stormwater run-on and runoff. Measures shall be provided to capture any waste oils, lubricants, or other potential pollutants and these wastes shall be properly disposed of off site. Fueling and major maintenance/repair, and washing shall be conducted off-site whenever feasible. Refer to Erosion & Sediment Control Field Manual, 4th Edition (page C9) or latest.
- Material Delivery, Handling and Storage:** In general, materials should not be stockpiled on site. Where temporary stockpiles are necessary and approved by the County, they shall be covered with secured plastic sheeting or tarp and located in designated areas near construction entrances and away from drainage paths and waterways. Barriers shall be provided around storage areas where materials are potentially in contact with runoff. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-11 to C-12) or latest.
- Handling and Disposal of Concrete and Cement:** When concrete trucks and equipment are washed on-site, concrete wastewater shall be contained in designated containers or in a temporary lined and watertight pit where wasted concrete can harden for later removal. If possible have concrete contractor remove concrete wash water from site. In no case shall fresh concrete be washed into the road right-of-way. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-15 to C-16) or latest.
- Pavement Construction Management:** Prevent or reduce the discharge of pollutants from paving operations, using measures to prevent run-on and runoff pollution and properly disposing of wastes. Avoid paving in the wet season and reschedule paving when rain is in the forecast. Residue from saw-cutting shall be vacuumed for proper disposal. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-17 to C-18) or latest.
- Contaminated Soil and Water Management:** Inspections to identify contaminated soils should occur prior to construction and at regular intervals during construction. Remediating contaminated soil should occur promptly after identification and be specific to the contaminant identified, which may include hazardous waste removal. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-19 to C-20) or latest.
- Sanitary/Septic Water Management:** Temporary sanitary facilities should be located away from drainage paths, waterways, and traffic areas. Only licensed sanitary and septic waste haulers should be used. Secondary containment should be provided for all sanitary facilities. Refer to Erosion & Sediment Control Field Manual, 4th Edition (page C-21) or latest.
- Inspection & Maintenance:** Areas of material and equipment storage sites and temporary sanitary facilities must be inspected weekly. Problem areas shall be identified and appropriate additional and/or alternative control measures implemented immediately, within 24 hours of the problem being identified.

STANDARD EROSION CONTROL NOTES

- Sediment Control Management:**
 - Tracking Prevention & Clean Up:** Activities shall be organized and measures taken as needed to prevent or minimize tracking of soil onto the public street system. A gravel or proprietary device construction entrance/exit is required for all sites. Clean up of tracked material shall be provided by means of a street sweeper prior to an approaching rain event, or at least once at the end of each workday that material is tracked, or, more frequently as determined by the County Inspector. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages B-31 to B-33) or latest.
 - Storm Drain Inlet and Catch Basin Inlet Protection:** All inlets within the vicinity of the project and within the project limits shall be protected with gravel bags placed around inlets or other inlet protection. At locations where exposed soils are present, staked fiber rolls or staked silt fences can be used. Inlet filters are not allowed due to clogging and subsequent flooding. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages B-49 to B-51) or latest.
 - Storm Water Runoff:** No storm water runoff shall be allowed to drain in to the existing and/or proposed underground storm drain system or other above ground watercourses until appropriate erosion control measures are fully installed.
 - Dust Control:** The contractor shall provide dust control in graded areas as required by providing wet suppression or chemical stabilization of exposed soils, providing for rapid clean up of sediments deposited on paved roads, furnishing construction road entrances and vehicle wash down areas, and limiting the amount of areas disturbed by clearing and earth moving operations by scheduling these activities in phases.
 - Stockpiling:** Excavated soils shall not be placed in streets or on paved areas. Borrow and temporary stockpiles shall be protected with appropriate erosion control measures (tarp, straw bales, silt fences, etc.) to ensure silt does not leave the site or enter the storm drain system or neighboring watercourse.
- Erosion Control:** During the rainy season, all disturbed areas must include an effective combination of erosion and sediment control. It is required that temporary erosion control measures are applied to all disturbed soil areas prior to a rain event. During the non-rainy season, erosion control measures must be applied sufficient to control wind erosion at the site.
- Inspection & Maintenance:** Disturbed areas of the Project's site, locations where vehicles enter or exit the site, and all erosion and sediment controls that are identified as part of the Erosion Control Plans must be inspected by the Contractor before, during, and after storm events, and at least weekly during seasonal wet periods. Problem areas shall be identified and appropriate additional and/or alternative control measures implemented immediately, within 24 hours of the problem being identified.
- Project Completion:** Prior to project completion and signoff by the County Inspector, all disturbed areas shall be reseeded, planted, or landscaped to minimize the potential for erosion on the subject site.
- It shall be the Owner's/Contractor's responsibility to maintain control of the entire construction operation and to keep the entire site in compliance with the erosion control plan.
- Erosion and sediment control best management practices shall be operable year round or until vegetation is fully established on landscaped surfaces.

Project Information

Best Management Practices and Erosion Control Details Sheet 1
County of Santa Clara



BMP-1

APPROVED FOR ISSUANCE
REFER TO ENCROACHMENT AND/OR
CONSTRUCTION PERMIT AND PLAN
COVER SHEET FOR SPECIAL
CONDITIONS AND PERMIT NUMBERING

OSUNA ENGINEERING INC.
Planning / Surveying / Civil Engineering
CONSULTING CIVIL ENGINEERS & LAND SURVEYORS
1949 O' TOOLE WAY
SAN JOSE, CA 95131
TEL: (408) 721-2100
Info@osunaengineering.com

OSUNA ENGINEERING INC.
No. 70829
Exp. 6-30-25
CIVIL
STATE OF CALIFORNIA









P. Oscar Osuna
PORFIRIO OSCAR OSUNA
RCE 70829 EXP. 6-30-25

OSUNA ENGINEERING INC.
PUBLIC IMPROVEMENTS AND GRADING & DRAINAGE PLAN
COUNTY BMP SHEET
11655 FOOTHILL AVE
CITY OF GILROY, CALIFORNIA
Project No.: 1383 Design: J.C. Check: D.C. Date: 11/8/24

REVISIONS
BY
CITY
DATE


SHEET
C7.1
OF 13 SHEETS

CONTRACTOR AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING THE PROVISION OF ALL NECESSARY PERMITS AND THE PROTECTION OF ALL UTILITIES AND ADJACENT PROPERTIES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND THE PROTECTION OF ALL UTILITIES AND ADJACENT PROPERTIES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND THE PROTECTION OF ALL UTILITIES AND ADJACENT PROPERTIES.




Project Information

NO.	DATE	BY	REVISIONS



OSUNA ENGINEERING INC.
Planning / Surveying / Civil Engineering
CONSULTING CIVIL ENGINEERS & LAND SURVEYORS
1949 O' TOOLE WAY
SAN JOSE, CA 95131
TEL: (408) 721-2100
Info@osunaengineering.com



PUBLIC IMPROVEMENTS AND GRADING & DRAINAGE PLAN
COUNTY BMP SHEET
11655 FOOTHILL AVE
CITY OF GILROY, CALIFORNIA
Project No.: 1383 | Designed: J.C. | Checked: D.C. | Date: 11/8/24

Best Management Practices and Erosion Control Details Sheet 2

County of Santa Clara



BMP-2

APPROVED FOR ISSUANCE
REFER TO ENCROACHMENT AND/OR
CONSTRUCTION PERMIT AND PLAN
COVER SHEET FOR SPECIAL
CONDITIONS AND PERMIT NUMBERING

SHEET
C7.2
OF 13 SHEETS