




DISCLAIMER: TS CIVIL ENGINEERING, INC. ONLY ACKNOWLEDGES ORIGINAL SIGNED AND STAMPED PLANS AND DRAWINGS. NO RESPONSIBILITY OR LIABILITY IS EXPRESSED OR IMPLIED FOR ELECTRONIC DATA AND/OR REPRODUCED PLANS AND DRAWINGS.

BOUNDARY AND TOPOGRAPHIC SURVEY  
 15201 CAMELOT DRIVE  
 SAN JOSE, CALIFORNIA  
 FEBRUARY 6, 2023  
 SCALE: 1" = 20'  
 CONTOUR INTERVAL = 1 FOOT



- LEGEND**
- FD. MONUMENT AS NOTED
  - ▲ FD. MAG NAIL
  - △ SET 1200 NAIL WITH PUNCH
  - CLEAN OUT
  - CC CONCRETE
  - CS CRAWL SPACE
  - EM ELECTRIC METER
  - FP FIRE PLACE
  - GM GAS METER
  - GP GATE POST
  - GUY POLE
  - JOINT POLE
  - MB MAIL BOX
  - OVERHANG SUPPORT POST
  - R ROCK
  - 4" X HEIGHT PVC BREATHING PIPE
  - S SEPTIC TANK LID
  - SPOT ELEVATION
  - 100.00+ STUMP AS NOTED
  - 12" TREE AS NOTED
  - 18" WATER LINE AT DAYLIGHT
  - WL WATER METER
  - BOUNDARY LINE
  - BUSHES/TREE OUTLINE
  - BUILDING LINE
  - EASEMENT LINE
  - FENCE LINE AS NOTED
  - SURVEY CONTROL LINE
  - TOE OF SLOPE
  - TOP OF SLOPE
  - RED PAINTED LINE-WATER
  - YELLOW PAINTED LINE-GAS

**BASIS OF BEARINGS AND BENCH MARK**  
 BEARINGS AND DISTANCES SHOWN ON THIS MAP ARE BASED ON A FAST-STATIC GPS SURVEY HOLDING SANTA CLARA VALLEY WATER DISTRICT NETWORK CONTROL POINTS P226 AND P221 THREE DIMENSIONALLY AND P227 VERTICALLY IN A LEAST SQUARES ADJUSTMENT OF THE GPS DATA. COORDINATE VALUES HELD ARE AS SHOWN ON THE RECORD OF SURVEY MAP FILED FEBRUARY 16, 2010 IN BOOK 835 OF MAPS AT PAGES 31 THROUGH 35, SANTA CLARA COUNTY RECORDS. MEASURED BEARINGS AND DISTANCES ARE GRID, NAD83, CALIFORNIA COORDINATE SYSTEM, ZONE 3, EPOCH 2009. MULTIPLY GRID DISTANCES BY 1.000071775 TO OBTAIN GROUND LEVEL DISTANCES. ELEVATIONS ARE ON THE NAVD88 ELEVATION DATUM.

**SURVEYOR'S STATEMENT**  
 THIS MAP CORRECTLY REPRESENTS A SURVEY MADE BY ME OR UNDER MY DIRECTION IN CONFORMANCE WITH THE REQUIREMENTS OF THE PROFESSIONAL LAND SURVEYORS' ACT AT THE REQUEST OF JORGE FERNANDEZ IN JANUARY 2023.  
*Kristina D. Comer*  
 KRISTINA D. COMERER, PLS 6766  
 DATE: FEBRUARY 14, 2023



**ATTENTION:**  
 THIS MAP IS PROVIDED IN AN ELECTRONIC FORMAT (ON COMPUTER DISK) AS A COURTESY TO JORGE FERNANDEZ. THE DELIVERY OF THE ELECTRONIC FILE DOES NOT CONSTITUTE THE DELIVERY OF OUR PROFESSIONAL WORK PRODUCT. THE SIGNED PAPER PRINT DELIVERED WITH THIS ELECTRONIC FILE CONSTITUTES OUR PROFESSIONAL WORK PRODUCT, AND IN THE EVENT THE ELECTRONIC FILE IS ALTERED, THE PRINT MUST BE REFERRED TO, FOR THE ORIGINAL AND CORRECT SURVEY INFORMATION. WE SHALL NOT BE RESPONSIBLE FOR ANY MODIFICATIONS MADE TO THE ELECTRONIC FILE, OR FOR ANY PRODUCTS, DERIVED FROM THE ELECTRONIC FILE WHICH ARE NOT REVIEWED, SIGNED AND SEALED BY US.  
 BY: *Kristina D. Comer*  
 DATE: FEBRUARY 14, 2023

**CROSS LAND SURVEYING, INC.**  
 2210 MT. PLEASANT ROAD  
 SAN JOSE, CA 95148  
 (408) 274-7994

TS/CIVIL ENGINEERING, INC.  
 1776 TECHNOLOGY DRIVE  
 SAN JOSE, CA 95110  
 PH: 408.452.9300  
 FAX: 408.837.7550

**TS** - CIVIL ENGINEERING



**TOPOGRAPHY PRIOR TO VIOLATION**  
 15201 CAMELOT DRIVE  
 SAN JOSE, CA 95132  
 APN 595-05-005

NO.	DATE	BY	REVISIONS
6			
5			
4			
3			
2			
1			

DATE: 09-22-25  
 SCALE: 1"=20'  
 DRAWN BY: DKH  
 SURVEYED BY: TJS  
 PROJ ENGR: TJS  
 CHECK BY: TJS  
 SHEET NO. **C-2**  
 OF 7 SHEET  
 JOB NO. 25-216

09/23/2025 5:21pm - Z:\2. Email Projects\EM09192025\_02 (TUS - NEED THIS SATURDAY - 1)\S\_Final\25-216 C-2 TOPOGRAPHIC SURVEY.dwg - C2

DISCLAIMER: TS CIVIL ENGINEERING, INC. ONLY ACKNOWLEDGES ORIGINAL SIGNED AND STAMPED PLANS AND DRAWINGS. NO RESPONSIBILITY OR LIABILITY IS EXPRESSED OR IMPLIED FOR ELECTRONIC DATA AND/OR REPRODUCED PLANS AND DRAWINGS.




R/S 179 M. 19  
R/S 174 M. 16  
PM 718 M. 20  
PARCEL 2

LEGEND	EXISTING	PROPOSED
PROPERTY LINE	---	---
ADJACENT PROPERTY LINE	---	---
STREET CENTER LINE	---	---
BUILDING SETBACK LINES	---	---
EASEMENT	---	---
DIRT ROAD	---	---
ROAD/PAVEMENT	---	---
CURB	---	---
CURB AND GUTTER	---	---
CONCRETE	---	---
CONTOUR MAJOR	---	---
CONTOUR MINOR	---	---
DAYLIGHT LINE	---	---
ROCK RETAINING WALL	---	---
DRIVEWAY	---	---
BUILDING	---	---
AC BERM	---	---
TOP OF BANK	---	---
TOE OF BANK	---	---
CREEK FLOWLINE	---	---
WIRE FENCE	---	---
CHAIN LINK FENCE	---	---
WOOD FENCE	---	---
SANITARY SEWER LINE	---	---
PERFORATED SEPTIC LINE	---	---
ELECTRIC LINE	---	---
GAS LINE	---	---
STORM DRAIN LINE	---	---
WATER LINE	---	---
OVERHEAD WIRE	---	---
DOWNSPOUT W/ SPLASHBLOCK	---	---
OVERLAND RELEASE	---	---
LIMIT OF WORK	---	---

**NOTE:**  
DISTURBED AREA = 9325 SF  
TOE & TOP OF FILLED AREA  
EQUAL DISTURBED AREA

- SCOPE OF WORK:**
1. CONDUCT PRE-CONSTRUCTION MEETING WITH LAND DEVELOPMENT FIELD INSPECTOR
  2. INSTALL PERIMETER EROSION CONTROL, PORTA-POTTY & CONSTRUCTION ENTRANCE
  3. STRIP VEGETATIVE MATERIAL FROM STOCKPILE & HAUL OFF TO LEGAL DUMPSITE, WATER SITE FOR DUST CONTROL
  4. EXCAVATE STOCKPILE & LOAD DUMP TRUCKS FOR HAULING, IF 20 CY PER LOAD APPROXIMATELY 60 LOADS
  5. EXPOSE ORIGINAL GROUND BELOW STOCKPILE & REMOVE ANY VEGETATIVE MATERIAL SCARIFY SURFACE AREA 6" TO 8" DEEP AND RECOMPACT SURFACE AT OPTIMUM MOISTURE TO 90% COMPACTION
  6. INSTALL STRAW WATTLES ACROSS RESTORED SLOPE SURFACE (4 ROWS AT 15' HORIZONTAL SPACING)
  7. COORDINATE COUNTY FINAL, INSPECTION
  8. SITE CLEAN-UP, REMOVE TOILET, REMOVE GRADING EQUIPMENT

DESIGNED UNDER THE SUPERVISION OF  
  
 TERENCE J. SZCWCZYK  
 EXPIRATION DATE: 09/30/25



**FILL VIOLATION GRADING PLAN**

15201 CAMELOT DRIVE  
SAN JOSE, CA 95132  
APN 595-05-005

NO.	REVISIONS	DATE
6		
5		
4		
3		
2		
1		


DATE: 09-22-25  
 SCALE: 1"=20'  
 DRAWN BY: DKH  
 SURVEYED BY: XXX  
 PROJ ENGR: TJS  
 CHECK BY: TJS

SHEET NO. **C-3**  
 OF 7 SHEET  
 JOB NO. 25-216

TS CIVIL ENGINEERING  
 1776 TECHNOLOGY DRIVE  
 SAN JOSE, CA 95110  
 PH: 408.452.9300  
 FAX: 408.837.7550




09/23/2025 5:45pm - Z: 2: Email Projects\EM09192025\_02 (TJS - NEED THIS SATURDAY - 1)\S\_Final\25-216 C-3 PRIOR TO VIOLATION.dwg - C3

DISCLAIMER: TS CIVIL ENGINEERING, INC. ONLY ACKNOWLEDGES ORIGINAL SIGNED AND STAMPED PLANS AND DRAWINGS. NO RESPONSIBILITY OR LIABILITY IS EXPRESSED OR IMPLIED FOR ELECTRONIC DATA AND/OR REPRODUCED PLANS AND DRAWINGS.



**FILL VOLUME SUMMARY**

-	0	20x35=700
A	40	72x35=2520
BB	104	192x35=6720
CC	280	280x35=9800
DD	280	252x35=8,820
EE	224	162x35=3920
-	0	TOTAL 32,480 CF
		+ 27=1202 CY




TS CIVIL ENGINEERING, INC.  
1776 TECHNOLOGY DRIVE  
SAN JOSE, CA 95110  
PH: 408.452.9300  
FAX: 408.837.7550

**GRADING CROSS SECTION**  
15201 CAMELOT DRIVE  
SAN JOSE, CA 95132  
APN 595-05-005

NO.	REVISIONS	DATE
6		
5		
4		
3		
2		
1		

DATE: 09-22-25  
SCALE: 1"=10'  
DRAWN BY: DKH  
SURVEYED BY: XXX  
PROJ ENGR: TJS  
CHECK BY: TJS



SHEET NO. **C-4**  
OF 7 SHEET  
JOB NO. 25-216



DESIGNED UNDER THE SUPERVISION OF  
TERENCE J. SZEWCZYK  
REGISTERED PROFESSIONAL ENGINEER  
NO. 35527  
EXP. 9-30-25  
STATE OF CALIFORNIA  
9-17-25  
TERENCE J. SZEWCZYK  
EXPIRATION DATE: 09/30/25

09/23/2025 7:03pm - Z:\2. Email Projects\EM09192025...02 (TJS - NEED THIS SATURDAY - 1)\S\_Final\25-216 C-4 CROSS SECTION.dwg - C2

DISCLAIMER: TS CIVIL ENGINEERING, INC. ONLY ACKNOWLEDGES ORIGINAL SIGNED AND STAMPED PLANS AND DRAWINGS. NO RESPONSIBILITY OR LIABILITY IS EXPRESSED OR IMPLIED FOR ELECTRONIC DATA AND/OR REPRODUCED PLANS AND DRAWINGS.




**LEGEND**

DESCRIPTION	EXISTING	PROPOSED
PROPERTY LINE	---	---
ADJACENT PROPERTY LINE	---	---
STREET CENTER LINE	---	---
BUILDING SETBACK LINES	---	---
EASEMENT	---	---
DIRT ROAD	---	---
ROAD/PAVEMENT	---	---
CURB	---	---
CURB AND GUTTER	---	---
CONCRETE	---	---
CONTOUR MAJOR	---	---
CONTOUR MINOR	---	---
DAYLIGHT LINE	---	---
ROCK RETAINING WALL	---	---
DRIVEWAY	---	---
BUILDING	---	---
AC BERM	---	---
TOP OF BANK	---	---
TOE OF BANK	---	---
CREEK FLOWLINE	---	---
WIRE FENCE	---	---
CHAIN LINK FENCE	---	---
WOOD FENCE	---	---
SANITARY SEWER LINE	---	---
PERFORATED SEPTIC LINE	---	---
ELECTRIC LINE	---	---
GAS LINE	---	---
STORM DRAIN LINE	---	---
WATER LINE	---	---
OVERHEAD WIRE	---	---
DOWNSPOUT W/ SPLASHBLOCK	---	---
OVERLAND RELEASE	---	---
LIMIT OF WORK	---	---

**LEGEND**

	ROCKED CONSTRUCTION ENTRANCE
	STAW WATTLES
	PORT-O-POTTY
	INLET PROTECTION




DESIGNED UNDER THE SUPERVISION OF  
  
 TERENCE J. SZCWCZYK  
 EXPIRATION DATE: 09/30/25

**SITE LOGISTICS & EROSION CONTROL PLAN**  
 15201 CAMELOT DRIVE  
 SAN JOSE, CA 95132  
 APN 595-05-005

NO.	REVISIONS	DATE
6		
5		
4		
3		
2		
1		

DATE: 09-22-25  
 SCALE: 1"=20'  
 DRAWN BY: DKH  
 SURVEYED BY: XXX  
 PROJ ENGR: TJS  
 CHECK BY: TJS  
 SHEET NO. **C-5**  
 OF 7 SHEET  
 JOB NO. 25-216

TS CIVIL ENGINEERING, INC.  
 1776 TECHNOLOGY DRIVE  
 SAN JOSE, CA 95110




PH: 408.452.9300  
 FAX: 408.837.7550

09/23/2025 6:07pm - Z:\2. Email Projects\EM09192025\_02 (TJS - NEED THIS SATURDAY - 1)\S\_Final\25-216 C-5 SITE LOGISTICS & EROSION CONTROL PLAN.dwg - C5

DISCLAIMER: TS CIVIL ENGINEERING, INC. ONLY ACKNOWLEDGES ORIGINAL SIGNED AND STAMPED PLANS AND DRAWINGS. NO RESPONSIBILITY OR LIABILITY IS EXPRESSED OR IMPLIED FOR ELECTRONIC DATA AND/OR REPRODUCED PLANS AND DRAWINGS.

### 3 Stabilized Construction Entrance/Exit

CASQA Detail TC-1



SECTION B-B  
NTS

NOTE: Construction sediment barrier and channelize runoff to sediment trapping device


Width as required to accommodate anticipated traffic

Temporary pipe culvert as needed

50' MIN  
or four times the circumference of the largest construction vehicle tire, whichever is greater

### 4 Velocity Dissipation Devices

CASQA Detail EC-10



PLAN VIEW


SECTION A-A

\* Length per ABAG Design Standards

Source for Graphics: California Stormwater BMP Handbook, California Stormwater Quality Association, January 2003. Available from www.cabmphandbooks.com.

### 1 Silt Fence

CASQA Detail SE-1



SILT FENCE

CROSS BARRIER DETAIL


SECTION C-C

**NOTES:**

- Construction the length of each reach so that the change in base elevation along the reach does not exceed 1/3 the height of the linear barrier, in no case shall the reach length exceed 500'
- The last 8'-0" at fence shall be turned up slope.
- Stake dimensions are nominal.
- Dimension may vary to fit field condition.
- Stakes shall be spaced at 8'-0" maximum and shall be positioned on downstream side of fence.
- Stake shall be overlap driven tightly together to prevent potential flow-through of sediment at joint. The top of stake shall be secure with wire.
- For end stake, fence fabric shall be folded around two stakes one full turn and secured with 4 staples.
- Minimum 4 staples per stake. Dimensions shown are typical.
- Cross barriers shall be a minimum of 1/3 a maximum at 1/2 the height of the linear barrier.
- Maintenance openings shall be constructed in a manner to ensure sediment remains behind silt fence.
- Joining sections shall not be placed at sump locations.
- Sandbag rows and layers shall be offset to eliminate gaps.

### 2 Silt Fence

CASQA Detail SE-1



JOINING SECTION DETAIL (TOP VIEW)

END STAKE DETAIL (TOP VIEW)

STAPLE DETAIL (SEE NOTE 9)

SECTION A-A

DETAIL A

END DETAIL

OPTIONAL MAINTENANCE OPENING DETAIL (SEE NOTE 11)

### STANDARD BEST MANAGEMENT PRACTICE NOTES

- Solid and Demolition Waste Management:** Provide designated waste collection areas and containers on site away from streets, gutters, storm drains, and waterways, and arrange for regular disposal. Waste containers must be watertight and covered at all times except when waste is deposited. Refer to Erosion & Sediment Control Field Manual, 4th Edition (page C3) or latest. **Hazardous Waste Management:** Provide proper handling and
- Disposal of hazardous wastes** by a licensed hazardous waste material hauler. Hazardous wastes shall be stored and properly labeled in sealed containers constructed of suitable materials. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-5 to C-6) or latest.
- Spill Prevention and Control:** Provide proper storage areas for liquid and solid materials, including chemicals and hazardous substances, away from streets, gutters, storm drains, and waterways. Spill control materials must be kept on site where readily accessible. Spills must be cleaned up immediately and contaminated soil disposed properly. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-7 to C-8, C-13 to C-14) or latest. Vehicle and Construction Equipment Service and Storage:
- An area shall be designated for the maintenance, where on-site maintenance is required, and storage of equipment that is protected from stormwater run-on and runoff. Measures shall be provided to capture any waste oils, lubricants, or other potential pollutants and these wastes shall be properly disposed of off site. Fueling and major maintenance/repair, and washing shall be conducted off-site whenever feasible. Refer to Erosion & Sediment Control Field Manual, 4th Edition (page C9) or latest.
- Material Delivery, Handling and Storage:** In general, materials should not be stockpiled on site. Where temporary stockpiles are necessary and approved by the County, they shall be covered with secured plastic sheeting or tarp and located in designated areas near construction entrances and away from drainage paths and waterways. Barriers shall be provided around storage areas where materials are potentially in contact with runoff. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-11 to C-12) or latest.
- Handling and Disposal of Concrete and Cement:** When concrete trucks and equipment are washed on-site, concrete wastewater shall be contained in designated containers or in a temporary lined and watertight pit where wasted concrete can harden for later removal. If possible have concrete contractor remove concrete wash water from site. In no case shall fresh concrete be washed into the road right-of-way. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-15 to C-16) or latest.
- Pavement Construction Management:** Prevent or reduce the discharge of pollutants from paving operations, using measures to prevent run-on and runoff pollution and properly disposing of wastes. Avoid paving in the wet season and reschedule paving when rain is in the forecast. Residue from saw-cutting shall be vacuumed for proper disposal. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-17 to C-18) or latest.
- Contaminated Soil and Water Management:** Inspections to identify contaminated soils should occur prior to construction and at regular intervals during construction. Remediating contaminated soil should occur promptly after identification and be specific to the contaminant identified, which may include hazardous waste removal. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-19 to C-20) or latest.
- Sanitary/Septic Water Management:** Temporary sanitary facilities should be located away from drainage paths, waterways, and traffic areas. Only licensed sanitary and septic waste haulers should be used. Secondary containment should be provided for all sanitary facilities. Refer to Erosion & Sediment Control Field Manual, 4th Edition (page C-21) or latest.
- Inspection & Maintenance:** Areas of material and equipment storage sites and temporary sanitary facilities must be inspected weekly. Problem areas shall be identified and appropriate additional and/or alternative control measures implemented immediately, within 24 hours of the problem being identified.

### STANDARD EROSION CONTROL NOTES

- Sediment Control Management: Tracking Prevention & Clean Up:** Activities shall be organized and measures taken as needed to prevent or minimize tracking of soil onto the public street system. A gravel or proprietary device construction entrance/exit is required for all sites. Clean up of tracked material shall be provided by means of a street sweeper prior to an approaching rain event, or at least once at the end of each workday that material is tracked, or more frequently as determined by the County Inspector. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages B-31 to B-33) or latest.   
  
 **Storm Drain Inlet and Catch Basin Inlet Protection:** All inlets within the vicinity of the project and within the project limits shall be protected with gravel bags placed around inlets or other inlet protection. At locations where exposed soils are present, staked fiber rolls or staked silt fences can be used. Inlet filters are not allowed due to clogging and subsequent flooding. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages B-49 to B-51) or latest. **Storm Water Runoff:** No storm water runoff shall be allowed to drain in to the existing and/or proposed underground storm drain system or other above ground watercourses until appropriate erosion control measures are fully installed. **Dust Control:** The contractor shall provide dust control in graded areas as required by providing wet suppression or chemical stabilization of exposed soils, providing for rapid clean up of sediments deposited on paved roads, furnishing construction road entrances and vehicle wash down areas, and limiting the amount of areas disturbed by clearing and earth moving operations by scheduling these activities in phases. **Stockpiling:** Excavated soils shall not be placed in streets or on paved areas. Borrow and temporary stockpiles shall be protected with appropriate erosion control measures (trops, straw bales, silt fences, etc.) to ensure silt does not leave the site or enter the storm drain system or neighboring watercourse.
- Erosion Control:** During the rainy season, all disturbed areas must include an effective combination of erosion and sediment control. It is required that temporary erosion control measures are applied to all disturbed soil areas prior to a rain event. During the non-rainy season, erosion control measures must be applied sufficient to control wind erosion at the site.
- Inspection & Maintenance:** Disturbed areas of the Project's site, locations where vehicles enter or exit the site, and all erosion and sediment controls that are identified as part of the Erosion Control Plans must be inspected by the Contractor before, during, and after storm events, and at least weekly during seasonal wet periods. Problem areas shall be identified and appropriate additional and/or alternative control measures implemented immediately, within 24 hours of the problem being identified.
- Project Completion:** Prior to project completion and signoff by the County Inspector, all disturbed areas shall be reseeded, planted, or landscaped to minimize the potential for erosion on the subject site.
- It shall be the Owner's/Contractor's responsibility to maintain control of the entire construction operation and to keep the entire site in compliance with the erosion control plan.
- Erosion and sediment control best management practices shall be operable year round or until vegetation is fully established on landscaped surfaces.
- Grading work between October 15 and April 15 is at the discretion of Santa Clara County building official.
- Exposed slope shall be protected with jute net and/or hydroseed. Hydroseed shall be a homogeneously mix of slurry containing not less than 44 lbs organic mulching amendment plus fertilizer, chemical additives and soils for each 100 gallons of water.

APPROVED FOR ISSUANCE  
REFER TO ENCROACHMENT AND/OR CONSTRUCTION PERMIT AND PLAN COVER SHEET FOR SPECIAL CONDITIONS AND PERMIT NUMBERS

DESIGNED UNDER THE SUPERVISION OF:  
TERENCE J. SZEWCZYK  
REGISTERED PROFESSIONAL ENGINEER  
NO. 35527  
EXP. 9-30-25  
STATE OF CALIFORNIA  
9-17-25  
EXPIRATION DATE: 09/30/25

BEST MANAGEMENT PRACTICES AND EROSION CONTROL DETAILS SHEET 1  
 15201 CAMELOT DRIVE  
 SAN JOSE, CA 95132  
 APN 595-05-005  
 TSCIVIL ENGINEERING, INC.  
 1776 TECHNOLOGY DRIVE  
 SAN JOSE, CA 95110  
 CIVIL ENGINEERING  
 PH: 408-452-9300  
 FAX: 408-837-7550


NO.	REVISIONS	DATE
6		
5		
4		
3		
2		
1		

DATE: 09-22-25  
SCALE: AS NOTED  
DRAWN BY: EB  
SURVEYED BY:  
PROJ ENGR: TJS  
CHECK BY: TJS  
SHEET NO.  
BMP1 OF 7 SHEET  
JOB NO. 25-216

09/23/2025 5:16pm - Z:\2. Email Projects\EM09192025\_02 (TJS - NEED THIS SATURDAY - 1)\S\_Final\25-216 BMP-1.dwg - BT

DISCLAIMER: TS CIVIL ENGINEERING, INC. ONLY ACKNOWLEDGES ORIGINAL SIGNED AND STAMPED PLANS AND DRAWINGS. NO RESPONSIBILITY OR LIABILITY IS EXPRESSED OR IMPLIED FOR ELECTRONIC DATA AND/OR REPRODUCED PLANS AND DRAWINGS.


**7 Geotextiles and Mats**  
CASQA Detail EC-7



- NOTES:
1. Check slots to be constructed per manufacturer's specifications.
  2. Staking or stapling layout per manufacturer's specifications.
  3. Install per manufacturer's recommendations.

**TYPICAL INSTALLATION DETAIL**


**5 Geotextiles and Mats**  
CASQA Detail EC-7



- NOTES:
1. Slope surface shall be free of rocks, clods, sticks and grass.
  2. Mats/blankets shall have good soil contact.
  3. Lay blankets loosely and stake or staple to maintain direct contact with the soil. Do not stretch.
  4. Install per manufacturer's recommendations.

**TYPICAL INSTALLATION DETAIL**


**3 Entrance/Outlet Tire Wash**  
CASQA Detail TC-3



NOTE: Many designs can be field fabricated, or fabricated units may be used.


**TYPICAL TIRE WASH**  
NOT TO SCALE

**1 Fiber Rolls**  
CASQA Detail SE-5




**ENTRENCHMENT DETAIL**  
NOT TO SCALE

**8 Storm Drain Inlet Protection**  
CASQA Detail SE-10




Source for Graphics: California Stormwater BMP Handbook, California Stormwater Quality Association, January 2003. Available from www.cabmphandbooks.com.

**6 Storm Drain Inlet Protection**  
CASQA Detail SE-10




- NOTES:
1. Intended for short-term use.
  2. Use to inhibit non-storm water flow.
  3. Allow for proper maintenance and cleanup.
  4. Bags must be removed after adjacent operation is completed.
  5. Not applicable in areas with high silts and clays without filter fabric.

**4 Storm Drain Inlet Protection**  
CASQA Detail SE-10



- Notes:
1. For use in cleared and grubbed and in graded areas.
  2. Shape basin so that longest inflow area faces longest length of trap.
  3. For concentrated flows, shape basin in 2:1 ratio with length oriented towards direction of flow.

**2 Concrete Waste Management**  
CASQA Detail WM-8



- NOTES:
1. ACTUAL LAYOUT DETERMINED IN FIELD.
  2. THE CONCRETE WASHOUT SIGN SHALL BE INSTALLED WITHIN 30FT. OF THE TEMPORARY CONCRETE WASHOUT FACILITY.

APPROVED FOR ISSUANCE  
REFER TO ENCROACHMENT AND/OR CONSTRUCTION PERMIT AND PLAN COVER SHEET FOR SPECIAL CONDITIONS AND PERMIT NUMBERS

DESIGNED UNDER THE SUPERVISION OF:  
**TERENCE J. SZWCZYNSKI**  
REGISTERED PROFESSIONAL ENGINEER  
NO. 35527  
EXP. 9-30-25  
STATE OF CALIFORNIA  
9-17-25

**BEST MANAGEMENT PRACTICES AND EROSION CONTROL DETAILS SHEET 2**  
15201 CAMELOT DRIVE  
SAN JOSE, CA 95132  
APN 595-05-005

NO.	DATE	REVISIONS	BY
6			
5			
4			
3			
2			
1			

DATE: 09-22-25

SCALE: AS NOTED

DRAWN BY: EB

SURVEYED BY:

PROJ ENGR: TJS

CHECK BY: TJS

SHEET NO.

**BMP2**  
OF 7 SHEET

JOB NO.

25-216

TSCIVIL ENGINEERING, INC.  
1776 TECHNOLOGY DRIVE  
SAN JOSE, CA 95110  
**TS** CIVIL ENGINEERING  
PH: 408.452.9300  
FAX: 408.837.7550

09/23/2025 5:17pm - Z: V2: Email Projects\EM09192025\_02 (TUS - NEED THIS SATURDAY - 1)\S\_Final\25-216 BMP-2.dwg - B2